
STATE OF UTAR DIVISION OF OIL, GAS AND MINING

DIVISION	OF OIL, GAS	ANI	DMINING				5, LEASE DESIGNATION AND SERIAL NO. ML-16532	
ADDI ICATION EO	D DEDMIT TO	DDII	LI DEEDEN				6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
APPLICATION FO			LL, DEEPEN				N/A	
a. TYPE OF WORK DRILL	x DEEF	EN					7. UNIT AGREEMENT NAME	
b. TYPE OF WELL			SINGLE	MULTI	IDI E		N/A 8. FARM OR LEASE NAME	
OIL X GAS	ОТНЕ	R		ZONE	TLE	7	N/A	
. NAME OF OPERATOR	<u> </u>	 					9. WELL NO.	
Newfield Production Co					<u> </u>		State #5-16-9-16	
ADDRESS AND TELEPHONE NUME Route #3 Box 3630, Myt			Phon	o. (13	5) 646-3721		10. FIELD AND POOL OR WILDCAT Monument Butte	
LOCATION OF WELL (FOOTAGE)			I none	c. (43	3) 040-3721		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:	
At Surface SW/N	W 2043' FNL	758' F	WL					
At proposed Producing Zone 574			2516				SW/NW	
4. DISTANCE IN MILES AND DIRECT	315187		110.130428		<u> </u>	<u> </u>	Sec. 16, T9S, R16E 12. County 13. STATE	
Approximately 22.1 mile							Duchesne UT	
5. DISTANCE FROM PROPOSED* LO		ERTY	16. NO, OF ACRES IN LEASE		17, NO. OF ACRES	S ASSIGNE	ED TO THIS WELL	
OR LEASÉ LINE, FT. (Also to nearest	- · · · · · · · · · · · · · · · · · · ·		640.00		40	`		
	pprox. 758' f/lse line and NA' f/unit line 640.00 40 DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, 19. PROPOSED DEPTH 20. ROTARY OR CAB.						OLS	
DRILLING, COMPLETED, OR APPI		r.	(500)		D-4-			
Approximately 14			6500'		Rota	T	ON PARE WORK WILL GRAPE	
5922' GL	I, GK, etc.)						OX. DATE WORK WILL START* UArter 2008	
	CASING AND C	EMI	ENTING PROG	RAN	1	1200 €		
SIZE OF HOLE	SIZE OF CASING	WEIGHT/E	FOOT	SETTING DEPTH		QUANTI	TY OF CEMENT	
12 1/4	8 5/8	24#		290	400	155 sx +/- 10%		
7 7/8	5 1/2	15.5#		· · · · · · · · · · · · · · · · · · ·		275 sx lead followed by 450 sx tail		
<u> </u>						See D	Petail Below	
wbsurface locations and measured are the actual cement volusion. SURFACE PIPE - 155 s.	nd true vertical depths. Give to the true vertical depths. Give to the true will be calculated as Class G Cement +	olowout p ated o	ff of the open hole	logs, p /4#/sk	olus 15% exe		osal is to drill or deepen directionally, give pertinent data	ion
10% E	Bentonite + .5% Soc	lium N	Metasilicate		l + .25 lbs/sk q: 21.04 gal		Flake + 2 lbs/sk Kol Seal +	
					ello Flake + eq: 7.88 gal/		ntonite + .3% Sodium Metasilicate	
A. Name & Signature Mandie Cro	indictory ozier	ju	Title: Regulatory	Specia	alist	Date:	11/19/2007	
(This space for State use only)			The state of the s		·			
API Number Assigned:	43-013-3384	9	APPROVAL:			v =/**		
Approved Utah Divi Oil, Gas an	ision of		*See Instruction	ns On	Reverse S	ide	RECEIVED NOV 2 9 2007	

DIV. OF OIL, GAS & MINING

T9S, R16E, S.L.B.&M.

 $N89^{\circ}50'W - 80.24$ (G.L.O.)





= SECTION CORNERS LOCATED


BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SW) 9 MILE 5-16-9-16 (Surface Location) NAD 83 LATITUDE = 40° 01' 57.02" LONGITUDE = 110° 07' 51.79"

(C.L.O.)

N00.02,W

NEWFIELD PRODUCTION COMPANY

WELL LOCATION, 9 MILE 5-16-9-16, LOCATED AS SHOWN IN THE SW 1/4 NW 1/4 OF SECTION 16, T9S, R16E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT OF HE ABOVE PREST WAS PREPARED FROM FIELD OF ACTUME SURVEYS MADE BY ME OR UNDER MY SUPPROBLEM AND STREET TO THE BEST OF MY KNOWLEDGE AND FILES No. 189377



TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078 (435) 781-2501

DATE SURVEYED: 10-10-07	SURVEYED BY: C.M.
DATE DRAWN: 10-31-07	DRAWN BY: F.T.M.
REVISED:	SCALE: 1" = 1000'

NEWFIELD PRODUCTION COMPANY STATE #5-16-9-16 SW/NW SECTION 16, T9S, R16E DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

Uinta 0-1700' Green River 1700' Wasatch 6500'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River Formation 1700' - 6500' - Oil

4. **PROPOSED CASING PROGRAM:**

Surface Casing: 8-5/8" J-55 24# w/ST&C collars; set at 290 (New)
Production Casing:5-1/2" J-55, 15.5# w/LT&C collars; set at TD (New or used, inspected).

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to Exhibit C for a diagram of BOP equipment that will be used on this well.

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

A fresh water/polymer system will be utilized to drill the well. If necessary, to control formation fluids, the system will be weighted with the addition of bentonite gel, and if conditions warrant, barite. This fresh water system typically will contain Total Dissolved Solids (TDS) of less than 3000 PPM. Neither potassium chloride nor chromates will be utilized in the fluid system. The anticipated mud weight is 8.4 ppg and weighted as necessary for gas control.

AIR DRILLING

In the event that the proposed location is to be "Air Drilled", Newfield requests a variance to regulations requiring a straight run blooie line. Newfield proposes that the flowline will contain two (2) 90-degree turns. Newfield also requests a variance to regulations requiring an automatic igniter or continuous pilot light on the blooie line. Newfield requests authorization to ignite as needed, and the flowline at 80'.

Newfield Production Company requests that the spark arrest, exhaust, or water cooled exhaust be waived under the Special Drilling Operations of Onshore Order #2.

Ten Point Well Program
Thirteen Point Well Program
Page 2 of 7

MUD PROGRAM

MUD TYPE

Surface - 3200'

fresh water system

3200' - TD'

fresh water system

From surface to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCL substitute additive. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite. No chromate additives will be used in the mud system.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. TESTING, LOGGING AND CORING PROGRAMS:

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @290° +/-, and a Compensated Neutron-Formation Density Log from TD to 3500° +-. A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

The anticipated maximum bottom hole pressure is 1800 psi. It is not anticipated that abnormal temperatures will be encountered; or that any other abnormal hazards such as H2S will be encountered in this area.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

It is anticipated that the drilling operations will commence the first quarter of 2008, and take approximately seven (7) days from spud to rig release.

Ten Point Well Program
Thirteen Point Well Program
Page 3 of 7

NEWFIELD PRODUCTION COMPANY STATE #5-16-9-16 SW/NW SECTION 16, T9S, R16E DUCHESNE COUNTY, UTAH

THIRTEEN POINT SURFACE PROGRAM

1. **EXISTING ROADS**

See attached Topographic Map "A"

To reach Newfield Production Company well location site State #5-16-9-16 located in the SW¹/₄ NW¹/₄ Section 16, T9S, R16E, S.L.B. & M., Duchesne County, Utah:

Proceed in a southwesterly direction out of Myton, Utah along Highway 40 approximately 1.4 miles to the junction of this highway and Utah State Highway 53; proceed southerly along Utah State Highway 53 approximately 1.7 miles to its junction with an existing road to the southwest; proceed southwesterly approximately 9.7 miles to its junction with an existing road to the southeast; proceed southeasterly approximately 0.3 miles to its junction with an existing road to the northeast; proceed northeasterly approximately 5.1 miles to its junction with and existing road to the southwest; proceed southwesterly approximately 1.8 miles to its junction with an existing road to the northwest; proceed in a northwesterly direction approximately 1.4 miles to its junction with the beginning of the proposed access road to the south; proceed southwesterly along the proposed access road approximately 2,640'; turn and proceed in a southwesterly direction along the proposed access road approximately 930' to the proposed well location.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to the point where Highway 216 exists to the South, thereafter the roads are constructed with existing materials and gravel. The highways are maintained by Utah State road crews. All other roads are maintained by County crews.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal.

2. PLANNED ACCESS ROAD

Approximately 3,570' of access road is proposed. See attached Topographic Map "B".

The proposed access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%.

There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

Ten Point Well Program
Thirteen Point Well Program
Page 4 of 7

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. **LOCATION OF EXISTING WELLS**

Refer to EXHIBIT B.

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted Desert Tan. All facilities will be painted within six months of installation.

5. LOCATION AND TYPE OF WATER SUPPLY

Fresh water purchased from the Johnson Water District will be used for drilling. A temporary poly pipeline may be used for water transportation from our existing supply line from Johnson Water District, or trucked from Newfield Production Company's injection facilities – **EXHIBIT** A.

There will be no water well drilled at this site.

6. SOURCE OF CONSTRUCTION MATERIALS

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. METHODS FOR HANDLING WASTE DISPOSAL

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

Ten Point Well Program
Thirteen Point Well Program
Page 5 of 7

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

8. <u>ANCILLARY FACILITIES</u>:

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT:**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. PLANS FOR RESTORATION OF SURFACE:

a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP:** State of Utah

12. OTHER ADDITIONAL INFORMATION:

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

The Archaeological Cultural Resource Survey Report is attached. Refer to Exhibit "D".

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the State 5-16-9-16, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the State 5-16-9-16 Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office shall be notified upon site completion prior to moving on the drilling rig.

Ten Point Well Program
Thirteen Point Well Program
Page 7 of 7

13. LESSEE'S OR OPERATOR'S REPRENSENTATIVE AND CERTIFICATION:

Representative

Name:

Dave Allred

Address:

Newfield Production Company

Route 3, Box 3630

Myton, UT 84052

Telephone:

(435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #5-16-9-16, SW/NW Section 16, T9S, R16E, LEASE #ML-16532, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Hartford Accident #4471291.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.


11/19/07

Date

Mandie Crozier

Regulatory Specialist

Newfield Production Company




NEWFIELD PRODUCTION COMPANY CROSS SECTIONS 9 MILE 5-16-9-16 20, ٠Ì STA. 2+90 1" = 50' \parallel STA. 2+20 1" = 50'EXISTING **GRADE** FINISHED GRADE 20, jj. WELL HEAD 1" = 50'STA. 1+60 20, - [] 1" = 50'STA. 0+00 ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards) CUT FILL 6" TOPSOIL **EXCESS** ITEM Topsoil is not included in Pad Cut PAD 6,110 4,520 1,590 NOTE: UNLESS OTHERWISE NOTED PIT 640 640 0 CUT SLOPES ARE AT 1:1 6,750 **TOTALS** 4,520 1,050 2,230 FILL SLOPES ARE AT 1.5:1


 SURVEYED BY:
 C.M.
 DATE SURVEYED:
 10-10-07


 DRAWN BY:
 F.T.M.
 DATE DRAWN:
 10-31-07


 SCALE:
 1" = 50"
 REVISED:


 $egin{array}{lll} egin{array}{lll} Tri & State & {}^{(435)} & {}^{781-2501} \ & Land & Surveying, & Inc. \ & _ & 180 & NORTH & VERNAL & AVE. & VERNAL, & UTAH & 84078 \end{array}$














2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

Exhibit "D"

CULTURAL RESOURCE INVENTORY OF NEWFIELD EXPLORATION'S TEN 40 ACRE PARCELS IN TOWNSHIP 9S, RANGE 16E, SECTION 16 DUCHESNE COUNTY, UTAH

By:

Jacki A. Montgomery

Prepared For:

State of Utah
School & Institutional Trust Lands Administration
Salt Lake City

Prepared Under Contract With:

Newfield Exploration Company Rt. 3 Box 3630 Myton, UT 84052

Submitted By:

Keith R. Montgomery Montgomery Archaeological Consultants, Inc. P.O. Box 219 Moab, Utah 84532

MOAC Report No. 07-348


October 31, 2007

United States Department of Interior (FLPMA)
Permit No. 07-UT-60122

State of Utah Public Lands Policy Archaeological Survey Permit No. 117

State of Utah Antiquities Project (Survey)
Permit No. U-07-MQ-1297s

APD RECEIVED: 11/29/2007	API NO. ASSIGNED: 43-013-33849
WELL NAME: STATE 5-16-9-16	
OPERATOR: NEWFIELD PRODUCTION (N2695)	PHONE NUMBER: 435-646-3721
CONTACT: MANDIE CROZIER	
PROPOSED LOCATION:	INSPECT LOCATN BY: / /
SWNW 16 090S 160E	
SURFACE: 2043 FNL 0758 FWL	Tech Review Initials Date
BOTTOM: 2043 FNL 0758 FWL	Engineering DKN 1/24/08
COUNTY: DUCHESNE	Geology
LATITUDE: 40.03252 LONGITUDE: -110.1304 UTM SURF EASTINGS: 574194 NORTHINGS: 443151	Surface
FIELD NAME: MONUMENT BUTTE (105)	
LEASE TYPE: 3 - State LEASE NUMBER: ML-16532 SURFACE OWNER: 3 - State	PROPOSED FORMATION: GRRV COALBED METHANE WELL? NO
Plat Bond: Fed[] Ind[] Sta[] Fee[] (No. B001834) Potash (Y/N) Oil Shale 190-5 (B) or 190-3 or 190-13 Water Permit (No. MUNICIPAL) RDCC Review (Y/N) (Date:) PROCE Surf Agreement (Y/N) Intent to Commingle (Y/N)	LOCATION AND SITING: R649-2-3. Unit:
STIPULATIONS: I Pacing Service 2- Stateman 3-50 Jaco Csa	(12-13-07) wr of Basis Contstip



Application for Permit to Drill

Statement of Basis

12/19/2007

Utah Division of Oil, Gas and Mining

Page 1

APD No

Operator

API WellNo

Status

Well Type OW

Surf Ownr S

CBM No

630

43-013-33849-00-00 NEWFIELD PRODUCTION COMPANY

Surface Owner-APD

Well Name STATE 5-16-9-16

Unit

Field

MONUMENT BUTTE

Type of Work

Location

SWNW 16 9S 16E S 2043 FNL 758 FWL

GPS Coord (UTM) 574194E 4431518N

Geologic Statement of Basis

Newfield proposes to set 290' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 2,900'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 16. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought high enough to cover the estimated base of the moderately saline ground water.

Brad Hill

12/19/2007

APD Evaluator

Date / Time

Surface Statement of Basis

The general area is approximately 22 miles southwest of Myton, Utah in the upper Castle Peak area. Castle Peak Draw runs in a northeasterly direction about 14 miles and joins Pariette Draw. Pariette Draw continues in a southeasterly direction about 6 miles and joins the Green River about 6 miles below Ouray Utah. Pariette Draw contains a perennial stream somewhat consisting of irrigation runoff and seepage. No streams springs or seeps occur in the area. An occasional pond constructed to store runoff for livestock or wildlife exists. Drainages are ephemeral only flowing during spring snowmelt or following intense summer rainstorms. Broad flats or rolling topography intersected by drainages with gentle to moderate side-slopes characterize the area. Access to the area from Myton, Utah is following State of Utah Hwy. 40 and Duchesne County and oilfield development roads a distance of 22.1 miles. Construction of 930 feet of new road will be required.

The proposed State #5-16-9-16 oil well location is in a small bowl that drains gently to the northeast. The bowl is surrounded on 3 sides by low hills with bedrock outcrops. The reserve pit will be cut into the hill on the west. Most of the location is in gentle terrain. Slight overland flow may occasionally occur from the south but most will be intercepted by the location topsoil stockpile. No diversions are recommended. The selected site poses no apparent surface concerns and appears to be a good location for constructing a pad, drilling and operating a well. The area was covered with about 10 inches of snow during the evaluation. Both the surface and minerals are owned by SITLA.

Daniel Emmett representing the Utah Division of Wildlife Resources stated the area is classified as substantial value sage grouse brooding habitat and crucial yearlong antelope habitat. He ask Mr. Allred of Newfield and Mr. Davis of SITLA that they try to schedule construction and drilling around the critical period of March 1 to June 15th for sagegrouse brooding. No restrictions for the antelope were requested. No other wildlife are expected to be significantly affected. Mr. Emmett gave Mr. Allred of Newfield Production Company and Mr. Davis of SITLA a copy of his evaluation and also a seed mix recommendation to be used when the reserve pit and location are reclaimed.

Floyd Bartlett

12/13/2007

Onsite Evaluator

Date / Time

Application for Permit to Drill Statement of Basis

12/19/2007

Utah Division of Oil, Gas and Mining

Page 2

Conditions of Approval / Application for Permit to Drill

Category

Condition

Pits

A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be

properly installed and maintained in the reserve pit.

Surface

The reserve pit shall be fenced upon completion of drilling operations.

Utah Division of Oil, Gas and Mining

Operator

NEWFIELD PRODUCTION COMPANY

Well Name

STATE 5-16-9-16

API Number

43-013-33849-0

APD No 630

Tw

Field/Unit MONUMENT BUTTE

Location: 1/4,1/4 SWNW

Sec 16

9S **Rng** 16E

2043 FNL 758 FWL

GPS Coord (UTM) 574203

4431525

Surface Owner

Participants

Floyd Bartlett (DOGM), David Allred (Newfield Production Company), Cory Miller (Tri-State Land Surveying), Jim Davis (SITLA), Daniel Emmett (Utah Division of Wildlife Resources).

Regional/Local Setting & Topography

The general area is approximately 22 miles southwest of Myton, Utah in the upper Castle Peak area. Castle Peak Draw runs in a northeasterly direction about 14 miles and joins Pariette Draw. Pariette Draw continues in a southeasterly direction about 6 miles and joins the Green River about 6 miles below Ouray Utah. Pariette Draw contains a perennial stream somewhat consisting of irrigation runoff and seepage. No streams springs or seeps occur in the area. An occasional pond constructed to store runoff for livestock or wildlife exists. Drainages are ephemeral only flowing during spring snowmelt or following intense summer rainstorms. Broad flats or rolling topography intersected by drainages with gentle to moderate side-slopes characterize the area. Access to the area from Myton, Utah is following State of Utah Hwy. 40 and Duchesne County and oilfield development roads a distance of 22.1 miles. Construction of 930 feet of new road will be required.

The proposed State #5-16-9-16 oil well location is in a small bowl that drains gently to the northeast. The bowl is surrounded on 3 sides by low hills with bedrock outcrops. The reserve pit will be cut into the hill on the west. Most of the location is in gentle terrain. Slight overland flow may occasionally occur from the south but most will be intercepted by the location topsoil stockpile. No diversions are recommended. The selected site poses no apparent surface concerns and appears to be a good location for constructing a pad, drilling and operating a well. The area was covered with about 10 inches of snow during the evaluation. Both the surface and minerals are owned by SITLA.

Surface Use Plan

Current Surface Use

Grazing

Recreational

Wildlfe Habitat

New Road

Miles Well Pad

Src Const Material

Surface Formation

0.09

Width 199

Length 290

Onsite

UNTA

Ancillary Facilities N

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetland N

Flora / Fauna

Area was covered with snow. Vegetation is a Deseret shrub type. Identified or expected vegetation consisted of black sagebrush, shadscale, greasewood, mustard weed, rabbit brush, horsebrush, broom snakeweed, and spring annuals.

Cattle, prairie dogs, antelops, small mammals and birds. Golden eagle have been sited in the general area.

Soil Type and Characteristics

Moderately shallow sandy clay loam with some surface rock.

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diverson Required N

Berm Required? N

Erosion Sedimentation Control Required? N

Slight overland flow may occasionally occur from the south but most will be intercepted by the location topsoil stockpile. No diversions are recommended.

Paleo Survey Run? Y

Paleo Potental Observed? N

Cultural Survey Run? Y

Cultural Resources? N

Reserve Pit

Site-Specific Factors		Site 1	Ranking		
Distance to Groundwater (feet)	>200		0		
Distance to Surface Water (feet)	>1000		0		
Dist. Nearest Municipal Well (ft)	>5280		0		
Distance to Other Wells (feet)	300 to 1320		10		
Native Soil Type	Mod permeability		10		
Fluid Type	Fresh Water		5		
Drill Cuttings	Normal Rock		0		
Annual Precipitation (inches)	<10		0		
Affected Populations	<10		0		
Presence Nearby Utility Conduits	Not Present		0		
		Final Score	25	1	Sensitivity Level

Characteristics / Requirements

A 40' x 80' x 8' deep reserve pit is planned in an area of cut on the northwest side of the location. A pit liner is required. Newfield commonly uses a 16 mil liner.

Closed Loop Mud Required? N Liner Required? N Liner Thickness 16 Pit Underlayment Required? N

Other Observations / Comments

ATV's used to reach site. Site under 10 inches of snow.


Floyd Bartlett

12/13/2007

Evaluator

Date / Time

2008-01 Newfield State 5-16-9-16



BOPE REVIEW

Well Name	Newfield State 5-16-9-16 API# 43-013-33849
INPUT	
Well Name	Newfield State 5-16-9-16 API# 43-013-33849
	String 1 String 2 String 3 String 4
Casing Size (")	20 13 3/8
Setting Depth (TVD)	400 6500
Previous Shoe Setting Depth (TVD)	0 400 0 0
Max Mud Weight (ppg)	8.4 8.4
BOPE Proposed (psi)	0 2000
Casing Internal Yield (psi)	2950 4810

Calculations	String 1	20	14	·
Max BHP [psi]	.052*Setting Depth*MW =	175	1	
			BOPE Adequate	For Drilling And Setting Casing at Depth?
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	127	NO	
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	87		No expected pressures @ Set dept 4
			*Can Full Expect	ted Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth) =	. 87		
Required Casing/BOPE Test	Pressure	400	psi	
*Max Pressure Allowed @ Pi	0	psi	*Assumes 1psi/ft frac gradient	

Calculations	String 2	13 3/8 "	
	05010 - 11 - 12 - 11 - 11 - 11	0000	
Max BHP [psi]	.052*Setting Depth*MW =	2839 BOPE Adequate For Drilling And Setting Casing at Depth?	
		BOPE Adequate For Drining And Setting Casing at Deptire	
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	2059 NO	
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	1409 YES	
		*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth) =	(149) (NO)	
Required Casing/BOPE Test	Pressure	2000 psi / i	
Max Pressure Allowed @ P	revious Casing Shoe =	400 p3i 4 *Assumes 1psi/ft frac gradient	

Well name:

2008-01 Newfield State 5-16-9-16

Operator:

Newfield Production Company

String type:

Surface

Project ID:

43-013-33849

Location:

Duchesne County

Minimum design factors:

Environment:

Collapse

Mud weight:

Design parameters:

Collapse: Design factor

H2S considered? 1.125

No 75 °F

8.400 ppg Design is based on evacuated pipe.

Surface temperature: Bottom hole temperature:

81 °F

Temperature gradient: Minimum section length: 1.40 °F/100ft 290 ft

Burst:

Design factor

1.00

Cement top:

153 ft

Burst

Max anticipated surface

pressure: Internal gradient: 352 psi 400 psi

Calculated BHP

No backup mud specified.

0.120 psi/ft Tension:

> 8 Round STC: 8 Round LTC:

Buttress:

1.80 (J) 1.80 (J) 1.60 (J)

Premium: Body yield: 1.50 (J) 1.50 (B) Non-directional string.

Tension is based on buoyed weight. Neutral point: 349 ft

Re subsequent strings:

Next setting depth: Next mud weight: Next setting BHP:

6.500 ft 8.400 ppg 2.836 psi

Fracture mud wt: Fracture depth: Injection pressure: 19.250 ppg 400 ft 400 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	400	8.625	24.00	J-55	ST&C	400	400	7.972	143
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	i̇̃75´	1370	7.851	"40Ó	2950	7.38	8	244	29.09 J

Prepared

Helen Sadik-Macdonald Div of Oil, Gas & Minerals Phone: 801-538-5357 FAX: 801-359-3940

Date: January 11,2008 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 400 ft, a mud weight of 8.4 ppg The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:

2008-01 Newfield State 5-16-9-16

Operator:

Newfield Production Company

String type:

Production

Project ID:

43-013-33849

Location:

Collapse

Duchesne County

Design parameters:

Mud weight: 8.400 ppg Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor

Environment:

H2S considered?

No

Surface temperature: Bottom hole temperature: 75 °F

Temperature gradient:

166 °F 1.40 °F/100ft

Minimum section length: 1,500 ft

Non-directional string.

Burst:

Design factor

1.00

1.125

Cement top:

103 ft

Burst

Max anticipated surface

No backup mud specified.

pressure: Internal gradient: 1,406 psi

Calculated BHP

0.220 psi/ft

2,836 psi

Tension: 8 Round STC:

1.80 (J)

8 Round LTC:

1.80 (J) **Buttress:** 1.60 (J)

Premium: Body yield: 1.50 (J)

1.50 (B)

Tension is based on buoyed weight. Neutral point:

5.674 ft

Run	Segment		Nominal		End	True Vert	Measured	Drift	Internal
Seq	Length (ft)	Size (in)	Weight (lbs/ft)	Grade	Finish	Depth (ft)	Depth (ft)	Diameter (in)	Capacity (ft³)
1	6500	5.5	15.50	J-55	LT&C	6500	6500	4.825	868.6
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	2836	4040	1.424	2836	4810	1.70	` 8 8 ´	217	2.47 J

Prepared

Helen Sadik-Macdonald Div of Oil, Gas & Minerals Phone: 801-538-5357 FAX: 801-359-3940

Date: January 11,2008 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6500 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

From:

Ed Bonner

To:

Mason, Diana

Date:

1/8/2008 12:05 PM

Subject:

Well Clearance

CC:

Davis, Jim; Garrison, LaVonne; Hill, Brad; Jarvis, Dan

The following wells have been given cultural resources clearance by the Trust Lands Cultural Resources Group:

ConocoPhillips Company

Utah 29-574D (API 43 015 30735)

EOG Resources, Inc

CWU 956-32 (API 43 047 39515)

Kerr McGee Oil & Gas Onshore LP

NBU 1021-2N (API 43 047 38840)

Newfield Production Company

Wells Draw Fed C-5-9-16 (API 43 013 33753)

State 1A-16-9-16 (API 43 013 33845)

State 2A-16-9-16 (API 43 013 33846)

State 3-16-9-16 (API 43 013 33847)

State 4-16-9-16 (API 43 013 33848)

State 5-16-9-16 (API 43 013 33849)

State 6-16-9-16 (API 43 013 33850)

State 12-16-9-16 (API 43 013 33852)

State 13-16-9-16 (API 43 013 33853)

State 16-16-9-16 (API 43 013 33854)

Pioneer Natural Resources USA, Inc

Main Canyon State 12-16-15-23 (API 43 047 39695)

Main Canyon State 34-21-15-23 (API 43 047 39696)

Horse Point State 34-10-16-23 (API 43 019 31558)

Horse Point State 41-1-16-23 (API 43 019 31599)

Grand Canyon State 23-35-15.5-23 (API 43 019 31560)

If you have any questions regarding this matter please give me a call.

Helen Sadik-Macdonald - Newfield wells

"Hans Wychgram"

To: Date:

CC:

01/09/2008 3:52 PM

Subject: Newfield wells

"Brad Mecham", "Mandie Crozier"

Helen,

As per our conversation this afternoon, Newfield agrees to set 400' of surface casing on the following wells:

State 3-16-9-16

State 4-16-9-16

State 5-16-9-16

State 6-16-9-16

State 11-16-9-16

State 12-16-9-16

State 13-16-9-16

State 16-16-9-16

Gilsonite L-32-8-17

Monument Butte F-36-8-16

Also, we discussed setting 300' of 20" conductor casing on the following deep gas wells:

Beluga 16T-5-9-17

Monument Butte 4-36T-8-16

Thanks,

Hans Wychgram



GARY R. HERBERT Lieutenant Governor

MICHAEL R. STYLER

State WUtah

DEPARTMENT OF NATURAL RESOURCES

Executive Director

Division of Oil Gas and Mining

JOHN R. BAZA Division Director

January 24, 2008

Newfield Production Company Rt. #3, Box 3630 Myton, UT 84052

Re:

State 5-16-9-16 Well, 2043' FNL, 758' FWL, SW NW, Sec. 16, T. 9 South, R. 16 East,

Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann.§ 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-33849.

Sincerely,

Gil Hunt

Associate Director

pab

Enclosures

cc:

Duchesne County Assessor

SITLA



Operator:	Newfield Production Company					
Well Name & Number	State 5-16-9-16					
API Number:	43-013-33849					
Lease:	ML-16532					
Location: SW NW	Sec. 16 T. 9 South R. 16 East					

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis
- 24 hours prior to spudding the well contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well contact Dustin Doucet
- Any changes to the approved drilling plan contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

• Dan Jarvis at:

(801) 538-5338 office

(801) 942-0873 home

• Carol Daniels at:

(801) 538-5284 office

• Dustin Doucet at:

(801) 538-5281 office

(801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

Page 2 43-013-33849 January 24, 2008

- 4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
- 5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
- 6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
- 7. Surface casing shall be cemented to the surface.

STATE OF UTAH

DIVISION OF OIL, GAS, AND MINIT	5. LEASE DESIGNATION AND SERIAL NO. ML-16532					
1. SUNDRY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBAL NAME				
Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plu Use "APPLICATION FOR PERMIT TO DRILL OR DEEPEN form		N/A				
	ii toi suon proposais.	7. UNIT AGREEMENT NAME				
OIL GAS WELL X OTHER	NA					
2. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY		8. WELL NAME and NUMBER STATE 5-16-9-16				
3. ADDRESS AND TELEPHONE NUMBER Rt. 3 Box 3630, Myton Utah 84052 435-646-3721		9 API NUMBER 43-013-33849				
4. LOCATION OF WELL		10 FIELD AND POOL, OR WILDCAT				
Footages 2043 FNL 758 FWL		MONUMENT BUTTE				
QQ, SEC, T, R, M: SW/NW Section 16, T9S R161	E					
23,020, 1,14,111		COUNTY DUCHESNE STATE UTAH				
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF N	NOTICE, REPORT OR OTHE					
NOTICE OF INTENT:		NT REPORT OF:				
(Submit in Duplicate)	(Submi	t Original Form Only) NEW CONSTRUCTION				
ABANDONNEW CONSTRUCTION	REPAIR CASING					
REPAIR CASING PULL OR ALTER CASING	CHANGE OF PL					
CHANGE OF PLANS RECOMPLETE	CONVERT TO I					
CONVERT TO INJECTION REPERFORATE		FRACTURE TREAT OR ACIDIZE VENT OR FLARE				
FRACTURE TREAT OR ACIDIZE VENT OR FLARE	FRACTURE TREAT	OR ACIDIZE VEINT OR FLARE				
MULTIPLE COMPLETION WATER SHUT OFF	OTHER					
X OTHER APD Change	DATE WORK COMPI					
	•	ole Completion and Recompletions to different OMPLETION OR RECOMPLETION REPORT AND				
	LOG form.					
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertin	*Must be accompanies nent details, and give pertinent da	by a cement verification report. tes. If well is directionally drilled, give subsurface locations				
and measured and true vertical depth for all markers and zones pertinent to this work.						
Newfeild Production requests the following change APD.	iges be made the dr	illing program on the above mentioned approved				
Surface Casing will be set @ 290'.						
^						
13. NAME & SIGNATURE: Mandie Crozier TITLE	Regulatory Special	ist DATE 3/7/2008				
(This space for State use only)						
4/94 A DODOVED DV THE C Technistictions	On Reverse Side	•				
494APPROVED BY THE S下午中的 OF UTAH DIVISION OF						
OIL. GAS. AND MINING		COPY SENT TO OPERATOR				
DATE 3/14/08 4		210000				
BY: John Wall	RECEIVED	146				
DI.	MAR 1 2 2008	Initials: <u>48</u>				

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company:		NEWFIELD PRODUCTION COMPANY						
Well Name:		ST	TATE 5-	<u>16-9-16</u>	<u> </u>		-	
Api No:	9]	Lease T	ype:	STATE	ı		
Section_16	Township_	09S	_Range_	16E	County_	DUCH	IESNE	
Drilling Cor	ntractor	ROSS	DRILLI	ING _		RIG #	24	
SPUDDE	D:							
	Date	04/07/	08					
	Time	3:30	PM	•				
	How	DRY						
Drilling wi	II Commence	ə:						
Reported by	-	JIM	SMITH					·
Telephone#		(435) 823-20	72				
Date	04/08/08	9	Signed	CF	łD			

A W

FORM APPROVED OMB No. 1004-0135 Expires January 31,2004

FORM 3160-5

(September 2001)

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

UTAH STATE ML-16532 6. If Indian, Allottee or Tribe Name.

5. Lease Serial No.

aballuolleu w	en. Ose i omi o ioo-o (Ai	D) for such proposa		1	
	RIPLICATE - Other Inst	ructions on reverses	ide	7. If Unit or CA/A	Agreement, Name and/or
I. Type of Well ☐ Gas Well ☐	Other			8. Well Name and	J No.
2. Name of Operator	- Other			STATE 5-16-	
NEWFIELD PRODUCTION CO	MPANY	·		9. API Well No.	
3a. Address Route 3 Box 3630		3b. Phone (include a	re code)	4301333849	
Myton, UT 84052	g	435.646.3721		1	ol, or Exploratory Area
4. Location of Well (Footage, 2) 2043 FNL 758 FWL	Sec., T., R., M., or Survey Descrip	otton)		MONUMENT 11. County or Par	
				Tr. County of run	non, out
SWNW Section 16 T9S R16E				DUCHESNE, U	UT
12. CHECK	APPROPRIATE BOX(E	S) TO INIDICATE N	ATURE OF N	OTICE, OR OT	ΓHER DATA
TYPE OF SUBMISSION		TY	PE OF ACTION		
	Acidize	Deepen	Productio	n(Start/Resume)	■ Water Shut-Off
■ Notice of Intent	☐ Alter Casing	Fracture Treat	Reclamati	ion	Well Integrity
Subsequent Report	Casing Repair	■ New Construction	Recomple	te	X Other
granderstanding the state of th	Change Plans	Plug & Abandon		ily Abandon	Weekly Status Report
Final Abandonment	Convert to	☐ Plug Back	Water Dis	sposal	
on 4/11/08 MIRU NDSI R csgn to 1,500 psi. Vernal cement & shoe. Drill a 7.8 log's TD to surface. PU & with 300 sks cement mixe cement to reserve pit. Nip	filed only after all requirements, including # 3. Set all equipment. Filed # 3. Set all equipment. Filed # 3. Set all equipment. Filed # 4. Roosevelt DO # 5. Tiled with fresh water to # 5. TIH with Guide shoe, shoe # 6. TIH with Guide shoe, shoe # 6. TIH with Guide shoe, shoe # 7. Tiled # 5. Tile	Pressure test Kelly, TI GM office was notifed a depth of 5825'. Lay jt, float collar, 139 jt's The 400 sks cement m (@ 105,000 #'s tension	W, Choke man I of test. PU BH down drill strin s of 5.5 J-55, 15 ixed @ 14.4 pp	ifold, & Bop's to IA and tag cem Ig & BHA. Oper 5.5# csgn. Set (Ig & 1.24 yld. F	o 2;000 psi. Test 8.625 lent @ 285'. Drill out n hole log w/ Dig/SP/GR @ 5820.73' / KB. Cement Returned 2 bbls of
I hereby certify that the foregoing is correct (Printed/ Typed)	true and	Title			
Jim Strith 4 Mg		Drilling Forer	nan		
Signature 10 1500		Date 04/16/2008			
In strong and a series	THIS SPACE FO	R FEDERAL OR S	CATE OFFICE	EUSE TOTAL	
COMPONE TO 10550		Title		Dat	te
Approved by Conditions of approval, if any, are attache certify that the applicant holds legal or eq which would entitle the applicant to condu-	uitable title to those rights in the subje	arrant or	2		
Title 18 U.S.C. Section 1001 and Title 43 States any false, fictitious and fraudulents	U.S.C. Section 1212, make it a crime	matter within its jurisdiction			ency of the United
(Instructions on reverse)		****	ECEIVE	D	

APR 18 2008

NEWFIELD PRODUCTION COMPANY CASING & CEMENT REPORT

The state of the s

	e di T		5 1/2"	CASING SET	AT	5820.73	-		
					Fit clir @	5799.48'			
LAST CASI	NG <u>8 5/8</u>	SET A	4 324. <u>33'</u>		OPERATOR	٦	Newfield F	Production	Company
DATUM	1:	2			WELL	State 5-16	-9-16		
DATUM TO	CUT OFF C	ASING _	12		FIELD/PRO	SPECT _	Monumen	t Butte	
DATUM TO	BRADENHE	EAD FLANGE			CONTRACT	FOR & RIG#		NDSI Rig #	3
TO DRILLER	5825'	LOGG	f 5 <u>935'</u>						
HOLE SIZE	7 7/8"			·					
CYMBRUNNY	4. GT			<u> </u>					
LOG OF CA	SING STRIN	NG:			· · · · · · · · · · · · · · · · · · ·		,		
PIECES		ITEM -	MAKE - DESC	RIPTION	WT/FT	GRD	THREAD	CONDT	LENGTH
		Landing Jt							14
		Short jt @	4020'/5.44''						
138	5 1/2"	ETC LT & C	casing		15.5#	J-55	8rd	Α	5786.88
									0.6
1	5 1/2"	ETC LT&C	csg		15.5#	J-55	8rd	Α	20.6
			GUIDE	shoe			8rd	Α	0.65
CASING INV	ENTORY B	AL.	FEET	JTS	TOTAL LEN	IGTH OF ST	RING		5822.73
TOTAL LEN	GTH OF ST	RING	5822.73	139	LESS CUT	OFF PIECE			14
LESS NON (CSG. ITEMS	}	15.25		PLUS DATU	JM TO T/CU	T OFF CSG		12
PLUS FULL	JTS. LEFT (TUC	221.29	6	CASING SE	T DEPTH			5820.73
FIGLE SIZE	TOTAL		6028.77	145	1				
TOTAL CSG	DEL. (W/C	THRDS)	6028.77	145	∫ COMPAF	RE			
THING OAS	SINC 1.		1ST STAGE	2nd STAGE	<u> </u>				•
BEGIN RUN	CSG:		4/15/2008	4:30 AM	GOOD CIRC	C THRU JOE		Yes	
CSG. IN HO	E		4/15/2008	8:30 AM	-1				
BEGIN CIRC			4/15/2008	8:30 AM	RECIPROC	ATED PIPE	FOR	_THRU	FT STROKE
BEGIN/PUM	PCMT		4/15/2008	10:25 AM			E HOLD? _		
BEGIN DSPI	. CMT		4/15/2008	11:05 AM	BUMPED PI	LUG TO _		2060	PSI
PLUG DOW	N		4/15/2008	11:30 AM					
CEMENT US	SED			CEMENT COI	MPANY-	B. J.			
STAGE	# SX			CEMENT TYP					
10 11 N	300	Premlite II w	// 10% gel + 3 °	% KCL, 3#'s /s	k CSE + 2# s	k/kolseal + 1	/2#'s/sk Cello	Flake	
GFQC 2007			.0 ppg W / 3.43						
2	400	50/50 poz V	V/ 2% Gel + 3%	KCL, .5%EC1	,1/4# sk C.F.				1.24 YLD
plant displace, be made with a	The garage of the	TCHER PLAC					KE & SPACIN	IG	
Centralizers	Middle fi	rst, top seco	ond & third. Th	nen every thir	d collar for a	a total of 20			
THANG	15.jp Szelfővere								
BECAN RUN	csg-								
CSG. IN HOL	The second secon							4048185	
COMPANY	REPRESEN	TATIVE			Jim Smith		DATÉ	4/`15/08	
EEGIN PUM									
regin dae									

PLUGTO III

STATE OF UTAH DIVISION OF OIL, GAS AND MINING **ENTITY ACTION FORM -FORM 6**

OPERATOR: NEWFIELD PRODUCTION COMPANY ADDRESS: RT. 3 BOX 3830 MYTON, UT 84052

OPERATOR ACCT. NO.

N2695

04/10/08

Date

ACTION CODE	CURRENT	NEW	API NUMBER				_				
	ENTITY NO.	ENTITY NO.		WELL MAKE	- 00	l ec	WELL	LOCATION	COUNTY	BPUD DATE	EFFECTIVE
Α	99999	16800	4304739733	UTE TRIBAL 2-1-5-1E	NWNE	4	58				DATE
WELL 14	COMMENTS:	Cappi)			HANAME	 	103	116	DUCHESNE	4/2/2008	14/28/08
]					, - ·
ACTION	CURRENT	NEW	API NUMBER				1				
CODE	ENTETY NO.	ENTITY NO.	ATTHOREEA	WELL NAME			ELL LOCA			SPUD	EFFECTIVE
Α	99999	16801	4304739259		00	8C	TP-	RE	COUNTY	DATE	DATE
		70001	4304/39259	FEDERAL 4-24-9-17	WWW	24	95	17E	DUCHESNE	4/2/2008	4/28/08
	(.	TRIPI)									1 1/20/00
		MW									
ACTION	CURPLENT ENTRY NO.	NEW ENTITY NO.	API NUMBER	WELL HAME							
		7		SUNDANCE	00	8C	TP TP	INU	COUNTY	8 PUD DATE	EFFECTIVE
B	99999	14844	4304734935					18E			,
	0 0)		400-1104-900	FEDERAL 8-6-9-18	SENE	6	98	17E	DUCHESNE	4/4/2008	H/10/10
	(SRRI)	2111	CITALE	1 1. 5/.	,						1/2000
	0/0/00	DM=	SENE	Sundance Uni	t					·	
ACTION CODE	CURRENT ENTITY NO.	NEW.	API NUMBER	WELL NAME				00450-44			
. 1					05	e c	TP	OCATION RG	COUNTY	SPUID DATE	EFFECTIVE DATE
A	99999	16802	4301333849	STATE 5-16-9-16	CHARMA						. / /
	GR	PAI)			SWNW	16	98	16E	DUCHESNE	4/7/2008	4/28/08
ACTION	CURRENT	T-									
CODE	ENTITY NO.	HEW ENTITY NO.	API NIAMPER	WELL HAME			WELL L	OCATION		BPUD	
					00	\$C	TP	RG	CONTAILA	DATE	EFFECTIVE DATE
						1					
NCLL B CC	MMENTS:				<u> </u>	L	t				
CTION	CURRENT	NEW	API NJMBER	WELL NAVE							
CODE	ENTITY NO.	ENTITY NO.		WILLIAME	000	sc	WELL LO	RG		SPID	EFFECTIVE
			_					- NG -	COUNTY	DATE	DATE
EIT & CO	MARINTS:				LL						_
										-	
TION CO	DES (See instructions on baci	t of farmi							A ·		
A-1194	Per seriity for seve well (single v	vat only)							//	-/-	
B-1441 C-from	ed to endsting entity (group or a more endsting entity to emotio	inti well) I fiziation essitu							011/	1/8//1	
D - Me	I from one existing entity to a	new entity						-	Significare	4101	Jentri Park
E- bar	r (explain in comment): section)						-	7	/	
								P	roduction Clerk	,	04/10/04

DIV. OF OIL, GAS & MINING APR 1 0 2008

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES 5. LEASE DESIGNATION AND SERIAL NUMBER: DIVISION OF OIL, GAS AND MINING UTAH STATE ML-16532 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: SUNDRY NOTICES AND REPORTS ON WELLS 7. UNIT or CA AGREEMENT NAME: Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. 1. TYPE OF WELL: 8. WELL NAME and NUMBER: OIL WELL GAS WELL OTHER STATE 5-16-9-16 2. NAME OF OPERATOR: 9. API NUMBER: NEWFIELD PRODUCTION COMPANY 4301333849 3. ADDRESS OF OPERATOR: 10. FIELD AND POOL, OR WILDCAT: PHONE NUMBER Route 3 Box 3630 CITY Myton STATE UT ZIP 84052 435.646.3721 MONUMENT BUTTE 4. LOCATION OF WELL: FOOTAGES AT SURFACE: 2043 FNL 758 FWL COUNTY: DUCHESNE OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SWNW, 16, T9S, R16E STATE: UT

II. CHECK APPRO	PRIATE BOXES TO INDICATI	E NATURE OF NOTICE, REPO	ORT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
☐ NOTICE OF INTENT	ACIDIZE	DEEPEN	REPERFORATE CURRENT FORMATION
(Submit in Duplicate)	ALTER CASING	FRACTURE TREAT	SIDETRACK TO REPAIR WELL
Approximate date work will	CASING REPAIR	NEW CONSTRUCTION	TEMPORARITLY ABANDON
	CHANGE TO PREVIOUS PLANS	OPERATOR CHANGE	TUBING REPAIR
	CHANGE TUBING	PLUG AND ABANDON	VENT OR FLAIR
SUBSEQUENT REPORT	CHANGE WELL NAME	☐ PLUG BACK	WATER DISPOSAL
(Submit Original Form Only) Date of Work Completion:	CHANGE WELL STATUS	PRODUCTION (START/STOP)	WATER SHUT-OFF
Date of work Completion;	COMMINGLE PRODUCING FORMATIONS	RECLAMATION OF WELL SITE	OTHER: - Weekly Status Report
05/20/2008	CONVERT WELL TYPE	RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The above subject well was completed on 05/14/08, attached is a daily completion status report.

NAME (PLEASE PRINT) Jentri Park TITLE Production Clerk 05/20/2008 SIGNATURE DATE

(This space for State use only)

RECEIVED MAY 27 2008

Daily Activity Report

Format For Sundry STATE 5-16-9-16 3/1/2008 To 7/30/2008

5/3/2008 Day: 1

Completion

Rigless on 5/2/2008 - Install 5m frac head. NU 6" 5K Cameron BOP. RU H/O truck & pressure test casing, blind rams, frac head, csg & casing valves to 4500 psi. RU Perforators LLC WLT w/ mast & run CBL under pressure. WLTD @ 5757' & cement top @ 70'. Perforate stage #1, CP3 sds @ 5698-5706' w/ 3-1/8" Slick Guns (19 gram, .49"EH. 120°) w/ 4 spf for total of 32 shots. 136 BWTR. SWIFN.

5/8/2008 Day: 2

Completion

Rigless on 5/7/2008 - Stage #1, CP3 sands. RU BJ Services. 0 psi on well. Frac CP3 sds w/ 34,586#'s of 20/40 sand in 434 bbls of Lightning 17 fluid. Broke @ 3030 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 1941 psi @ ave rate of 23.2 BPM. Pumped 504 gals of 15% HCL in flush for Stage #2. ISIP 2046 psi. Leave pressure on well. Stage #2, LODC sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 8' perf gun. Set plug @ 5440'. Perforate LODC sds @ 5334-42' w/ 3-1/8" Slick Guns w/ 4 spf for total of 32 shots. RU BJ Services. 1674 psi on well. Frac LODC sds w/ 24,721#'s of 20/40 sand in 348 bbls of Lightning 17 fluid. Broke @ 1889 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2425 psi @ ave rate of 23.2 BPM. Pumped 504 gals of 15% HCL in flush for Stage #3. ISIP 2165 psi. Leave pressure on well. 918 BWTR Stage #3, A.5 sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 11' perf gun. Set plug @ 5180'. Perforate A.5 sds @ 5080- 91' w/ 3-1/8" Slick Guns w/ 4 spf for total of 44 shots. RU BJ Services. 1708 psi on well. Frac A.5 sds w/ 84,098#'s of 20/40 sand in 666 bbls of Lightning 17 fluid. Broke @ 3959 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2065 psi @ ave rate of 23.2 BPM. Pumped 504 gals of 15% HCL in flush for Stage #4. ISIP 2582 psi. Leave pressure on well. 1584 BWTR Stage #4, B2 sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 6' perf gun. Set plug @ 5040'. Perforate B2 sds @ 4968- 74' w/ 3-1/8" Slick Guns w/ 4 spf for total of 24 shots. RU BJ Services. 1921 psi on well. Frac B2 sds w/ 24,764#'s of 20/40 sand in 354 bbls of Lightning 17 fluid. Broke @ 3710 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 3365 psi @ ave rate of 23.3 BPM. Pumped 504 gals of 15% HCL in flush for Stage #5. ISIP 2959 psi. Leave pressure on well. 1938 BWTR Stage #5, D2 sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 7' perf gun. Set plug @ 4880'. Perforate D2 sds @ 4778- 85' w/ 3-1/8" Slick Guns w/ 4 spf for total of 28 shots. RU BJ Services. 1452 psi on well. Frac D2 sds w/ 24,664#'s of 20/40 sand in 341 bbls of Lightning 17 fluid. Broke @ 3618 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 1975 psi @ ave rate of 23.3 BPM. Pumped 504 gals of 15% HCL in flush for Stage #6. ISIP 1906 psi. Leave pressure on well. 2279 BWTR Stage #6, GB4 sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 12' perf gun. Set plug @ 4280'. Perforate GB4 sds @ 4170-82' w/ 3-1/8" Slick Guns w/ 4 spf for total of 48 shots. RU BJ Services. 1466 psi on well. Frac GB4 sds w/ 59,402#'s of 20/40 sand in 511 bbls of Lightning 17 fluid. Broke @ 3066 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 1805 psi @ ave rate of

23.3 BPM. ISIP 1929 psi. Begin immediate flowback on 12/64 choke @ 1 BPM. Flowed for 7 1/2 hrs & died. Rec. 430 BTF. SIWFN w/ 2360 BWTR.

5/9/2008 Day: 3

Completion

Leed #712 on 5/8/2008 - MIRU Leed rig 712. 100 psi on well. Bleed off pressure. ND Cameron BOP & 5M WH. NU 3M WH & Shaffer BOP. Talley PU & RIH w/ 4 3/4" chomp bit, bit sub & 2 7/8" J- 55 tbg. Tagged sand @4259'. RU Nabors power swivel. Circulate sand & drill out plugs. Sand @ 4259', Plug @ 4280', Drilled up in 40 mins, Tagged sand @ 4625', Circulate clean down to plug @ 4880'. SIWFN w/ 2335 BWTR.

5/13/2008 Day: 4

Completion

Leed #712 on 5/12/2008 - 25 psi on well. Bleed off pressure. Continue to clean out sand & drill out plugs. Plug @ 4880' (Drilled out in 18 mins). Tagged sand @ 5032', Plug @ 5040' (Drilled out in 28 mins), Tagged sand @ 5146', Plug @ 5180' (Drilled up in 23 mins). Tagged plug @ 5440', (Drilled up in 19 mins). Tagged fill @ 5657'. C/O to PBTD @ 5799'. RD power swivel. LD 2 jts of tbg. EOT @ 5738'. RU swab equipment. IFL @ sfc. Made 14 runs. Rec 150 BTF. FFL @ 1200'. Trace of oil, No sand. RD swab equipment. TIH w/ tbg. Tagged sand @ 5754'. Circulate clean down to PBTD @ 5799'. LD 4 jts of tbg. EOT 5680'. SIWFN w/ 2280 BWTR.

5/14/2008 Day: 5

Completion

Leed #712 on 5/13/2008 - 25 psi on well. Bleed off pressure. TOH w/ tbg. LD bit & bit sub. PU & RIH w/ production tbg as follows: BP, 4- jts, 2 7/8" nipple, PBGA, 1- jt, SN, 2-jts, TA, 168 jts of 2 7/8" J-55 tbg. ND BOP, Set TA w/ 15,000#'s of tension @ 5280'. Land tbg on flange. NU WH. Prime up rod pump. PU & RIH w/ follow: CDI: 2 1/2" X 1 1/2" X 18' RHAC, 6- 1 1/2" wtr bars, 20- 3/4" guided rods, 93- 3/4" plain rods, 94- 3/4" guided rods, 1-2' X 3/4" sub, 1 1/2" X 26' Polish rod. Space out rods. 2280 BWTR. Left well down due to surface equipment, Final report will follow.

5/15/2008 Day: 6

Completion

Rigless on 5/14/2008 - Complete flow line ty in. Adjust tag. PWOP @ 1:00 pm w/74" SL & 5 SPM. Final report.

Pertinent Files: Go to File List



UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE* FORM APPROVED

(See other instructions ons reverse side)

OMB NO. 1004-0137

Expires: February 28, 1995

5. LEASE DESIGNATION AND SERIAL NO.

ML-16532

WELL	COM	PLETION	OR RI	COMP	LETION	REPORT A	ND LOG*	6. IF INDIAN, A		OR TRIBE NAME
1a. TYPE OF WORK								7. UNIT AGREE	EMENT NA	ME
		OIL WELL	X	GAS WELL	DRY	Other			St	ate
1b. TYPE OF WELL		***************************************								
NEW X	work	DEEPEN		PLUG	DIFF			8. FARM OR LE		e, well no. -16-9-16
WELL ^	OVER			BACK	RESVR.	Other		9. WELL NO.	State 5	-10-9-10
2. NAME OF OPERATOR		Ne	wfield F	xnloratio	n Compan	V		9. WELL NO.	43-013	3-33849
3. ADDRESS AND TELE	PHONE NO.		WIICIG L	Apioratio	Compan	<i>J</i>		10. FIELD AND		
		1401 17th	St. Sui	te 1000 [Denver, Co	O 80202			Monum	ent Butte
4. LOCATION OF WE	LL (Report	locations clearly a	nd in accor	dance with any	State requireme	ents.*)			M., OR BLO	OCK AND SURVEY
At Surface		2043	FNL & 7	'58' FWL (S	W/NW) Sec	. 16, T9S, R16E		OR AREA		TOO D40E
At top prod. Interval re	ported belo	w						Se	ec. 16,	T9S, R16E
										1
At total depth			1	14. API NO.	13-33849	DATE ISSUED	1/24/08	12. COUNTY OR		13. STATE
16 DATE COUDDED	IIC DATE:	Γ.D. REACHED	17 DA	TE COMPL. (Rea			DF, RKB, RT, GR, ET	Duch		19. ELEV. CASINGHEAD
15. DATE SPUDDED 04/07/08		04/14/08	17. DA	05/14		5922		5934' KB		19. EEEV, CASINGITEAD
20. TOTAL DEPTH, MD		21. PLUG BAC	K T.D., MD		22. IF MULTIF		23. INTERVALS	ROTARY TOOLS		CABLE TOOLS
·					HOW MAN	NY*	DRILLED BY			
5825'			5799'				>	<u> </u>		
24. PRODUCING INTER	VAL(S), OF T	HIS COMPLETION-	TOP, BOTTO	OM, NAME (MD	AND TVD)*					25. WAS DIRECTIONAL
				Green Riv	ver 4170)'-5706'				SURVEY MADE
										No
26. TYPE ELECTRIC AN			naatad	Donoity	Compone	atad Mautran (GP Coliner	Cement Bond L		27. WAS WELL CORED No
	Guara,	SF, Compe	nsaleu					Cement Bond t	_og	110
23. CASING SIZE/	(CD ADE	WEIGHT	IB/FT		SET (MD)	port all strings set in HOLE SIZE		MENT, CEMENTING RECO	ORD	AMOUNT PULLED
8-5/8" -	J-55	24			24'	12-1/4"		vith 160 sx Class "C		
5-1/2" -		15.	5#	58	21'	7-7/8"	300 sx Premli	ite II and 400 sx 50/	50 Poz	
29.		LIN	ER RECOI	RD			30.	TUBING REC		
SIZE		TOP (MD)	вотто	M (MD)	SACKS CEMENT	F* SCREEN (MD)	SIZE 2-7/8"	DEPTH SET (MD)	PACKER SET (MD) TA @
		147.0					2-1/0	EOT @ 5508'		5280'
	1						A CYP CYYOT	FRACTURE, CEMEN	T COLUE	
31. PERFORATION RE	CORD (Inter TERVAL	val, size and number		ZE S	SPF/NUMBE	B DEPTH INT	ERVAL (MD)			MATERIAL USED
III		3) 5698'-5706'		9"	4/32	5698'-	- ` ' -	Frac w/ 34,586#	20/40 sa	and in 434 bbls fluid
	_ `	C) 5334'-5342'		9"	4/32		-5342'	Frac w/ 24,721#	20/40 sa	and in 348 bbls fluid
		5) 5080'-5091'		9"	4/44		-5091'	Frac w/ 84,098#	20/40 sa	and in 666 bbls fluid
		2) 4968'-4974'		9"	4/24		-4974'			and in 354 bbls fluid
	<u>`</u>	2) 4778'-4785'		9"	4/28	4778'-				and in 341 bbls fluid
		4) 4170'-4182'		9"	4/48		-4182'	Frac w/ 59,402#	20/40 sa	and in 511 bbls fluid
	,,,,,	.,		-						
					· · · · · · · · · · · · · · · · · · ·					
				- 						
33.*					PROD	UCTION				
				(Flowing gas lif	t, pumping-size a	nd type of pump)		nn l		ATUS (Producing or shut-in) RODUCING
DATE FIRST PRODUCT 05/14/		PRODUCTIO	N METHOD 2-1.	/2" x 1-1/2	2" x 16' x 1	18. KHAC SIM	Plunger Pun		Г	
DATE FIRST PRODUCT		PRODUCTION HOURS TESTED	ом метнор 2-1 снокі	/2" x 1-1/2 SIZE PI	2" x 16' x 1 ROD'N, FOR	OILBBLS.	Plunger Pun GASMCF.	WATERBBL.		GAS-OIL RATIO
DATE FIRST PRODUCT 05/14/	08		2-1	/2" x 1-1/2 SIZE PI	2" x 16' x 1	OILBBLS. 47		WATERBBL.		gas-oil ratio 1574
DATE FIRST PRODUCT 05/14/ DATE OF TEST	/08 8		2-1 CHOKE	/2" x 1-1/2 E SIZE PETT	2" x 16' x 1 ROD'N. FOR EST PERIOD	OILBBLS.	GASMCF.	WATERBBL.		GAS-OIL RATIO
DATE FIRST PRODUCT 05/14/ DATE OF TEST 06-21-0	/08 8	HOURS TESTED	2-1 CHOKE	/2" x 1-1/2 E SIZE PH TI JLATED JR RATE	2" x 16' x 1 ROD'N, FOR EST PERIOD	OILBBLS. 47	GASMCF.	WATERBBL.		gas-oil ratio 1574
DATE FIRST PRODUCT 05/14/ DATE OF TEST 06-21-0 FLOW. TUBING PRESS.	['] 08 8	HOURS TESTED CASING PRESSUR	2-1 CHOKE	/2" x 1-1/2 E SIZE PETT	2" x 16' x 1 ROD'N, FOR EST PERIOD	OILBBLS. 47	GASMCF.	WATERBBL. 18 WATERBBL.		gas-oil ratio 1574
DATE FIRST PRODUCT 05/14/ DATE OF TEST 06-21-0	['] 08 8	HOURS TESTED CASING PRESSUR	2-1 CHOKE E CALCU 24-HOU	/2" x 1-1/2 E SIZE PI TI JLATED JR RATE>	2" x 16' x ´ ROD'N, FOR EST PERIOD OIL-BBL.	OILBBLS. 47	GASMCF.	WATERBBL.		gas-oil ratio 1574
DATE FIRST PRODUCT 05/14/ DATE OF TEST 06-21-0 FLOW. TUBING PRESS.	8 AS (Sold, used	HOURS TESTED CASING PRESSUR	2-1 CHOKE	/2" x 1-1/2 E SIZE PH TI JLATED JR RATE	2" x 16' x ´ ROD'N, FOR EST PERIOD OIL-BBL.	OILBBLS. 47	GASMCF.	WATERBBL. 18 WATERBBL. TEST WITNESS	EÇE ED BYE	1574 1574 17-API (CORR.) 7 2008
DATE FIRST PRODUCT 05/14/ DATE OF TEST 06-21-0 FLOW. TUBING PRESS. 34. DISPOSITION OF GA 35. LIST OF ATTACHM	8 AS (Sold, used	HOURS TESTED CASING PRESSUR for fuel, vented, etc.)	2-1 CHOKE	/2" x 1-1/2 ESIZE PITI FLATED JIR RATE > & Used for	2" x 16' x 2" ROD'N. FOR EST PERIOD OIL-BBL. OIL-BBL.	GAS-MCF.	GAS-MCF. 74	WATERBBL. 18 WATERBBL. TEST WITNESS	EÇE ED BYE	1574 1574 17-API (CORR.) 7 2008
DATE FIRST PRODUCT 05/14/ DATE OF TEST 06-21-0 FLOW. TUBING PRESS. 34. DISPOSITION OF GA 35. LIST OF ATTACHM	8 AS (Sold, used ENTS at the large	HOURS TESTED CASING PRESSUR for fuel, vented, etc.)	2-1 CHOKE	/2" x 1-1/2 ESIZE PITI FLATED JIR RATE > & Used for	2" x 16' x 7 ROD'N, FOR EST PERIOD OIL-BBL. OIL-BBL.	GAS-MCF.	GASMCF. 74	WATERBBL. 18 WATERBBL. TEST WITNESS	EÇE ED BYE	GAS-OIL RATIO 1574 TY-API (CORR.)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

VERT. DEPTH TRUE TOP MEAS. DEPTH 3874 3890 3998 4248 4515 4663 4663 4897 5004 5552 NP GEOLOGIC MARKERS Castle Peak Basal Carbonate Total Depth (LOGGERS Douglas Creek Mkr BiCarbonate Mkr Garden Gulch Mkr Garden Gulch 1 B Limestone Mkr Garden Gulch 2 NAME Point 3 Mkr X Mkr Y-Mkr 38. DESCRIPTION, CONTENTS, ETC. 37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals, and all State 5-16-9-16 Well Name drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and BOTTOM TOP FORMATION recoveries);

4/94

STATE OF UTAH

DIVISION OF OIL, GAS, AND MININ	1G	5. LEASE DESIGNATION AND SI	ERIAL NO.		
SUNDRY NOTICES AND REPORTS	ON WELLS	ML-16532 6. IF INDIAN, ALLOTTEE OR TR	IBAL NAME		
Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plug Use "APPLICATION FOR PERMIT TO DRILL OR DEEPEN form	-	N/A			
OIL GAS WELL X OTHER		7. UNIT AGREEMENT NAME NA			
2. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY	8. WELL NAME and NUMBER STATE 5-16	-9-16			
3. ADDRESS AND TELEPHONE NUMBER Rt. 3 Box 3630, Myton Utah 84052 435-646-3721	_	9 API NUMBER 43-013-33849			
4. LOCATION OF WELL		10 FIELD AND POOL, OR WILDC	AT		
Footages 2043 FNL 758 FWL		MONUMEN	T BUTTE		
QQ, SEC, T, R, M: SW/NW Section 16, T9S R16E		COUNTY DUCHESNE STATE UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NO	OTICE, REPORT OR OTHE	R DATA			
NOTICE OF INTENT:	· ·	NT REPORT OF:			
(Submit in Duplicate) ABANDON NEW CONSTRUCTION	ABANDON*	t Original Form Only)	NEW CONSTRUCTION		
REPAIR CASING PULL OR ALTER CASING	REPAIR CASING		PULL OR ALTER CASING		
CHANGE OF PLANS RECOMPLETE	X CHANGE OF PLA	ANS			
CONVERT TO INJECTION REPERFORATE	CONVERT TO IN	IJECTION	REPERFORATE		
FRACTURE TREAT OR ACIDIZE VENT OR FLARE	FRACTURE TREAT	FRACTURE TREAT OR ACIDIZE VENT OR FLARE			
MULTIPLE COMPLETION WATER SHUT OFF	OTHER	3R			
OTHER	DATE WORK COMPL	ETED			
	Report results of Multip	le Completion and Recompletions	to different		
	reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND				
	LOG form.	by a cement verification report.			
 DESCR(BE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertiner and measured and true vertical depth for all markers and zones pertinent to this work. 			ive subsurface locations		
As per a conversation with Helen Sadik MacDona	ld approval was gi	ven to go ahead and	set the planned 290' of		
surface casing that is normally set on wells drilled					
Subsequently 324' of surface casing was set on the					
1					
13.					
NAME & SIGNATURE Mandle Crozier TITLE	Regulatory Speciali	St DATE_	7/21/2008		
(This space for State use only)					

* See Instructions On Reverse Side



	STATE OF UTAH		FORM 9			
	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MININ		5.LEASE DESIGNATION AND SERIAL NUMBER: ML-16532			
SUNDF	RY NOTICES AND REPORTS OF	N WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
	oposals to drill new wells, significantly de reenter plugged wells, or to drill horizonta n for such proposals.		7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)			
1. TYPE OF WELL Oil Well			8. WELL NAME and NUMBER: STATE 5-16-9-16			
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	OMPANY		9. API NUMBER: 43013338490000			
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT		HONE NUMBER: Ext	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2043 FNL 0758 FWL			COUNTY: DUCHESNE			
QTR/QTR, SECTION, TOWNS	HIP, RANGE, MERIDIAN: 16 Township: 09.0S Range: 16.0E Meridia	n: S	STATE: UTAH			
11. CHEC	K APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPOR	RT, OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION				
	ACIDIZE	ALTER CASING	CASING REPAIR			
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME			
- Approximate date from the state	✓ CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	✓ CONVERT WELL TYPE			
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION			
11/29/2012	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK			
SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION			
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON			
DRILLING REPORT	L TUBING REPAIR	VENT OR FLARE	☐ WATER DISPOSAL			
Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION			
	WILDCAT WELL DETERMINATION	OTHER	OTHER:			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The subject well has been converted from a producing oil well to an injection well on 11/28/2012. On 11/20/2012 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 11/29/2012 the casing was pressured up to 1270 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 250 psig during the test. There was not a State representative available to witness the test. By:						
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician				
SIGNATURE		DATE 12/6/2012				


Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company Rt. 3 Box 3630 Myton, UT 84052 435-646-3721

Witness:	Date 11 1 271 12 Time am pm
Test Conducted by: Rolly Bagly	
Others Present:	
Well: State 5-16-9-16	Field: Wonument Butte
	API No: 4301333 849
Well Location: State 5-16-9-16	A 1100 (30130)

<u>Time</u>	Casing Pressure	
0 min	1270	psig
5	1270	psig
10	1270	psig
15	1270	psig
20	1270	psig
25	1270	psig
30 min	1770	psig
35		psig
40	•	psig
45		_ psig
50		_ psig
55		_ psig
60 min		_ psig
Tubing pressure:	250	_ psig
Result:	Pass	Fail

Signature of Witness:			100
Signature of Per	son Conducting	Test:	Val



Sundry Number: 32914 API Well Number: 43013338490000 Page 1 of 3

Summary Rig Activity

Daily Activity Report

Format For Sundry STATE 5-16-9-16 9/1/2012 To 1/30/2013

11/19/2012 Day: 1

Conversion

Nabors #1450 on 11/19/2012 - MIRUSU, pull rods - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN - spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN - spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN

Finalized Daily Cost: \$0

Cumulative Cost: \$13,709

11/20/2012 Day: 3

Conversion

Nabors #1450 on 11/20/2012 - POOH w/ 36 stands, breaking, cleaning, & doping colars on the way out, LD 43 joints - Travel time, start rig, morning meeting. Other, bleed well, CSG 250 PSI TBG PSI, rig maintainance, derrick inspection. POOH w/ 36 stands, breaking, cleaning, & doping colars on the way out, LD 43 joints. Make up BHA, 2 3/8" XN, 2 3/8" x 4' sub, 2 3/8" x 2 7/8" XO, 5 1/2" x 2 7/8" PKR, on/off tool, 2 7/8" S/N, 131 joints. pump 10 bbl pad, drop valve, fill TBG w/ 25 bbl, pumped TBG upto 3000 PSI, RU sandline, TBG droped to 2600 PSI in 15 min, bumped back up to 3000 PSI, droped to 2600 PSI in 15 min, bumped back upto 3000 PSI, droped to 2800 PSI in 15 min, pulled test tee, redoped and retightened tee, pump TBG upto 3000 PSI, held for 30 min, good test. fish valve, RD sandline. SWI, clean

Page 2 of 3 Summary Rig Activity

up for the night. - Travel time, start rig, morning meeting. Other, bleed well, CSG 250 PSI TBG PSI, rig maintainance, derrick inspection. POOH w/ 36 stands, breaking, cleaning, & doping colars on the way out, LD 43 joints. Make up BHA, 2 3/8" XN, 2 3/8" x 4' sub, 2 3/8" x 2 7/8" XO, 5 1/2" x 2 7/8" PKR, on/off tool, 2 7/8" S/N, 131 joints. pump 10 bbl pad, drop valve, fill TBG w/ 25 bbl, pumped TBG upto 3000 PSI, RU sandline, TBG droped to 2600 PSI in 15 min, bumped back up to 3000 PSI, droped to 2600 PSI in 15 min, bumped back upto 3000 PSI, droped to 2800 PSI in 15 min, pulled test tee, redoped and retightened tee, pump TBG upto 3000 PSI, held for 30 min, good test. fish valve, RD sandline. SWI, clean up for the night. - Travel time, start rig, morning meeting. Other, bleed well, CSG 250 PSI TBG PSI, rig maintainance, derrick inspection. POOH w/ 36 stands, breaking, cleaning, & doping colars on the way out, LD 43 joints. Make up BHA, 2 3/8" XN, 2 3/8" x 4' sub, 2 3/8" x 2 7/8" XO, 5 1/2" x 2 7/8" PKR, on/off tool, 2 7/8" S/N, 131 joints. pump 10 bbl pad, drop valve, fill TBG w/ 25 bbl, pumped TBG upto 3000 PSI, RU sandline, TBG droped to 2600 PSI in 15 min, bumped back up to 3000 PSI, droped to 2600 PSI in 15 min, bumped back upto 3000 PSI, droped to 2800 PSI in 15 min, pulled test tee, redoped and retightened tee, pump TBG upto 3000 PSI, held for 30 min, good test. fish valve, RD sandline. SWI, clean up for the night.

Daily Cost: \$0

Cumulative Cost: \$27,910

11/21/2012 Day: 4

Conversion

Nabors #1450 on 11/21/2012 - Nu wellhead, pressure test - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - move different rig on to fish out tools move different rig on to fish out tools - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - move different rig on to fish out tools - move different rig on to fish out tools - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - move different rig on to fish out tools - move different rig on to fish out tools Finalized

Daily Cost: \$0

Cumulative Cost: \$38,945

11/27/2012 Day: 6

Conversion

Nabors #1450 on 11/27/2012 - MIRU, TOOH W/131 JTS S&N on/off TOOL 70 - Crew Traval & safety Meeting, RD Rig road rig from 3-23-9-16 to 5-16-9-16, MIRU, SICP 1350 Bleed off casing bleed off tubing for 1 1/2 hours, tbg release off packer NU BOP RU tbg EQ TOOH W/131 jts SN& on/off TOOL W/ 70 jts Completely solid with oil did not find gyro tools TIH W/tbg string W/ bit & scraper on bottom flushing pluged jts did not find gyro - Crew Traval & safety Meeting . RD Rig road rig from 3-23-9-16 to 5-16-9-16, MIRU, SICP 1350 Bleed off casing bleed off tubing for 1 1/2 hours, tbg release off packer NU BOP RU tbg EQ TOOH W/131 jts SN& on/off TOOL W/70 its Completely solid with oil did not find gyro tools TIH W/tbg string W/ bit & scraper on bottom flushing pluged jts did not find gyro - Crew Traval & safety Meeting . RD Rig road rig from 3-23-9-16 to 5-16-9-16, MIRU, SICP 1350 Bleed off casing bleed off tubing for 1 1/2 hours, tbg release off packer NU BOP RU tbg EQ TOOH W/131 jts SN& on/off TOOL W/ 70 jts Completely solid with oil did not find gyro tools TIH W/tbg string W/ bit & scraper on bottom flushing pluged jts did not find gyro

Sundry Number: 32914 API Well Number: 43013338490000 Page 3 of 3 Summary Rig Activity

Daily Cost: \$0

Cumulative Cost: \$49,676

11/29/2012 Day: 7

Conversion

Nabors #1450 on 11/29/2012 - Pressure test TBG & CSG, Tested good - Crew training and safety meeting, TIH W/ 2 3/8 re-entry / Giude ,2 3/8 Xn nipple 2 3/8 TBG sub 2 3/8 x2 7/8 x over, 5 1/2 as-z1 packer ,on/off TOOL, 2 7/8 SN 60 JTS flush TBG W/ 30 BW TIH W/ 71 more JTS 2 7/8 J-55 TBG pump 30 BW Drop SV psi test tbg to 3000 psi W/40 more bbls hold for 45 minutes good test BET SV W/ sand line , RU VES & gyro well RD work floor ND BOP Set PKR @ 4,128' for 16000 tension SV @ 41723' Xn @ 4136 EOT @ 4138' land tbg W/injection tree mix 15 gal pkr fliud W/ 60 bbls fresh H20 psi CSG to 1500psi W/ 50 bbls lost 100 psi & held good @ 1400 psi 30 min took 1 1/2 hr to get good test Rd and ready to road. - Crew training and safety meeting, TIH W/ 2 3/8 re-entry / Giude ,2 3/8 Xn nipple 2 3/8 TBG sub 2 3/8 x2 7/8 x over, 5 1/2 as-z1 packer ,on/off TOOL, 2 7/8 SN 60 JTS flush TBG W/ 30 BW TIH W/ 71 more JTS 2 7/8 J-55 TBG pump 30 BW Drop SV psi test tbg to 3000 psi W/40 more bbls hold for 45 minutes good test BET SV W/ sand line , RU VES & gyro well RD work floor ND BOP Set PKR @ 4,128' for 16000 tension SV @ 41723' Xn @ 4136 EOT @ 4138' land tbg W/injection tree mix 15 gal pkr fliud W/ 60 bbls fresh H20 psi CSG to 1500psi W/ 50 bbls lost 100 psi & held good @ 1400 psi 30 min took 1 1/2 hr to get good test Rd and ready to road. - Crew training and safety meeting, TIH W/ 2 3/8 re-entry / Giude ,2 3/8 Xn nipple 2 3/8 TBG sub 2 3/8 x2 7/8 x over, 5 1/2 as-z1 packer ,on/off TOOL, 2 7/8 SN 60 JTS flush TBG W/ 30 BW TIH W/ 71 more JTS 2 7/8 J-55 TBG pump 30 BW Drop SV psi test tbg to 3000 psi W/40 more bbls hold for 45 minutes good test BET SV W/ sand line, RU VES & gyro well RD work floor ND BOP Set PKR @ 4,128' for 16000 tension SV @ 41723' Xn @ 4136 EOT @ 4138' land tbg W/injection tree mix 15 gal pkr fliud W/ 60 bbls fresh H20 psi CSG to 1500psi W/ 50 bbls lost 100 psi & held good @ 1400 psi 30 min took 1 1/2 hr to get good test Rd and ready to road. Finalized

Daily Cost: \$0

Cumulative Cost: \$56,304

12/3/2012 Day: 8

Conversion

Rigless on 12/3/2012 - Conduct initial MIT - On 11/20/2012 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 11/29/2012 the casing was pressured up to 1270 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 250 psig during the test. There was not a State representative available to witness the test. - On 11/20/2012 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 11/29/2012 the casing was pressured up to 1270 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 250 psig during the test. There was not a State representative available to witness the test. - On 11/20/2012 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 11/29/2012 the casing was pressured up to 1270 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 250 psig during the test. There was not a State representative available to witness the test. Finalized

Daily Cost: \$0

Cumulative Cost: \$138,638

Pertinent Files: Go to File List


STATE OF UTAR DIVISION OF OIL, GAS AND MINING

DIVISION	5. LEASE DESIGNATION AND SERIAL NO. ML-16532							
ADDI ICATION EO	6. IF INDIAN, ALLOTTEE OR TRIBE NAME							
APPLICATION FO			LL, DEEPEN				N/A	
a. TYPE OF WORK DRILL	x DEEF	EN					7. UNIT AGREEMENT NAME	
b. TYPE OF WELL			SINGLE	MULTI	IDI E		N/A 8. FARM OR LEASE NAME	
OIL X GAS	ОТНЕ	R		ZONE	TLE	7	N/A	
NAME OF OPERATOR	<u> </u>	 					9. WELL NO.	
Newfield Production Co					<u> </u>		State #5-16-9-16	
ADDRESS AND TELEPHONE NUME Route #3 Box 3630, Myt			Phon	o. (13	5) 646-3721		10. FIELD AND POOL OR WILDCAT Monument Butte	
LOCATION OF WELL (FOOTAGE)			I none	c. (43	3) 040-3721		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:	
At Surface SW/N	W 2043' FNL	758' F	WL					
At proposed Producing Zone 574			2516				SW/NW	
4. DISTANCE IN MILES AND DIRECT	315187		110.130428		<u> </u>	<u> </u>	Sec. 16, T9S, R16E 12. County 13. STATE	
Approximately 22.1 mile							Duchesne UT	
5. DISTANCE FROM PROPOSED* LO		ERTY	16. NO, OF ACRES IN LEASE		17, NO. OF ACRES	S ASSIGNE	ED TO THIS WELL	
OR LEASE LINE, FT. (Also to nearest Approx. 758' f/lse line at	- · · · · · · · · · · · · · · · · · · ·		640.00		40	`		
8. DISTANCE FROM PROPOSED LOC		·	19. PROPOSED DEPTH		20, ROTARY OR (OLS	
DRILLING, COMPLETED, OR APPI		r.	(500)		D-4-			
Approximately 14			6500'		Rota	T	ON PARE WORK WILL GRAPE	
5922' GL	I, GK, etc.)					1	OX. DATE WORK WILL START* UArter 2008	
	CASING AND C	EMI	ENTING PROG	RAN	1	1200 €		
SIZE OF HOLE	SIZE OF CASING	WEIGHT/E	FOOT	SETTING	G DEPTH ,	QUANTI	TY OF CEMENT	
12 1/4	8 5/8	24#		290	400	155 sx +/- 10%		
7 7/8	5 1/2	15.5#				275 sx lead followed by 450 sx tail		
<u> </u>						See D	Petail Below	
wbsurface locations and measured are the actual cement volusion. SURFACE PIPE - 155 s.	nd true vertical depths. Give to the true vertical depths. Give to the true will be calculated as Class G Cement +	olowout p ated o	ff of the open hole	logs, p /4#/sk	olus 15% exe		osal is to drill or deepen directionally, give pertinent data	ion
10% E	Bentonite + .5% Soc	lium N	Metasilicate		l + .25 lbs/sk q: 21.04 gal		Flake + 2 lbs/sk Kol Seal +	
					ello Flake + eq: 7.88 gal/		ntonite + .3% Sodium Metasilicate	
A. Name & Signature Mandie Cro	indictory ozier	ju	Title: Regulatory	Specia	alist	Date:	11/19/2007	
(This space for State use only)			The state of the s		·			
API Number Assigned:	43-013-3384	9	APPROVAL:			v =/**		
Approved Utah Divi Oil, Gas an	ision of		*See Instruction	ns On	Reverse S	ide	RECEIVED NOV 2 9 2007	

DIV. OF OIL, GAS & MINING

T9S, R16E, S.L.B.&M.

 $N89^{\circ}50'W - 80.24$ (G.L.O.)





= SECTION CORNERS LOCATED


BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SW) 9 MILE 5-16-9-16 (Surface Location) NAD 83 LATITUDE = 40° 01' 57.02" LONGITUDE = 110° 07' 51.79"

(C.L.O.)

N00.02,W

NEWFIELD PRODUCTION COMPANY

WELL LOCATION, 9 MILE 5-16-9-16, LOCATED AS SHOWN IN THE SW 1/4 NW 1/4 OF SECTION 16, T9S, R16E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT OF HE ABOVE PREST WAS PREPARED FROM FIELD OF ACTUME SURVEYS MADE BY ME OR UNDER MY SUPPROBLEM AND STREET TO THE BEST OF MY KNOWLEDGE AND FILES No. 189377



TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078 (435) 781-2501

DATE SURVEYED: 10-10-07	SURVEYED BY: C.M.
DATE DRAWN: 10-31-07	DRAWN BY: F.T.M.
REVISED:	SCALE: 1" = 1000'

NEWFIELD PRODUCTION COMPANY STATE #5-16-9-16 SW/NW SECTION 16, T9S, R16E DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

Uinta 0-1700' Green River 1700' Wasatch 6500'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River Formation 1700' - 6500' - Oil

4. **PROPOSED CASING PROGRAM:**

Surface Casing: 8-5/8" J-55 24# w/ST&C collars; set at 290 (New)
Production Casing:5-1/2" J-55, 15.5# w/LT&C collars; set at TD (New or used, inspected).

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to Exhibit C for a diagram of BOP equipment that will be used on this well.

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

A fresh water/polymer system will be utilized to drill the well. If necessary, to control formation fluids, the system will be weighted with the addition of bentonite gel, and if conditions warrant, barite. This fresh water system typically will contain Total Dissolved Solids (TDS) of less than 3000 PPM. Neither potassium chloride nor chromates will be utilized in the fluid system. The anticipated mud weight is 8.4 ppg and weighted as necessary for gas control.

AIR DRILLING

In the event that the proposed location is to be "Air Drilled", Newfield requests a variance to regulations requiring a straight run blooie line. Newfield proposes that the flowline will contain two (2) 90-degree turns. Newfield also requests a variance to regulations requiring an automatic igniter or continuous pilot light on the blooie line. Newfield requests authorization to ignite as needed, and the flowline at 80'.

Newfield Production Company requests that the spark arrest, exhaust, or water cooled exhaust be waived under the Special Drilling Operations of Onshore Order #2.

Ten Point Well Program
Thirteen Point Well Program
Page 2 of 7

MUD PROGRAM

MUD TYPE

Surface - 3200'

fresh water system

3200' - TD'

fresh water system

From surface to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCL substitute additive. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite. No chromate additives will be used in the mud system.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. <u>TESTING, LOGGING AND CORING PROGRAMS</u>:

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @290° +/-, and a Compensated Neutron-Formation Density Log from TD to 3500° +-. A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

The anticipated maximum bottom hole pressure is 1800 psi. It is not anticipated that abnormal temperatures will be encountered; or that any other abnormal hazards such as H2S will be encountered in this area.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

It is anticipated that the drilling operations will commence the first quarter of 2008, and take approximately seven (7) days from spud to rig release.

Ten Point Well Program
Thirteen Point Well Program
Page 3 of 7

NEWFIELD PRODUCTION COMPANY STATE #5-16-9-16 SW/NW SECTION 16, T9S, R16E DUCHESNE COUNTY, UTAH

THIRTEEN POINT SURFACE PROGRAM

1. **EXISTING ROADS**

See attached Topographic Map "A"

To reach Newfield Production Company well location site State #5-16-9-16 located in the SW¹/₄ NW¹/₄ Section 16, T9S, R16E, S.L.B. & M., Duchesne County, Utah:

Proceed in a southwesterly direction out of Myton, Utah along Highway 40 approximately 1.4 miles to the junction of this highway and Utah State Highway 53; proceed southerly along Utah State Highway 53 approximately 1.7 miles to its junction with an existing road to the southwest; proceed southwesterly approximately 9.7 miles to its junction with an existing road to the southeast; proceed southeasterly approximately 0.3 miles to its junction with an existing road to the northeast; proceed northeasterly approximately 5.1 miles to its junction with and existing road to the southwest; proceed southwesterly approximately 1.8 miles to its junction with an existing road to the northwest; proceed in a northwesterly direction approximately 1.4 miles to its junction with the beginning of the proposed access road to the south; proceed southwesterly along the proposed access road approximately 2,640'; turn and proceed in a southwesterly direction along the proposed access road approximately 930' to the proposed well location.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to the point where Highway 216 exists to the South, thereafter the roads are constructed with existing materials and gravel. The highways are maintained by Utah State road crews. All other roads are maintained by County crews.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal.

2. PLANNED ACCESS ROAD

Approximately 3,570' of access road is proposed. See attached Topographic Map "B".

The proposed access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%.

There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

Ten Point Well Program
Thirteen Point Well Program
Page 4 of 7

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. LOCATION OF EXISTING WELLS

Refer to EXHIBIT B.

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted Desert Tan. All facilities will be painted within six months of installation.

5. LOCATION AND TYPE OF WATER SUPPLY

Fresh water purchased from the Johnson Water District will be used for drilling. A temporary poly pipeline may be used for water transportation from our existing supply line from Johnson Water District, or trucked from Newfield Production Company's injection facilities – **EXHIBIT** A.

There will be no water well drilled at this site.

6. SOURCE OF CONSTRUCTION MATERIALS

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. METHODS FOR HANDLING WASTE DISPOSAL

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

Ten Point Well Program
Thirteen Point Well Program
Page 5 of 7

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

8. <u>ANCILLARY FACILITIES</u>:

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT:**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. PLANS FOR RESTORATION OF SURFACE:

a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP:** State of Utah

12. OTHER ADDITIONAL INFORMATION:

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

The Archaeological Cultural Resource Survey Report is attached. Refer to Exhibit "D".

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the State 5-16-9-16, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the State 5-16-9-16 Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office shall be notified upon site completion prior to moving on the drilling rig.

Ten Point Well Program
Thirteen Point Well Program
Page 7 of 7

13. LESSEE'S OR OPERATOR'S REPRENSENTATIVE AND CERTIFICATION:

Representative

Name:

Dave Allred

Address:

Newfield Production Company

Route 3, Box 3630

Myton, UT 84052

Telephone:

(435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #5-16-9-16, SW/NW Section 16, T9S, R16E, LEASE #ML-16532, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Hartford Accident #4471291.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.


11/19/07

Date

Mandie Crozier

Regulatory Specialist


Newfield Production Company





NEWFIELD PRODUCTION COMPANY CROSS SECTIONS 9 MILE 5-16-9-16 20, ٠ij 1" = 50'STA. 2+90 Ш STA. 2+20 1" = 50'EXISTING **GRADE** FINISHED GRADE 20, jj. WELL HEAD STA. 1+60 1" = 50'20, - [] 1" = 50'STA. 0+00 ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards) ITEM CUT FILL 6" TOPSOIL **EXCESS** Topsoil is not included in Pad Cut PAD 6,110 4,520 1,590 NOTE: UNLESS OTHERWISE NOTED PIT 640 640 0 CUT SLOPES ARE AT 1:1 TOTALS 6,750 1,050 4,520 2,230 FILL SLOPES ARE AT 1.5:1


SURVEYED BY: C.M.	DATE SURVEYED: 10-10-07
DRAWN BY: F.T.M.	DATE DRAWN: 10-31-07
SCALE: $1" = 50'$	REVISED:


/Tri~State (435) 781–2501 /Land~Surveying,~Inc. 180 North Vernal ave. Vernal, Utah 84078














2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

Exhibit "D"

CULTURAL RESOURCE INVENTORY OF NEWFIELD EXPLORATION'S TEN 40 ACRE PARCELS IN TOWNSHIP 9S, RANGE 16E, SECTION 16 DUCHESNE COUNTY, UTAH

By:

Jacki A. Montgomery

Prepared For:

State of Utah
School & Institutional Trust Lands Administration
Salt Lake City

Prepared Under Contract With:

Newfield Exploration Company Rt. 3 Box 3630 Myton, UT 84052

Submitted By:

Keith R. Montgomery Montgomery Archaeological Consultants, Inc. P.O. Box 219 Moab, Utah 84532

MOAC Report No. 07-348


October 31, 2007

United States Department of Interior (FLPMA)
Permit No. 07-UT-60122

State of Utah Public Lands Policy Archaeological Survey Permit No. 117

State of Utah Antiquities Project (Survey)
Permit No. U-07-MQ-1297s

APD RECEIVED: 11/29/2007	API NO. ASSIGNED: 43-013-33849
WELL NAME: STATE 5-16-9-16	
OPERATOR: NEWFIELD PRODUCTION (N2695)	PHONE NUMBER: 435-646-3721
CONTACT: MANDIE CROZIER	
PROPOSED LOCATION:	INSPECT LOCATN BY: / /
SWNW 16 090S 160E	
SURFACE: 2043 FNL 0758 FWL	Tech Review Initials Date
BOTTOM: 2043 FNL 0758 FWL	Engineering DKN 1/24/08
COUNTY: DUCHESNE	Geology
LATITUDE: 40.03252 LONGITUDE: -110.1304 UTM SURF EASTINGS: 574194 NORTHINGS: 44315	Surface
FIELD NAME: MONUMENT BUTTE (105	
LEASE TYPE: 3 - State LEASE NUMBER: ML-16532 SURFACE OWNER: 3 - State	PROPOSED FORMATION: GRRV COALBED METHANE WELL? NO
Plat Bond: Fed[] Ind[] Sta[] Fee[] (No. B001834) Potash (Y/N) Oil Shale 190-5 (B) or 190-3 or 190-13 Water Permit (No. MUNICIPAL) RDCC Review (Y/N) (Date:) Fee Surf Agreement (Y/N) Intent to Commingle (Y/N)	LOCATION AND SITING: R649-2-3. Unit:
STIPULATIONS: 1- Spacing Se 2- STATEM	(12-13-07) ip ENT OF RASIS Cont Stip



Application for Permit to Drill

Statement of Basis

12/19/2007

Utah Division of Oil, Gas and Mining

Page 1

APD No

Operator

API WellNo

Status

Well Type OW

Surf Ownr S

CBM

No

630

43-013-33849-00-00

Surface Owner-APD

NEWFIELD PRODUCTION COMPANY

Unit

Well Name STATE 5-16-9-16 Field

MONUMENT BUTTE

Type of Work

Location

SWNW 16 9S 16E S 2043 FNL 758 FWL

GPS Coord (UTM) 574194E 4431518N

Geologic Statement of Basis

Newfield proposes to set 290' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 2,900'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 16. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought high enough to cover the estimated base of the moderately saline ground water.

Brad Hill

12/19/2007

APD Evaluator

Date / Time

Surface Statement of Basis

The general area is approximately 22 miles southwest of Myton, Utah in the upper Castle Peak area. Castle Peak Draw runs in a northeasterly direction about 14 miles and joins Pariette Draw. Pariette Draw continues in a southeasterly direction about 6 miles and joins the Green River about 6 miles below Ouray Utah. Pariette Draw contains a perennial stream somewhat consisting of irrigation runoff and seepage. No streams springs or seeps occur in the area. An occasional pond constructed to store runoff for livestock or wildlife exists. Drainages are ephemeral only flowing during spring snowmelt or following intense summer rainstorms. Broad flats or rolling topography intersected by drainages with gentle to moderate side-slopes characterize the area. Access to the area from Myton, Utah is following State of Utah Hwy. 40 and Duchesne County and oilfield development roads a distance of 22.1 miles. Construction of 930 feet of new road will be required.

The proposed State #5-16-9-16 oil well location is in a small bowl that drains gently to the northeast. The bowl is surrounded on 3 sides by low hills with bedrock outcrops. The reserve pit will be cut into the hill on the west. Most of the location is in gentle terrain. Slight overland flow may occasionally occur from the south but most will be intercepted by the location topsoil stockpile. No diversions are recommended. The selected site poses no apparent surface concerns and appears to be a good location for constructing a pad, drilling and operating a well. The area was covered with about 10 inches of snow during the evaluation. Both the surface and minerals are owned by SITLA.

Daniel Emmett representing the Utah Division of Wildlife Resources stated the area is classified as substantial value sage grouse brooding habitat and crucial yearlong antelope habitat. He ask Mr. Allred of Newfield and Mr. Davis of SITLA that they try to schedule construction and drilling around the critical period of March 1 to June 15th for sagegrouse brooding. No restrictions for the antelope were requested. No other wildlife are expected to be significantly affected. Mr. Emmett gave Mr. Allred of Newfield Production Company and Mr. Davis of SITLA a copy of his evaluation and also a seed mix recommendation to be used when the reserve pit and location are reclaimed.

Floyd Bartlett

12/13/2007

Onsite Evaluator

Date / Time

Application for Permit to Drill Statement of Basis

12/19/2007

Utah Division of Oil, Gas and Mining

Page 2

Conditions of Approval / Application for Permit to Drill

Category

Condition

Pits

A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be

properly installed and maintained in the reserve pit.

Surface

The reserve pit shall be fenced upon completion of drilling operations.

Utah Division of Oil, Gas and Mining

Operator

NEWFIELD PRODUCTION COMPANY

Well Name

STATE 5-16-9-16

API Number

43-013-33849-0

APD No 630

Tw

Field/Unit MONUMENT BUTTE

Location: 1/4,1/4 SWNW

Sec 16

9S **Rng** 16E

2043 FNL 758 FWL

GPS Coord (UTM) 574203

4431525

Surface Owner

Participants

Floyd Bartlett (DOGM), David Allred (Newfield Production Company), Cory Miller (Tri-State Land Surveying), Jim Davis (SITLA), Daniel Emmett (Utah Division of Wildlife Resources).

Regional/Local Setting & Topography

The general area is approximately 22 miles southwest of Myton, Utah in the upper Castle Peak area. Castle Peak Draw runs in a northeasterly direction about 14 miles and joins Pariette Draw. Pariette Draw continues in a southeasterly direction about 6 miles and joins the Green River about 6 miles below Ouray Utah. Pariette Draw contains a perennial stream somewhat consisting of irrigation runoff and seepage. No streams springs or seeps occur in the area. An occasional pond constructed to store runoff for livestock or wildlife exists. Drainages are ephemeral only flowing during spring snowmelt or following intense summer rainstorms. Broad flats or rolling topography intersected by drainages with gentle to moderate side-slopes characterize the area. Access to the area from Myton, Utah is following State of Utah Hwy. 40 and Duchesne County and oilfield development roads a distance of 22.1 miles. Construction of 930 feet of new road will be required.

The proposed State #5-16-9-16 oil well location is in a small bowl that drains gently to the northeast. The bowl is surrounded on 3 sides by low hills with bedrock outcrops. The reserve pit will be cut into the hill on the west. Most of the location is in gentle terrain. Slight overland flow may occasionally occur from the south but most will be intercepted by the location topsoil stockpile. No diversions are recommended. The selected site poses no apparent surface concerns and appears to be a good location for constructing a pad, drilling and operating a well. The area was covered with about 10 inches of snow during the evaluation. Both the surface and minerals are owned by SITLA.

Surface Use Plan

Current Surface Use

Grazing

Recreational

Wildlfe Habitat

New Road

Miles Well Pad

Src Const Material

Surface Formation

0.09

Width 199

Length 290

Onsite

UNTA

Ancillary Facilities N

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetland N

Flora / Fauna

Area was covered with snow. Vegetation is a Deseret shrub type. Identified or expected vegetation consisted of black sagebrush, shadscale, greasewood, mustard weed, rabbit brush, horsebrush, broom snakeweed, and spring annuals.

Cattle, prairie dogs, antelops, small mammals and birds. Golden eagle have been sited in the general area.

Soil Type and Characteristics

Moderately shallow sandy clay loam with some surface rock.

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diverson Required N

Berm Required? N

Erosion Sedimentation Control Required? N

Slight overland flow may occasionally occur from the south but most will be intercepted by the location topsoil stockpile. No diversions are recommended.

Paleo Survey Run? Y

Paleo Potental Observed? N

Cultural Survey Run? Y

Cultural Resources? N

Reserve Pit

Site-Specific Factors		Site 1	Ranking		
Distance to Groundwater (feet)	>200		0		
Distance to Surface Water (feet)	>1000		0		
Dist. Nearest Municipal Well (ft)	>5280		0		
Distance to Other Wells (feet)	300 to 1320		10		
Native Soil Type	Mod permeability		10		
Fluid Type	Fresh Water		5		
Drill Cuttings	Normal Rock		0		
Annual Precipitation (inches)	<10		0		
Affected Populations	<10		0		
Presence Nearby Utility Conduits	Not Present		0		
		Final Score	25	1	Sensitivity Level

Characteristics / Requirements

A 40' x 80' x 8' deep reserve pit is planned in an area of cut on the northwest side of the location. A pit liner is required. Newfield commonly uses a 16 mil liner.

Closed Loop Mud Required? N Liner Required? N Liner Thickness 16 Pit Underlayment Required? N

Other Observations / Comments

ATV's used to reach site. Site under 10 inches of snow.


Floyd Bartlett

12/13/2007

Evaluator

Date / Time

2008-01 Newfield State 5-16-9-16



BOPE REVIEW

Well Name	Newfield State 5-16-9-16 API# 43-013-33849					
INPUT						
Well Name	Newfield State 5-16-9-16 API# 43-013-33849					
	String 1 String 2 String 3 String 4					
Casing Size (")	20 13 3/8					
Setting Depth (TVD)	400 6500					
Previous Shoe Setting Depth (TVD)	0 400 0 0					
Max Mud Weight (ppg)	8.4 8.4					
BOPE Proposed (psi)	0 2000					
Casing Internal Yield (psi)	2950 4810					

Calculations	String 1	20	14	·
Max BHP [psi]	.052*Setting Depth*MW =	175	1	
			BOPE Adequate	For Drilling And Setting Casing at Depth?
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	127	NO	
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	87		No expected pressures @ Set dept 4
			*Can Full Expect	ted Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth) =	. 87		
Required Casing/BOPE Test	Pressure	400	psi	
*Max Pressure Allowed @ Pi	0	psi	*Assumes 1psi/ft frac gradient	

Calculations	String 2	13 3/8 "	
	05010 - 11 - 12 - 11 - 11 - 11	0000	
Max BHP [psi]	.052*Setting Depth*MW =	2839 BOPE Adequate For Drilling And Setting Casing at Depth?	
		BOPE Adequate For Drining And Setting Casing at Deptire	
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) =	2059 NO	
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) =	1409 YES	
		*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth) =	(149) (NO)	
Required Casing/BOPE Test	Pressure	2000 psi / i	
Max Pressure Allowed @ P	revious Casing Shoe =	400 p3i 4 *Assumes 1psi/ft frac gradient	

Well name:

2008-01 Newfield State 5-16-9-16

Operator:

Newfield Production Company

String type:

Surface

Project ID:

43-013-33849

Location:

Duchesne County

Minimum design factors:

Environment:

Collapse

Mud weight:

Design parameters:

Collapse: Design factor

H2S considered? 1.125

No 75 °F

8.400 ppg Design is based on evacuated pipe.

Surface temperature: Bottom hole temperature:

81 °F

Temperature gradient: Minimum section length: 1.40 °F/100ft 290 ft

Burst:

Design factor

1.00

Cement top:

153 ft

Burst

Max anticipated surface

pressure: Internal gradient: 352 psi 400 psi

Calculated BHP

No backup mud specified.

0.120 psi/ft Tension:

> 8 Round STC: 8 Round LTC:

Buttress:

1.80 (J) 1.80 (J) 1.60 (J)

Premium: Body yield: 1.50 (J) 1.50 (B) Non-directional string.

Tension is based on buoyed weight. Neutral point: 349 ft

Re subsequent strings:

Next setting depth: Next mud weight: Next setting BHP:

6.500 ft 8.400 ppg 2.836 psi

Fracture mud wt: Fracture depth: Injection pressure: 19.250 ppg 400 ft 400 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	400	8.625	24.00	J-55	ST&C	400	400	7.972	143
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	i̇̃75´	1370	7.851	"40Ó	2950	7.38	8	244	29.09 J

Prepared

Helen Sadik-Macdonald Div of Oil, Gas & Minerals Phone: 801-538-5357 FAX: 801-359-3940

Date: January 11,2008 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 400 ft, a mud weight of 8.4 ppg The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:

2008-01 Newfield State 5-16-9-16

Operator:

Newfield Production Company

String type:

Production

Project ID:

43-013-33849

Location:

Collapse

Duchesne County

Design parameters:

Mud weight: 8.400 ppg Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor

Environment:

H2S considered?

No

Surface temperature: Bottom hole temperature: 75 °F

Temperature gradient:

166 °F 1.40 °F/100ft

Minimum section length: 1,500 ft

Non-directional string.

Burst:

Design factor

1.00

1.125

Cement top:

103 ft

Burst

Max anticipated surface

No backup mud specified.

pressure: Internal gradient: 1,406 psi

Calculated BHP

0.220 psi/ft

2,836 psi

Tension: 8 Round STC:

1.80 (J)

8 Round LTC:

1.80 (J) **Buttress:** 1.60 (J)

Premium: Body yield: 1.50 (J)

1.50 (B)

Tension is based on buoyed weight. Neutral point:

5.674 ft

Run	Segment		Nominal		End	True Vert	Measured	Drift	Internal
Seq	Length (ft)	Size (in)	Weight (lbs/ft)	Grade	Finish	Depth (ft)	Depth (ft)	Diameter (in)	Capacity (ft³)
1	6500	5.5	15.50	J-55	LT&C	6500	6500	4.825	868.6
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	2836	4040	1.424	2836	4810	1.70	` 8 8 ´	217	2.47 J

Prepared

Helen Sadik-Macdonald Div of Oil, Gas & Minerals Phone: 801-538-5357 FAX: 801-359-3940

Date: January 11,2008 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6500 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

From:

Ed Bonner

To:

Mason, Diana

Date:

1/8/2008 12:05 PM

Subject:

Well Clearance

CC:

Davis, Jim; Garrison, LaVonne; Hill, Brad; Jarvis, Dan

The following wells have been given cultural resources clearance by the Trust Lands Cultural Resources Group:

ConocoPhillips Company

Utah 29-574D (API 43 015 30735)

EOG Resources, Inc

CWU 956-32 (API 43 047 39515)

Kerr McGee Oil & Gas Onshore LP

NBU 1021-2N (API 43 047 38840)

Newfield Production Company

Wells Draw Fed C-5-9-16 (API 43 013 33753)

State 1A-16-9-16 (API 43 013 33845)

State 2A-16-9-16 (API 43 013 33846)

State 3-16-9-16 (API 43 013 33847)

State 4-16-9-16 (API 43 013 33848)

State 5-16-9-16 (API 43 013 33849)

State 6-16-9-16 (API 43 013 33850)

State 12-16-9-16 (API 43 013 33852)

State 13-16-9-16 (API 43 013 33853)

State 16-16-9-16 (API 43 013 33854)

Pioneer Natural Resources USA, Inc

Main Canyon State 12-16-15-23 (API 43 047 39695)

Main Canyon State 34-21-15-23 (API 43 047 39696)

Horse Point State 34-10-16-23 (API 43 019 31558)

Horse Point State 41-1-16-23 (API 43 019 31599)

Grand Canyon State 23-35-15.5-23 (API 43 019 31560)

If you have any questions regarding this matter please give me a call.

Helen Sadik-Macdonald - Newfield wells

"Hans Wychgram"

To: Date:

CC:

01/09/2008 3:52 PM

Subject: Newfield wells

"Brad Mecham", "Mandie Crozier"

Helen,

As per our conversation this afternoon, Newfield agrees to set 400' of surface casing on the following wells:

State 3-16-9-16

State 4-16-9-16

State 5-16-9-16

State 6-16-9-16

State 11-16-9-16

State 12-16-9-16

State 13-16-9-16

State 16-16-9-16

Gilsonite L-32-8-17

Monument Butte F-36-8-16

Also, we discussed setting 300' of 20" conductor casing on the following deep gas wells:

Beluga 16T-5-9-17

Monument Butte 4-36T-8-16

Thanks,

Hans Wychgram



MICHAEL R. STYLER
Executive Director

State WUtah

DEPARTMENT OF NATURAL RESOURCES

Division of Oil Gas and Mining

JOHN R. BAZA
Division Director

GARY R. HERBERT
Lieutenant Governor

January 24, 2008

Newfield Production Company Rt. #3, Box 3630 Myton, UT 84052

Re:

State 5-16-9-16 Well, 2043' FNL, 758' FWL, SW NW, Sec. 16, T. 9 South, R. 16 East,

Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann.§ 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-33849.

Sincerely,

Gil Hunt

Associate Director

pab

Enclosures

cc:

Duchesne County Assessor

SITLA



Operator:	Newfield Production Company					
Well Name & Number	State 5-16-9-16					
API Number:	43-013-33849					
Lease:	ML-16532					
Location: SW NW	Sec. 16 T. 9 South R. 16 East					

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis
- 24 hours prior to spudding the well contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well contact Dustin Doucet
- Any changes to the approved drilling plan contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

• Dan Jarvis at:

(801) 538-5338 office

(801) 942-0873 home

• Carol Daniels at:

(801) 538-5284 office

• Dustin Doucet at:

(801) 538-5281 office

(801) 733-0983 home

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

Page 2 43-013-33849 January 24, 2008

- 4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
- 5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
- 6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
- 7. Surface casing shall be cemented to the surface.

STATE OF UTAH

DIVISION OF OIL, GAS, AND MINIT	5. LEASE DESIGNATION AND SERIAL NO. ML-16532				
1. SUNDRY NOTICES AND REPORTS	6. IF INDIAN, ALLOTTEE OR TRIBAL NAME				
Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plu Use "APPLICATION FOR PERMIT TO DRILL OR DEEPEN form	N/A				
	7. UNIT AGREEMENT NAME				
OIL GAS WELL X OTHER	NA				
2. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY		8. WELL NAME and NUMBER STATE 5-16-9-16			
3. ADDRESS AND TELEPHONE NUMBER Rt. 3 Box 3630, Myton Utah 84052 435-646-3721		9 API NUMBER 43-013-33849			
4. LOCATION OF WELL		10 FIELD AND POOL, OR WILDCAT			
Footages 2043 FNL 758 FWL		MONUMENT BUTTE			
QQ, SEC, T, R, M: SW/NW Section 16, T9S R161	E				
23,020, 1,14,111		COUNTY DUCHESNE STATE UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF N	NOTICE, REPORT OR OTHE				
NOTICE OF INTENT:		NT REPORT OF:			
(Submit in Duplicate)	(Submi	t Original Form Only) NEW CONSTRUCTION			
ABANDONNEW CONSTRUCTION	REPAIR CASING				
REPAIR CASING PULL OR ALTER CASING	CHANGE OF PL				
CHANGE OF PLANS RECOMPLETE	VIECTION REPERFORATE				
CONVERT TO INJECTION REPERFORATE					
FRACTURE TREAT OR ACIDIZE VENT OR FLARE	FRACTURE TREAT	OR ACIDIZE VEINT OR FLARE			
MULTIPLE COMPLETION WATER SHUT OFF	OTHER				
X OTHER APD Change	DATE WORK COMPI				
	•	ole Completion and Recompletions to different OMPLETION OR RECOMPLETION REPORT AND			
	LOG form.				
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertin	*Must be accompanies nent details, and give pertinent da	by a cement verification report. tes. If well is directionally drilled, give subsurface locations			
and measured and true vertical depth for all markers and zones pertinent to this work.					
Newfeild Production requests the following change APD.	iges be made the dr	illing program on the above mentioned approved			
Surface Casing will be set @ 290'.					
^					
13. NAME & SIGNATURE: Mandie Crozier TITLE	Regulatory Special	ist DATE 3/7/2008			
(This space for State use only)					
4/94 A DODOVED DV THE C Technistictions	On Reverse Side	•			
494APPROVED BY THE S下午中的 OF UTAH DIVISION OF					
OIL. GAS. AND MINING		COPY SENT TO OPERATOR			
DATE 3/14/08 4		210000			
BY: John Wall	RECEIVED	146			
DI.	Initials: <u>48</u>				

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Co	mpany:	N]	NEWFIELD PRODUCTION COMPANY						
Well Name:		STATE 5-16-9-16							
Api No:	43-013-3384	9		Lease 7	Гуре:	STATE			
Section_16	Township_	09S	_Range_	16E	County_	DUCHESNE	_		
Drilling Con	ntractor	ROSS	DRILL	ING		RIG# 24	· · · · · · · · · · · · · · · · · · ·		
SPUDDE	D:								
	Date	04/07/	08						
	Time	3:30	PM	To the second					
	How	DRY		··-					
Drilling wi	ill Commence	e <i>:</i> _							
Reported by	-	JIM	SMITH	<u> </u>					
Telephone#		(435) 823-20	72			···		
Date	04/08/08		Signed	CF	łD				

A W

FORM APPROVED OMB No. 1004-0135 Expires January 31,2004

FORM 3160-5

(September 2001)

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

UTAH STATE ML-16532 6. If Indian, Allottee or Tribe Name.

5. Lease Serial No.

aballuolleu w	en. Ose i omi o ioo-o (Ai	D) for such proposa		1			
SUBMIT IN T	7. If Unit or CA/A	Agreement, Name and/or					
I. Type of Well ☐ Gas Well ☐	Other			8. Well Name and	J No.		
2. Name of Operator	STATE 5-16-						
NEWFIELD PRODUCTION CO	MPANY	·		9. API Well No.			
3a. Address Route 3 Box 3630		3b. Phone (include a	re code)	4301333849			
Myton, UT 84052	g	435.646.3721		1	ol, or Exploratory Area		
4. Location of Well (Footage, 2) 2043 FNL 758 FWL	Sec., T., R., M., or Survey Descrip	otton)			MONUMENT BUTTE 11. County or Parish, State		
				Tr. County of run	non, out		
SWNW Section 16 T9S R16E				DUCHESNE, U	UT		
12. CHECK	APPROPRIATE BOX(E	S) TO INIDICATE N	ATURE OF N	OTICE, OR OT	ΓHER DATA		
TYPE OF SUBMISSION		TY	PE OF ACTION				
	Acidize	Deepen	Productio	n(Start/Resume)	■ Water Shut-Off		
■ Notice of Intent	☐ Alter Casing	Fracture Treat	Reclamati	ion	Well Integrity		
Subsequent Report	Casing Repair	■ New Construction	Recomple	te	X Other		
granderstanding the state of th	Change Plans	Plug & Abandon		ily Abandon	Weekly Status Report		
Final Abandonment	Convert to	☐ Plug Back	Water Dis	sposal			
on 4/11/08 MIRU NDSI R csgn to 1,500 psi. Vernal cement & shoe. Drill a 7.8 log's TD to surface. PU & with 300 sks cement mixe cement to reserve pit. Nip	filed only after all requirements, including # 3. Set all equipment. Filed # 3. Set all equipment. Filed # 3. Set all equipment. Filed # 4. Roosevelt DO # 5. Tiled with fresh water to # 5. TIH with Guide shoe, shoe # 6. TIH with Guide shoe, shoe # 6. TIH with Guide shoe, shoe # 7. Tiled # 5. Tile	Pressure test Kelly, TI GM office was notifed a depth of 5825'. Lay jt, float collar, 139 jt's The 400 sks cement m (@ 105,000 #'s tension	W, Choke man I of test. PU BH down drill strin s of 5.5 J-55, 15 ixed @ 14.4 pp	ifold, & Bop's to IA and tag cem Ig & BHA. Oper 5.5# csgn. Set (Ig & 1.24 yld. F	o 2;000 psi. Test 8.625 lent @ 285'. Drill out n hole log w/ Dig/SP/GR @ 5820.73' / KB. Cement Returned 2 bbls of		
I hereby certify that the foregoing is correct (Printed/ Typed)	true and	Title					
Jim Strith 4 Mg		Drilling Forer	nan				
Signature 10 1500		Date 04/16/2008					
In the second second	THIS SPACE FO	R FEDERAL OR S	CATE OFFICE	EUSE TOTAL			
COMPONE TO 10550		Title		Dat	te		
Approved by Conditions of approval, if any, are attache certify that the applicant holds legal or eq which would entitle the applicant to condu	uitable title to those rights in the subje	arrant or	2				
Title 18 U.S.C. Section 1001 and Title 43 States any false, fictitious and fraudulents	U.S.C. Section 1212, make it a crime	matter within its jurisdiction			ency of the United		
(Instructions on reverse)		****	ECEIVE	D			

APR 18 2008

NEWFIELD PRODUCTION COMPANY CASING & CEMENT REPORT

The state of the s

	e villi Historia Villiani		5 1/2"	CASING SET	AT	5820.73	-		
					Fit clir @	5799.48'			
LAST CASI	NG <u>8 5/8</u>	SET A	4 324. <u>33'</u>		OPERATOR	٦	Newfield F	Production	Company
DATUM	1:	2			WELL	State 5-16	-9-16		
DATUM TO	CUT OFF C	ASING _	12		FIELD/PRO	SPECT _	Monumen	t Butte	
DATUM TO	BRADENHE	EAD FLANGE			CONTRACT	FOR & RIG#		NDSI Rig #	3
TO DRILLER	5825'	LOGG	f 5 <u>935'</u>						
HOLE SIZE	7 7/8"			·					
CYMBRUNNY	4. GT			<u> </u>					
LOG OF CA	SING STRIN	NG:			· · · · · · · · · · · · · · · · · · ·		,		
PIECES		ITEM -	MAKE - DESC	RIPTION	WT/FT	GRD	THREAD	CONDT	LENGTH
		Landing Jt							14
		Short jt @	4020'/5.44''						
138	5 1/2"	ETC LT & C	casing		15.5#	J-55	8rd	Α	5786.88
									0.6
1	5 1/2"	ETC LT&C	csg		15.5#	J-55	8rd	Α	20.6
			GUIDE	shoe			8rd	Α	0.65
CASING INV	ENTORY B	AL.	FEET	JTS	TOTAL LEN	IGTH OF ST	RING		5822.73
TOTAL LEN	GTH OF ST	RING	5822.73	139	LESS CUT	OFF PIECE			14
LESS NON (CSG. ITEMS	}	15.25		PLUS DATU	JM TO T/CU	T OFF CSG		12
PLUS FULL	JTS. LEFT (TUC	221.29	6	CASING SE	T DEPTH			5820.73
HOLE SIZE	TOTAL		6028.77	145	1				
TOTAL CSG	DEL. (W/C	THRDS)	6028.77	145	∫ COMPAF	RE			
THING OAS	SINC 1.		1ST STAGE	2nd STAGE	<u> </u>				•
BEGIN RUN	CSG:		4/15/2008	4:30 AM	GOOD CIRC	C THRU JOE		Yes	
CSG. IN HO	E		4/15/2008	8:30 AM	-1				
BEGIN CIRC		· · · · · · · · · · · · · · · · · · ·	4/15/2008	8:30 AM	RECIPROC	ATED PIPE	FOR	_THRU	FT STROKE
BEGIN/PUM	PCMT		4/15/2008	10:25 AM			E HOLD? _		
BEGIN DSPI	. CMT		4/15/2008	11:05 AM	BUMPED PI	LUG TO _		2060	PSI
PLUG DOW	N		4/15/2008	11:30 AM					
CEMENT US	SED			CEMENT COI	MPANY-	B. J.			
STAGE	# SX			CEMENT TYP					
10 11 N	300	Premlite II w	// 10% gel + 3 °	% KCL, 3#'s /s	k CSE + 2# s	k/kolseal + 1	/2#'s/sk Cello	Flake	
<u>Grand</u>			.0 ppg W / 3.43						
2	400	50/50 poz V	V/ 2% Gel + 3%	KCL, .5%EC1	,1/4# sk C.F.				1.24 YLD
plant displace, be made with a	The garage of the	TCHER PLAC					KE & SPACIN	IG	
Centralizers	Middle fi	rst, top seco	ond & third. Th	nen every thir	d collar for a	a total of 20			
THANG	15.jp Szelfővere								
BECAN RUN	csg-								
CSG. IN HOL	The second secon							4048185	
COMPANY	REPRESEN	TATIVE			Jim Smith		DATÉ	4/`15/08	
EEGIN PUM									
regin dae									

PLUGTO III

STATE OF UTAH DIVISION OF OIL, GAS AND MINING **ENTITY ACTION FORM -FORM 6**

OPERATOR: NEWFIELD PRODUCTION COMPANY ADDRESS: RT. 3 BOX 3830 MYTON, UT 84052

OPERATOR ACCT. NO.

N2695

04/10/08

Date

ACTION CODE	CURRENT	NEW	API NUMBER				_				
	ENTITY NO.	ENTITY NO.		WELL MAKE	OC SC TP RO			LOCATION	COUNTY	BPUD DATE	EFFECTIVE
A	99999	16800	4304739733	UTE TRIBAL 2-1-5-1E	NWNE	4	58				DATE
WELL 11	COMMENTS:	Cappi)			HAMME	 	103	116	DUCHESNE	4/2/2008	14/28/08
		CACO									-
ACTION	CURRENT	NBW	API NUMBER			1	ļ				
CODE	ENTETY NO.	ENTITY NO.	ATTOMERA	WELL NAME	00	SC SC	ELL LOCA		· · · · · · · · · · · · · · · · · · ·	SPU D	EFFECTIVE
Α	99999	16801	4304739259	EEDEDAL 4.54.6.4-		<u> </u>	<u> </u>	RE	COUNTY	DATE	DATE
		7	4004133233	FEDERAL 4-24-9-17	NWNW	24	95	17E	DUCHESNE	4/2/2008	4/28/08
	(.	TRIPI)									1/00/
ACTION		7700									
CODE	CURRENT ENTRY NO.	EMITTY NO.	API NUMBER	WELL HAVE			WELL	LOCATION			
_				SUNDANCE	QQ.	8C	IP I	MU	COURTY	8PUD DATE	EFFECTIVE
B	99999	14844	4304734935	FEDERAL 8-6-9-18	SENE	ا م	00	18E			
	(()()	_				6	98	17E	DUCHESNE	4/4/2008	14/28/08
	GKAKU	BH =	SENE	Sundance Uni	+						/
ACTION	CURRENT	NEW T	API NUMBER							· · · · · · · · · · · · · · · · · · ·	
COOR	ENTITY NO.	ENTITY NO.	AN INJAMEN	WELL NAME	65	ec	WELL	OCATION		SPUD .	EFFECTIVE
A	99999	16802	4204000040				न्ह	RIG	COUNTY	DATE	DATE
			4301333849	STATE 5-16-9-16	SWNW	16	98	16E	DUCHESNE	4/7/2008	4/20/20
	<u>GR</u>	KV								3112000	1/2908
CODE	CURRENT ENTITY NO.	NEW	API NIAMPER	WELL NAME							
	2407110	ENTITY NO.			00	\$C	TP TP	DCATION RG	COUNTY	BPUD	EFFECTIVE
										DATE	DATE
VELL 5 CO	MMENTS:				<u> </u>						
спом	CURRENT	NEW	48000000								
CODE	ENTITY NO.	ENTITY NO.	API NUMBER	WELLINWE			WELL	CATION	<u> </u>	SPUD	
					000	SC	TP	Rick	COUNTY	DATE	EFFECTIVE DATE
ELL 6 CO	MMENTS:					1					
TION CO	DES (See instructions on baci								. .		
A-1194	Per seriity for save well (single v	vat only)							/	-/_/	
B-*wa	ell to existing entity (group or a mana axisting solity to ancilla	iriti well)							11/1	1/1/1	
D - Me	I from one existing entity to a	new entity						-	Significance	4101	Jentri Park
E- bar	r (explain in comment): section)						_	7	/	
								<u> </u>	roduction Clerk	7	04/10/09

DIV. OF OIL, GAS & MINING APR 1 0 2008

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES 5. LEASE DESIGNATION AND SERIAL NUMBER: DIVISION OF OIL, GAS AND MINING UTAH STATE ML-16532 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: SUNDRY NOTICES AND REPORTS ON WELLS 7. UNIT or CA AGREEMENT NAME: Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. 1. TYPE OF WELL: 8. WELL NAME and NUMBER: OIL WELL GAS WELL OTHER STATE 5-16-9-16 2. NAME OF OPERATOR: 9. API NUMBER: NEWFIELD PRODUCTION COMPANY 4301333849 3. ADDRESS OF OPERATOR: 10. FIELD AND POOL, OR WILDCAT: PHONE NUMBER Route 3 Box 3630 CITY Myton STATE UT ZIP 84052 435.646.3721 MONUMENT BUTTE 4. LOCATION OF WELL: FOOTAGES AT SURFACE: 2043 FNL 758 FWL COUNTY: DUCHESNE OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SWNW, 16, T9S, R16E STATE: UT

II. CHECK APPRO	PRIATE BOXES TO INDICATI	E NATURE OF NOTICE, REPO	ORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION							
☐ NOTICE OF INTENT	ACIDIZE	DEEPEN	REPERFORATE CURRENT FORMATION					
(Submit in Duplicate)	ALTER CASING	FRACTURE TREAT	SIDETRACK TO REPAIR WELL					
Approximate date work will	CASING REPAIR	NEW CONSTRUCTION	TEMPORARITLY ABANDON					
	CHANGE TO PREVIOUS PLANS	OPERATOR CHANGE	TUBING REPAIR					
	CHANGE TUBING	PLUG AND ABANDON	VENT OR FLAIR					
SUBSEQUENT REPORT	CHANGE WELL NAME	☐ PLUG BACK	WATER DISPOSAL					
(Submit Original Form Only) Date of Work Completion:	CHANGE WELL STATUS	PRODUCTION (START/STOP)	WATER SHUT-OFF					
Date of work Completion;	COMMINGLE PRODUCING FORMATIONS	RECLAMATION OF WELL SITE	OTHER: - Weekly Status Report					
05/20/2008	CONVERT WELL TYPE	RECOMPLETE - DIFFERENT FORMATION						

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The above subject well was completed on 05/14/08, attached is a daily completion status report.

NAME (PLEASE PRINT) Jentri Park TITLE Production Clerk 05/20/2008 SIGNATURE DATE

(This space for State use only)

RECEIVED MAY 27 2008

Daily Activity Report

Format For Sundry STATE 5-16-9-16 3/1/2008 To 7/30/2008

5/3/2008 Day: 1

Completion

Rigless on 5/2/2008 - Install 5m frac head. NU 6" 5K Cameron BOP. RU H/O truck & pressure test casing, blind rams, frac head, csg & casing valves to 4500 psi. RU Perforators LLC WLT w/ mast & run CBL under pressure. WLTD @ 5757' & cement top @ 70'. Perforate stage #1, CP3 sds @ 5698-5706' w/ 3-1/8" Slick Guns (19 gram, .49"EH. 120°) w/ 4 spf for total of 32 shots. 136 BWTR. SWIFN.

5/8/2008 Day: 2

Completion

Rigless on 5/7/2008 - Stage #1, CP3 sands. RU BJ Services. 0 psi on well. Frac CP3 sds w/ 34,586#'s of 20/40 sand in 434 bbls of Lightning 17 fluid. Broke @ 3030 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 1941 psi @ ave rate of 23.2 BPM. Pumped 504 gals of 15% HCL in flush for Stage #2. ISIP 2046 psi. Leave pressure on well. Stage #2, LODC sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 8' perf gun. Set plug @ 5440'. Perforate LODC sds @ 5334-42' w/ 3-1/8" Slick Guns w/ 4 spf for total of 32 shots. RU BJ Services. 1674 psi on well. Frac LODC sds w/ 24,721#'s of 20/40 sand in 348 bbls of Lightning 17 fluid. Broke @ 1889 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2425 psi @ ave rate of 23.2 BPM. Pumped 504 gals of 15% HCL in flush for Stage #3. ISIP 2165 psi. Leave pressure on well. 918 BWTR Stage #3, A.5 sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 11' perf gun. Set plug @ 5180'. Perforate A.5 sds @ 5080- 91' w/ 3-1/8" Slick Guns w/ 4 spf for total of 44 shots. RU BJ Services. 1708 psi on well. Frac A.5 sds w/ 84,098#'s of 20/40 sand in 666 bbls of Lightning 17 fluid. Broke @ 3959 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 2065 psi @ ave rate of 23.2 BPM. Pumped 504 gals of 15% HCL in flush for Stage #4. ISIP 2582 psi. Leave pressure on well. 1584 BWTR Stage #4, B2 sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 6' perf gun. Set plug @ 5040'. Perforate B2 sds @ 4968- 74' w/ 3-1/8" Slick Guns w/ 4 spf for total of 24 shots. RU BJ Services. 1921 psi on well. Frac B2 sds w/ 24,764#'s of 20/40 sand in 354 bbls of Lightning 17 fluid. Broke @ 3710 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 3365 psi @ ave rate of 23.3 BPM. Pumped 504 gals of 15% HCL in flush for Stage #5. ISIP 2959 psi. Leave pressure on well. 1938 BWTR Stage #5, D2 sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 7' perf gun. Set plug @ 4880'. Perforate D2 sds @ 4778- 85' w/ 3-1/8" Slick Guns w/ 4 spf for total of 28 shots. RU BJ Services. 1452 psi on well. Frac D2 sds w/ 24,664#'s of 20/40 sand in 341 bbls of Lightning 17 fluid. Broke @ 3618 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 1975 psi @ ave rate of 23.3 BPM. Pumped 504 gals of 15% HCL in flush for Stage #6. ISIP 1906 psi. Leave pressure on well. 2279 BWTR Stage #6, GB4 sands. RU Lone Wolf WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" 5K composite flow through frac plug & 12' perf gun. Set plug @ 4280'. Perforate GB4 sds @ 4170-82' w/ 3-1/8" Slick Guns w/ 4 spf for total of 48 shots. RU BJ Services. 1466 psi on well. Frac GB4 sds w/ 59,402#'s of 20/40 sand in 511 bbls of Lightning 17 fluid. Broke @ 3066 psi. Pumped 780 gals of fresh wtr mixed with 30 gals of Techni-Hib 767W. Treated w/ ave pressure of 1805 psi @ ave rate of

23.3 BPM. ISIP 1929 psi. Begin immediate flowback on 12/64 choke @ 1 BPM. Flowed for 7 1/2 hrs & died. Rec. 430 BTF. SIWFN w/ 2360 BWTR.

5/9/2008 Day: 3

Completion

Leed #712 on 5/8/2008 - MIRU Leed rig 712. 100 psi on well. Bleed off pressure. ND Cameron BOP & 5M WH. NU 3M WH & Shaffer BOP. Talley PU & RIH w/ 4 3/4" chomp bit, bit sub & 2 7/8" J- 55 tbg. Tagged sand @4259'. RU Nabors power swivel. Circulate sand & drill out plugs. Sand @ 4259', Plug @ 4280', Drilled up in 40 mins, Tagged sand @ 4625', Circulate clean down to plug @ 4880'. SIWFN w/ 2335 BWTR.

5/13/2008 Day: 4

Completion

Leed #712 on 5/12/2008 - 25 psi on well. Bleed off pressure. Continue to clean out sand & drill out plugs. Plug @ 4880' (Drilled out in 18 mins). Tagged sand @ 5032', Plug @ 5040' (Drilled out in 28 mins), Tagged sand @ 5146', Plug @ 5180' (Drilled up in 23 mins). Tagged plug @ 5440', (Drilled up in 19 mins). Tagged fill @ 5657'. C/O to PBTD @ 5799'. RD power swivel. LD 2 jts of tbg. EOT @ 5738'. RU swab equipment. IFL @ sfc. Made 14 runs. Rec 150 BTF. FFL @ 1200'. Trace of oil, No sand. RD swab equipment. TIH w/ tbg. Tagged sand @ 5754'. Circulate clean down to PBTD @ 5799'. LD 4 jts of tbg. EOT 5680'. SIWFN w/ 2280 BWTR.

5/14/2008 Day: 5

Completion

Leed #712 on 5/13/2008 - 25 psi on well. Bleed off pressure. TOH w/ tbg. LD bit & bit sub. PU & RIH w/ production tbg as follows: BP, 4- jts, 2 7/8" nipple, PBGA, 1- jt, SN, 2-jts, TA, 168 jts of 2 7/8" J-55 tbg. ND BOP, Set TA w/ 15,000#'s of tension @ 5280'. Land tbg on flange. NU WH. Prime up rod pump. PU & RIH w/ follow: CDI: 2 1/2" X 1 1/2" X 18' RHAC, 6- 1 1/2" wtr bars, 20- 3/4" guided rods, 93- 3/4" plain rods, 94- 3/4" guided rods, 1-2' X 3/4" sub, 1 1/2" X 26' Polish rod. Space out rods. 2280 BWTR. Left well down due to surface equipment, Final report will follow.

5/15/2008 Day: 6

Completion

Rigless on 5/14/2008 - Complete flow line ty in. Adjust tag. PWOP @ 1:00 pm w/74" SL & 5 SPM. Final report.

Pertinent Files: Go to File List



UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE* FORM APPROVED

(See other instructions ons reverse side)

OMB NO. 1004-0137

Expires: February 28, 1995

5. LEASE DESIGNATION AND SERIAL NO.

ML-16532

WELL	COM	PLETION	OR RI	COMP	LETION	REPORT A	ND LOG*	6. IF INDIAN, ALLOT	TEE OR TRIBE NAME NA		
1a. TYPE OF WORK								7. UNIT AGREEMEN	T NAME		
		OIL WELL	X	GAS WELL	DRY	Other			State		
1b. TYPE OF WELL	•										
NEW X	NEW X WORK DEEPEN PLUG DIFF BACK RESVR. Other State						NAME, WELL NO. Se 5-16-9-16				
WELL ^				BACK	RESVR.	Other		9. WELL NO.	<u>e 5-10-9-10</u>		
2. NAME OF OPERATOR		Ne	wfield F	xnloration	n Compan	v			013-33849		
3. ADDRESS AND TELEPHONE NO. 10. FIELD AND POOL OR V											
									ument Butte		
` `									R BLOCK AND SURVEY		
At Surface		2043	FNL & 7	'58' FWL (S	W/NW) Sec	. 16, 19S, R16E		OR AREA	1		
At top prod. Interval re	ported belo	w						Sec.	6, T9S, R16E		
At total depth			14. API NO. 43-013-33849			DATE ISSUED	1/24/08	12. COUNTY OR PAR	1		
16 DATE COURDED	16 DATE 3	Γ.D. REACHED	17 DA	TE COMPL. (Rea			0F, RKB, RT, GR, ETC	Duchesne	19. ELEV. CASINGHEAD		
15. DATE SPUDDED 04/07/08		04/14/08	I /. DA	05/14		5922		5934' KB	19. ELEV, CASINGHEAD		
20. TOTAL DEPTH, MD &		21. PLUG BAC	K T.D., MD		22. IF MULTIF		23. INTERVALS	ROTARY TOOLS	CABLE TOOLS		
·		1			HOW MAN	1A*	DRILLED BY				
5825'			5799'				>	X			
24. PRODUCING INTERV	AL(S), OF T	HIS COMPLETION-	TOP, BOTT	OM, NAME (MD	AND TVD)*				25. WAS DIRECTIONAL		
				Green Riv	er 4170)'-5706'			SURVEY MADE		
									No No		
26. TYPE ELECTRIC AN			naatad	Donoity	Compone	atad Nautran (CP Coliner	Cement Bond Log	27. WAS WELL CORED No		
	Guard,	SF, Compe	nsaleu					Cement Bond Log	NU		
23. CASING SIZE/	CDADE	WEIGHT	IB/FT	DEPTH S		port all strings set in v HOLE SIZE		ENT, CEMENTING RECORD	AMOUNT PULLED		
8-5/8"	J-55	24			24'	12-1/4"		ith 160 sx Class "G" cn			
5-1/2"		15.	5#	# 5821'			300 sx Premlit	e II and 400 sx 50/50 F	oz		
29.		LIN	ER RECO	RD			30.	TUBING RECORD			
SIZE	<u> </u>	TOP (MD)	вотто	M (MD)	SACKS CEMENT	* SCREEN (MD)	2-7/8"	DEPTH SET (MD)	PACKER SET (MD)		
	<u> </u>						2-1/0	EOT @ 5508'	5280'		
	1						LOYD CYYOT I	FRACTURE, CEMENT SO			
31. PERFORATION REG		val, size and number		ZE S	SPF/NUMBE	R 32.			OF MATERIAL USED		
IN'	INTERVAL (CP3) 5608' 5706'							Frac w/ 34,586# 20/4	0 sand in 434 bbls fluid		
<u>IN'</u>	(CP	3) 5698'-5706'	.4		4/32	5698'-					
<u>IN.</u>	_ `	3) 5698'-5706' C) 5334'-5342'		9"	4/32 4/32	5698'- 5334'-		Frac w/ 24,721# 20/4	0 sand in 348 bbls fluid		
IN	(LOD	C) 5334'-5342'	.4	9" 9"	4/32	5334'-	-5342'				
IN	(LOD	C) 5334'-5342' 5) 5080'-5091'	.4 .4	9" 9" 9"			-5342' -5091'	Frac w/ 84,098# 20/4	0 sand in 348 bbls fluid 0 sand in 666 bbls fluid 0 sand in 354 bbls fluid		
IN	(LOD	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974'	.4 .4 .4	9" 9" 9" 9"	4/32 4/44 4/24	5334'- 5080'- 4968'-	-5342' -5091' -4974'	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4	0 sand in 666 bbls fluid		
IN	(LOD) (A. (B	C) 5334'-5342' 5) 5080'-5091'	.4 .4 .4 .4	9" 9" 9" 9"	4/32 4/44	5334'- 5080'-	-5342' -5091' -4974' -4785'	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid		
IN	(LOD) (A. (B	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785'	.4 .4 .4 .4	9" 9" 9" 9"	4/32 4/44 4/24 4/28	5334'- 5080'- 4968'- 4778'-	-5342' -5091' -4974' -4785'	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid		
IN	(LOD) (A. (B	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785'	.4 .4 .4 .4	9" 9" 9" 9"	4/32 4/44 4/24 4/28	5334'- 5080'- 4968'- 4778'-	-5342' -5091' -4974' -4785'	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid		
IN	(LOD) (A. (B	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785'	.4 .4 .4 .4	9" 9" 9" 9"	4/32 4/44 4/24 4/28	5334'- 5080'- 4968'- 4778'-	-5342' -5091' -4974' -4785'	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid		
	(LOD) (A. (B	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785'	.4 .4 .4 .4	9" 9" 9" 9"	4/32 4/44 4/24 4/28 4/48	5334'- 5080'- 4968'- 4778'-	-5342' -5091' -4974' -4785'	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid		
33.* DATE FIRST PRODUCTION 05/14/	(LOD) (A. (B (D (GB	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785' 4) 4170'-4182'	.4 .4 .4 .4	9" 9" 9" 9" 9" 9"	4/32 4/44 4/24 4/28 4/48	5334'- 5080'- 4968'- 4778'- 4170'- UCTION Ind type of pump) 18' RHAC SM	-5342' -5091' -4974' -4785' -4182' Plunger Pum	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4 Frac w/ 59,402# 20/4	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid 0 sand in 511 bbls fluid LSTATUS (Producing or shut-in) PRODUCING		
33.* DATE FIRST PRODUCTI	(LOD) (A. (B (D (GB	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785' 4) 4170'-4182'	.4 .4 .4 .4	9" 9" 9" 9" 9" 9" (Flowing, gas lift/2" x 1-1/2	4/32 4/44 4/24 4/28 4/48 PROD pumping-size ai 2" x 16' x '	5334'- 5080'- 4968'- 4778'- 4170'- UCTION ad type of pump)	-5342' -5091' -4974' -4785' -4182'	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4 Frac w/ 59,402# 20/4	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid 0 sand in 511 bbls fluid		
33.* DATE FIRST PRODUCTI 05/14/ DATE OF TEST 06-21-08	(LOD) (A. (B (D (GB	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785' 4) 4170'-4182'	.4 .4 .4 .4 .4 .4 .4 .4 .4	9" 9" 9" 9" 9" 9" Flowing, gas lift 2" x 1-1/2 E SIZE PT	4/32 4/44 4/24 4/28 4/48 PROD , pumping—size ai 2" x 16' x '	5334'- 5080'- 4968'- 4778'- 4170'- UCTION d type of pump) 8' RHAC SM OIL-BBLS.	-5342' -5091' -4974' -4785' -4182' Plunger Pum	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4 Frac w/ 59,402# 20/4 Prac w/ 59,402# 20/4 NP WATER-BBL.	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid 0 sand in 511 bbls fluid 0 sand in 511 bbls fluid L STATUS (Producing or shut-in) PRODUCING GAS-OIL RATIO 1574		
33.* DATE FIRST PRODUCTI 05/14/ DATE OF TEST	(LOD) (A. (B (D (GB	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785' 4) 4170'-4182'	.4 .4 .4 .4 .4 .4 .1 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4	9" 9" 9" 9" 9" 9" 9" 5" 9" 9" 1-1/2" x 1-1/2	4/32 4/44 4/24 4/28 4/48 PROD , pumping-size ac 2" x 16' x 200'N. FOR SST PERIOD	5334'- 5080'- 4968'- 4778'- 4170'- UCTION and type of pump) 18' RHAC SM OILBBLS.	-5342' -5091' -4974' -4785' -4182' Plunger Pum	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4 Frac w/ 59,402# 20/4 mp WATER-BBL.	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid 0 sand in 511 bbls fluid L STATUS (Producing or shut-in) PRODUCING GAS-OIL RATIO		
33.* DATE FIRST PRODUCTI 05/14/ DATE OF TEST 06-21-08	(LOD) (A. (B (D (GB	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785' 4) 4170'-4182' PRODUCTIO	.4 .4 .4 .4 .4 .4 .1 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4	9" 9" 9" 9" 9" 9" 9" Eliant	4/32 4/44 4/24 4/28 4/48 PROD , pumping—size ai 2" x 16' x '	5334'- 5080'- 4968'- 4778'- 4170'- UCTION d type of pump) 8' RHAC SM OIL-BBLS.	-5342' -5091' -4974' -4785' -4182' Plunger Pum	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4 Frac w/ 59,402# 20/4 Prac w/ 59,402# 20/4 NP WATER-BBL.	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid 0 sand in 511 bbls fluid 0 sand in 511 bbls fluid L STATUS (Producing or shut-in) PRODUCING GAS-OIL RATIO 1574		
33.* DATE FIRST PRODUCTI 05/14/ DATE OF TEST 06-21-03 FLOW, TUBING PRESS.	(LOD) (A. (B (D (GB	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785' 4) 4170'-4182' PRODUCTIO HOURS TESTED CASING PRESSUR	.4 .4 .4 .4 .4 .4 .1 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4	9" 9" 9" 9" 9" 9" 9" 5" 9" 9" 1-1/2" x 1-1/2	4/32 4/44 4/24 4/28 4/48 PROD , pumping—size ai 2" x 16' x '	5334'- 5080'- 4968'- 4778'- 4170'- UCTION d type of pump) 8' RHAC SM OIL-BBLS.	-5342' -5091' -4974' -4785' -4182' Plunger Pum	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4 Frac w/ 59,402# 20/4 Prac w/ 59,402# 20/4 WEI WATER-BBL. 18 WATER-BBL. OIL GR	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid 0 sand in 511 bbls fluid 0 sand in 511 bbls fluid L STATUS (Producing or shut-in) PRODUCING GAS-OIL RATIO 1574		
33.* DATE FIRST PRODUCTI 05/14/ DATE OF TEST 06-21-08	(LOD) (A. (B (D (GB	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785' 4) 4170'-4182' PRODUCTIO HOURS TESTED CASING PRESSUR	.4 .4 .4 .4 .4 .4 .1 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4	9" 9" 9" 9" 9" 9" 9" UFLOWING, gas lift 1/2" x 1-1/2 E SIZE PR TE ULATED JIR RATE	4/32 4/44 4/24 4/28 4/48 PROD , pumping—size as 2" x 16' x 2 CODN, FOR EST PERIOD ———>	5334'- 5080'- 4968'- 4778'- 4170'- UCTION d type of pump) 8' RHAC SM OIL-BBLS.	-5342' -5091' -4974' -4785' -4182' Plunger Pum	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4 Frac w/ 59,402# 20/4 Prac w/ 59,402# 20/4 NP WATER-BBL.	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid 0 sand in 511 bbls fluid 0 sand in 511 bbls fluid L STATUS (Producing or shut-in) PRODUCING GAS-OIL RATIO 1574		
33.* DATE FIRST PRODUCTI 05/14/ DATE OF TEST 06-21-03 FLOW, TUBING PRESS.	(LOD) (A. (B) (D) (GB)	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785' 4) 4170'-4182' PRODUCTIO HOURS TESTED CASING PRESSUR	.4 .4 .4 .4 .4 .4 .1 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4	9" 9" 9" 9" 9" 9" 9" Eliant	4/32 4/44 4/24 4/28 4/48 PROD , pumping—size as 2" x 16' x 2 CODN, FOR EST PERIOD ———>	5334'- 5080'- 4968'- 4778'- 4170'- UCTION d type of pump) 8' RHAC SM OIL-BBLS.	-5342' -5091' -4974' -4785' -4182' Plunger Pum	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4 Frac w/ 59,402# 20/4 WEI WATER-BBL. 18 WATER-BBL. OIL GE TEST WITNESSED B	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid 0 sand in 511 bbls fluid 0 sand in 511 bbls fluid L STATUS (Producing or shut-in) PRODUCING GAS-OIL RATIO 1574 AVITY-API (CORR.)		
33.* DATE FIRST PRODUCTI 05/14/ DATE OF TEST 06-21-06 FLOW. TUBING PRESS. 34. DISPOSITION OF GA 35. LIST OF ATTACHM 36. I hereby certify tha	(LOD) (A. (B) (D) (GB) ON 08 8	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785' 4) 4170'-4182' PRODUCTION HOURS TESTED CASING PRESSUR	.4 .4 .4 .4 .4 .4 .1 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4	9" 9" 9" 9" 9" 9" 9" UFlowing, gas lift /2" x 1-1/2 E SIZE PATE JUATED J	4/32 4/44 4/24 4/28 4/48 PROD pumping-size an 2" x 16' x ' COD'N. FOR SST PERIOD OIL-BBL. OF Fuel	5334'- 5080'- 4968'- 4778'- 4170'- UCTION ad type of pump) 18' RHAC SM OILBBLS. 47 GASMCF.	-5342' -5091' -4974' -4785' -4182' Plunger Pum GASMCF. 74	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4 Frac w/ 59,402# 20/4 WEI WATER-BBL. 18 WATER-BBL. OIL GE TEST WITNESSED B	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid 0 sand in 511 bbls fluid 0 sand in 511 bbls fluid L STATUS (Producing or shut-in) PRODUCING GAS-OIL RATIO 1574 AVITY-API (CORR.)		
33.* DATE FIRST PRODUCTI 05/14/ DATE OF TEST 06-21-03 FLOW. TUBING PRESS. 34. DISPOSITION OF GA 35. LIST OF ATTACHM	(LOD) (A. (B) (C) (GB) ON	C) 5334'-5342' 5) 5080'-5091' 2) 4968'-4974' 2) 4778'-4785' 4) 4170'-4182' PRODUCTION HOURS TESTED CASING PRESSUR	.4 .4 .4 .4 .4 .4 .1 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4 .4	9" 9" 9" 9" 9" 9" 9" UFlowing, gas lift /2" x 1-1/2 E SIZE PATE JUATED J	4/32 4/44 4/24 4/28 4/48 PROD pumping—size ai 2" x 16' x 2 COD'N. FOR EST PERIOD OIL-BBL.	5334'- 5080'- 4968'- 4778'- 4170'- UCTION ad type of pump) 18' RHAC SM OILBBLS. 47 GASMCF.	-5342' -5091' -4974' -4785' -4182' Plunger Pum GASMCF.	Frac w/ 84,098# 20/4 Frac w/ 24,764# 20/4 Frac w/ 24,664# 20/4 Frac w/ 59,402# 20/4 WEI WATER-BBL. 18 WATER-BBL. OIL GE TEST WITNESSED B	0 sand in 666 bbls fluid 0 sand in 354 bbls fluid 0 sand in 341 bbls fluid 0 sand in 511 bbls fluid 0 sand in 511 bbls fluid L STATUS (Producing or shut-in) PRODUCING GAS-OIL RATIO 1574 AVITY-API (CORR.)		

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

ì.

FORMATION	TOP BOTTOM DESCRIPTION, CONTENTS, ETC.		DESCRIPTION, CONTENTS, ETC.		ТО	P
				NAME	MEAS. DEPTH	TRUE VERT. DEPTH
			Well Name State 5-16-9-16	Garden Gulch Mkr Garden Gulch 1	3674' 3890'	
				Garden Gulch 2 Point 3 Mkr	3998' 4248'	
				X Mkr	4515'	
				Y-Mkr Douglas Creek Mkr BiCarbonate Mkr B Limestone Mkr	4549' 4663' 4897' 5004'	
				Castle Peak Basal Carbonate Total Depth (LOGGERS	5552' NP 5835'	
	-					

4/94

STATE OF UTAH

DIVISION OF OIL, GAS, AND MININ	5. LEASE DESIGNATION AND SERIAL NO.				
SUNDRY NOTICES AND REPORTS	ON WELLS	ML-16532 6. IF INDIAN, ALLOTTEE OR TRIBAL NAME			
Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plug Use "APPLICATION FOR PERMIT TO DRILL OR DEEPEN form I	N/A				
OIL GAS WELL X OTHER	7. UNIT AGREEMENT NAME NA				
2. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY	8. WELL NAME and NUMBER STATE 5-16-9-16				
3. ADDRESS AND TELEPHONE NUMBER Rt. 3 Box 3630, Myton Utah 84052 435-646-3721	-	9 API NUMBER 43-013-33849			
4. LOCATION OF WELL		10 FIELD AND POOL, OR WILDO	CAT		
Footages 2043 FNL 758 FWL		MONUMEN	T BUTTE		
QQ, SEC, T, R, M: SW/NW Section 16, T9S R16E	; 	COUNTY DUCHESNE STATE UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NO	OTICE, REPORT OR OTHE	R DATA			
NOTICE OF INTENT:		NT REPORT OF:			
(Submit in Duplicate) ABANDON NEW CONSTRUCTION	ABANDON*	Original Form Only)	NEW CONSTRUCTION		
REPAIR CASING PULL OR ALTER CASING	REPAIR CASING		PULL OR ALTER CASING		
CHANGE OF PLANS RECOMPLETE	X CHANGE OF PLA	ans [RECOMPLETE		
CONVERT TO INJECTION REPERFORATE	CONVERT TO IN	JECTION	REPERFORATE		
FRACTURE TREAT OR ACIDIZE VENT OR FLARE	FRACTURE TREAT	OR ACIDIZE	VENT OR FLARE		
MULTIPLE COMPLETION WATER SHUT OFF	OTHER				
OTHER	DATE WORK COMPLI	ETED			
	1	le Completion and Recompletions	to different		
	i	MPLETION OR RECOMPLETION	ON REPORT AND		
	LOG form.	y a cement verification report.			
 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinen and measured and true vertical depth for all markers and zones pertinent to this work. 			give subsurface locations		
As per a conversation with Helen Sadik MacDonal	ld approval was gi	ven to go ahead and	l set the planned 290' of		
surface casing that is normally set on wells drilled					
Subsequently 324' of surface casing was set on the					
1					
13.					
NAME & SIGNATURE Mandle Crozier TITLE	Regulatory Specialis	st DATE_	7/21/2008		
(This space for State use only)					

* See Instructions On Reverse Side





September 2, 2011

Mr. Mark Reinbold State of Utah Division of Oil, Gas and Mining 1594 W North Temple Salt Lake City, Utah 84114-5801

RE:

Permit Application for Water Injection Well

State #5-16-9-16

Monument Butte Field, Lease #ML-16532 Section 16-Township 9S-Range 16E

Duchesne County, Utah

Dear Mr. Reinbold:

Newfield Production Company herein requests approval to convert the State #5-16-9-16 from a producing oil well to a water injection well in the Monument Butte (Green River) Field.

I hope you find this application complete; however, if you have any questions or require additional information, please contact me at (303) 893-0102.

Sincerely,

Eric Sundberg C Regulatory Lead

RECEIVED
SEP 07 2011
DIV. OF OIL, GAS & MINING

NEWFIELD PRODUCTION COMPANY APPLICATION FOR APPROVAL OF CLASS II INJECTION WELL

STATE #5-16-9-16

MONUMENT BUTTE FIELD (GREEN RIVER) FIELD

LEASE #ML-16532

SEPTEMBER 2, 2011

RECEIVED
SEP 07 2011

DIV. OF OIL, GAS & MINING

TABLE OF CONTENTS

LETTER OF INTENT COVER PAGE TABLE OF CONTENTS UIC FORM 1 – APPLICATION FOR INJECTION WELL WELLBORE DIAGRAM OF PROPOSED INJECTION WORK PROCEDURE FOR INJECTION CONVERSION COMPLETED RULE R615-5-1 QUESTIONNAIRE COMPLETED RULE R615-5-2 QUESTIONNAIRE ONE-HALF MILE RADIUS MAP ATTACHMENT A **ATTACHMENT A-1** WELL LOCATION PLAT LIST OF SURFACE OWNERS WITHIN ONE-HALF MILE RADIUS ATTACHMENT B CERTIFICATION FOR SURFACE OWNER NOTIFICATION ATTACHMENT C WELLBORE DIAGRAM - STATE #5-16-9-16 ATTACHMENT E WELLBORE DIAGRAM - STATE #3-16-9-16 **ATTACHMENT E-1** WELLBORE DIAGRAM - STATE #4-16-9-16 **ATTACHMENT E-2 ATTACHMENT E-3** WELLBORE DIAGRAM - STATE #6-16-9-16 WELLBORE DIAGRAM - STATE #11-16-9-16 ATTACHMENT E-4 WELLBORE DIAGRAM - STATE #12-16-9-16 **ATTACHMENT E-5** WELLBORE DIAGRAM - CASTLE PEAK STATE #32-16-9-16 ATTACHMENT E-6 WELLBORE DIAGRAM - FEDERAL #1-17-9-16 ATTACHMENT E-7 WELLBORE DIAGRAM – FEDERAL #8-17-9-16 ATTACHMENT E-8 WELLBORE DIAGRAM - FEDERAL #9-17-9-16 **ATTACHMENT E-9** ATTACHMENT F WATER ANALYSIS FRACTURE GRADIENT CALCULATIONS ATTACHMENT G FRACTURE REPORTS DATED - 5/6/08 - 5/14/08 ATTACHMENT G-1 WORK PROCEDURE FOR PROPOSED PLUG AND ABANDON ATTACHMENT H WELLBORE DIAGRAM OF PROPOSED PLUGGED WELL **ATTACHMENT H-1**

STATE OF UTAH DIVISION OF OIL, GAS AND MINING

ADDRESS

Comments:

APPLICATION FOR INJECTION WELL - UIC FORM 1

1001 17th Street, Suite 2000

Denver, Colorado 80202

OPERATOR Newfield Production Company

Well Name and number: State #5-16-9-	-16
Field or Unit name: Monument Butte (Green Riv	ver) Lease No. ML-16532
Well Location: QQ SWNW section	16 township 9S range 16E county Duchesne
Is this application for expansion of an existing pro	oject? Yes [X] No []
Dis	nhanced Recovery? Yes [X] No [] sposal? Yes [] No [X] orage? Yes [] No [X]
Is this application for a new well to be drilled? If this application is for an existing well, has a casing test been performed on the well?. Date of test: API number: 43-013-33849	Yes[] No[X]
	3997 to 5799 00 bpd pressure 1902 psig and/or [] fresh water within 1/2
	dditional information as required by R615-5-2 should company this form.
List of Attachments: Attachments ".	'A" through "H-1"
I certify that this report is true and complete to the	e best of my knowledge.
Name: Eric Sundberg Title Regulatory Lead Phone No. (303) 893-0102	Signature 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
(State use only) Application approved by Approval Date	Title

State 5-16-9-16

Spud Date: 04-07-08 Put on Production: 05-14-08 GL: 5922' KB: 5934'

Propose Injection Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-7/8" GRADE: J-55 WEIGHT: 24#

LENGTH: 7 jts. (312.48') DEPTH LANDED: 324'

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2" GRADE: J-55 WEIGHT: 15,5#


LENGTH: 139jts. (5807.48') HOLE SIZE: 7-7/8" DEPTH LANDED: 5825*

CEMENT DATA: 300 sk Prem. Lite II mixed & 400 sxs 50/50 POZ.

CEMENT TOP AT: 70

TUBING

SIZE/GRADE/WT .: 2-7/8" / J-55 / 6.5# NO. OF JOINTS: 168 jts (5268.1') TUBING ANCHOR: 5268.11 NO. OF JOINTS: 2 jts (62.6') SEATING NIPPLE: 2-7/8" (1.10') SN LANDED AT: 5345.51' KB NO. OF JOINTS: 5 jts (155.2') TOTAL STRING LENGTH: EOT @ 5496'



FRAC JOB

12-18-09

05-07-08 5698-5706 Frac CP3 sands as follows:

Frac with 34586 #'s of 20/40 sand in 434 bbls of Lightning 17 fluid. Treat at an ave pressure of 1941 psi @ 23,2 BPM.

ISIP 2046 psi.

Frac LODC sands as follows: 05-07-08 5334-5342'

Frac with 24721 #'s of 20/40 sand in 348 bbls of Lightning 17 fluid, Treat at an ave pressure of 2425 psi @ 23.2 BPM.

ISIP 2165 psi.

05-07-08 5080-5091' Frac A.5 sands as follows:

Frac with 84098 #'s of 20/40 sand in 666 bbls of Lightning 17 fluid. Treat at an ave pressure of 2065 psi @ 23.2 BPM. ISIP

2582 psi

05-07-08 4968-4974' Frac B2 sand as follows:

Frac with 24764 #'s of 20/40 sand in 354 bbls of Lightning 17 fluid. Treat at an ave pressure of 3365 psi @ 23,3 BPM.

ISIP 2959 psi

Frac D2 sands as follows: 05-07-08 4778-4785

Frac with 24664 #'s of 20/40 sand in 341 bbls Lightning of 17 fluid, Treat at an ave pressure of 1975 psi @ 23.3 BPM.

ISIP 2279 psi.

Frac GB4 sands as follows: 05-07-08 4170-41823

Frac with 59402 #'s of 20/40 sand in 511 bbls of Lightning 17 fluid. Treat at an ave pressure of 1805 psi @ 23.3 BPM. ISIP 1929 psi

Pump Change. Update rod and tubing



State 5-16-9-16

2043' FNL & 758' FWL SWNW Section 16-T9S-R16E Duchesne Co, Utah API #43-013-33849; Lease #Utah State ML-16532 PERFORATION RECORD

4170-4182' 4 JSPF 48 holes 4778-4785' 4 JSPF 28 holes 4968-4974' 4 JSPF 24 holes 5080-5091' 4 JSPF 44 holes 5334-5342' 4 JSPF 32 holes 5698-5706' 4 JSPF 32 holes

WORK PROCEDURE FOR INJECTION CONVERSION

- 1. Rig up hot oil truck to casing. Pump water. Unseat pump. Flush rods. Trip out of hole with rods and pump.
- 2. Trip out of hole with tubing, breaking and doping every connection. Trip in hole with packer and tubing. Rig up water truck to casing. Pump packer fluid. Set packer.
- 3. Test casing and packer.
- 4. Rig down and move out.

REQUIREMENTS FOR INJECTION OF FLUIDS INTO RESERVOIRS RULE R615-5-1

- 1. Operations to increase ultimate recovery, such as cycling of gas, the maintenance of pressure, the introduction of gas, water or other substances into a reservoir for the purpose of secondary or other enhanced recovery or for storage and the injection of water into any formation for the purpose of water disposal shall be permitted only by order of the Board after notice and hearing.
- 2. A request for agency action for authority for the injection of gas, liquified petroleum gas, air, water or any other medium into any formation for any reason, including but not necessarily limited to the establishment of or the expansion of waterflood projects, enhanced recovery projects, and pressure maintenance projects shall contain:
 - 2.1 The name and address of the operator of the project.

Newfield Production Company 1001 17th Street, Suite 2000 Denyer, Colorado 80202

2.2 A plat showing the area involved and identifying all wells, including all proposed injection wells, in the project area and within one-half mile of the project area.

See Attachment A.

2.3 A full description of the particular operation for approval is requested.

Approval is requested to convert the State #5-16-9-16 from a producing oil well to a water injection well in Monument Butte (Green River) Field.

2.4 A description of the pools from which the identified wells are producing or have produced.

The proposed injection well will inject into the Green River Formation.

2.5 The names, description and depth of the pool or pools to be affected.

The injection zone is in the Green River Formation. For the State #5-16-9-16 well, the proposed injection zone is from Garden Gulch to Castle Peak (3997' - 5799). The confining strata directly above and below the injection zones are the Garden Gulch and the top of the Wasatch Formation or TD, which ever is shallower. The Garden Gulch Marker top is at 3674' and the TD is at 5825'.

2.6 A copy of a log of a representative well completed in the pool.

The referenced log for the State #5-16-9-16 is on file with the Utah Division of Oil, Gas and Mining.

2.7 A statement as to the type of fluid to be used for injection, its source and the estimated amounts to be injected daily.

The primary type and source of fluid to be used for injection will be culinary water commingled with produced water. The average estimated injection of fluids will be at a rate of 300 BPD, and the estimated maximum injection will be at a rate of 500 BPD.

2.8 A list of all operators and surface owners within one-half mile radius of the proposed project.

See Attachment B.

2.9 An affidavit certifying that said operators or owners and surface owners within a one-half mile radius have been provided a copy of the petition for injection.

See Attachment C.

2.10 Any additional information the Board may determine is necessary to adequately review the petition.

Newfield Production Company will supply any additional information requested by the Utah Division of Oil, Gas and Mining.

4.0 Establish recovery projects may be expanded and additional wells placed on injection only upon authority from the Board after notice and hearing or by administrative approval.

This proposed injection well is on a State lease (Lease #ML-16532) in the Monument Butte Federal (Green River) Field, and this request is for administrative approval.

REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING WATER DISPOSAL, STORAGE AND ENHANCED RECOVERY WELLS SECTION V – RULE R615-5-2

- 1. Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.
- 2. The application for an injection well shall include a properly completed Form DOGM-UIC-1 and the following:
 - 2.1 A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well.

See Attachments A and B.

2.2 Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity.

All logs are on file with the Utah Division of Oil, Gas and Mining.

2.3 A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented.

A copy of the cement bond log is on file with the Utah Division of Oil, Gas and Mining.

2.4 Copies of logs already on file with the Division should be referenced, but need not be refiled.

All copies of logs are on file with the Utah Division of Oil, Gas and Mining.

2.5 A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well.

The casing program is 8-5/8", 24# surface casing run to 324' KB, and 5-1/2", 15.5# casing run from surface to 5825' KB. A casing integrity test will be conducted at the time of conversion. See Attachment E.

2.6 A statement as to the type of fluid to be used for injection, its source and estimated amounts to be injected daily.

The primary type and source of fluid to be used for injection will be culinary water commingled with produced water. The estimated average rate of injection will be 300 BPD, and the estimated maximum rate of injection will be 500 BPD.

2.7 Standard laboratory analysis of the fluid to be injected, the fluid in the formation into which the fluid is being injected, and the compatibility of the fluids.

See Attachment F.

The proposed average and maximum injection pressures.

The proposed average injection pressure will be approximately 1100 psig and the maximum injection pressure will not exceed 1902 psig.

2.8 Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining interval that could enable the injected fluid or formation fluid to enter the fresh water strata.

The minimum fracture gradient for the State #5-16-9-16, for existing perforations (4170' - 5706') calculates at 0.90 psig/ft. The maximum injection pressures will be limited so as not to exceed this gradient. A step rate test will be performed periodically to ensure we are below parting pressure. The proposed maximum injection pressure is 1902 psig. We may add additional perforations between 3674' and 5825'. See Attachments G and G-1.

2.9 Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent.

In the State #5-16-9-16, the proposed injection zone (3997' - 5799') is in the Garden Gulch to the Castle Peak of the Green River Formation. The reservoir is a very fine-grained sandstone with minor imbedded shale streaks. The estimated porosity is 13%. The members are composed of porous and permeable lenticular calcareous sandstone and low porosity carbonates and calcareous shale. The porous and lenticular sandstone varies in thickness from 0-31' and is confined to the Monument Butte Federal Field. Outside the Monument Butte Federal Field, the sandstone is composed of tight, very fine, silty, calcareous sandstone, less than 3' thick. The stratum confining the injection zone is composed of tight, moderately calcareous, sandy lacustrine shale. All of the confining strata are impermeable, and will effectively seal off the oil, gas, and water of the injection zone from any strata directly above or below it.

2.10 A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter the improper intervals.

See Attachments E through E-9.

Additionally, the injection system will be equipped with high and low pressure shut down devices that will automatically shut in injection waters if a system blockage or leakage occurs. One way check valves will also ensure proper flow management. Relief valves will also be utilized for high-pressure relief.


2.11 An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well.


See Attachment C.

2.12 Any other information that the Board or Division may determine is necessary to adequately review the application.


Newfield Production Company will supply any requested information to the Board or Division.

ATTACHMENT A





State 5-16 Section 16, T9S-R16E






EXHIBIT B

#	Legal Description	Lessor & Expiration	Lessee & Operating Rights	Surface Owner
1	T9S-R16E SLM	State of Utah	QEP Energy Company	State of Utah
	Section 16: ALL	ML 16532	El Paso E&P Company, LP	
		НВР	American Petroleum Corp	
			Brave River Production	
			Trans Republic Resources Inc	
			El Paso Production Oil & Gas Company	
			Newfield RMI LLC	
2	T9S-R16E SLM	USA	Newfield Production Company	USA
	Section 8: SWNE, SE	UTU-64379	Newfield RMI LLC	
	Section 9: SWSW	НВР	Yates Petroleum Corporation	
	Section 17: NE		·	
	Section 18: E2SW, SE, Lots 3,4			
	Section 19: NE, E2NW, Lots 1,2			
	Section 21: N2			
	Section 22: W2NE, SENE, NW			
3	T9S-R16E SLM	USA	Newfield Production Company	USA
	Section 17: S2	UTU-52018	Newfield RMI LLC	
	Section 20: N2	НВР		
4	T9S-R16E SLM	USA	Newfield Production Company	USA
	Section 9: E2SW, SWSE	UTU-79831 HBP	Newfield RMI LLC	

ATTACHMENT C

CERTIFICATION FOR SURFACE OWNER NOTIFICATION

RE:	Application for Approval of Class II Injection Well State #5-16-9-16
I hereby one-hal	y certify that a copy of the injection application has been provided to all surface owners within a f mile radius of the proposed injection well.
Signed:	Newfield Production Company Eric Sundberg Regulatory Lead
	to and subscribed before me this 15t day of September, 2011. Public in and for the State of Colorado: (2011)
	My Commission Expires 02/10/2013 EL. TWILL TARY TARY

State 5-16-9-16

Spud Date: 04-07-08 Put on Production: 05-14-08

State 5-16-9-16 2043' FNL & 758' FWL SWNW Section 16-T9S-R16E Duchesne Co, Utah API #43-013-33849; Lease #Utah State ML-16532

Wellbore Diagram

GL: 5922' KB: 5934' FRAC JOB SURFACE CASING CSG SIZE: 8-7/8" 05-07-08 5698-5706 Frac CP3 sands as follows: Frac with 34586 #'s of 20/40 sand in 434 bbls of Lightning 17 fluid. Treat at an GRADE: J-55 Cement Top@ 70 ave pressure of 1941 psi @ 23.2 BPM. WEIGHT: 24# ISIP 2046 psi LENGTH: 7 jts. (312,48') Casing Shoe @ 324' 05-07-08 5334-5342' Frac LODC sands as follows: DEPTH LANDED: 324 Frac with 24721 #'s of 20/40 sand in 348 bbls of Lightning 17 fluid, Treat at an ave pressure of 2425 psi @ 23.2 BPM. HOLE SIZE: 12-1/4" CEMENT DATA: 160 sxs Class "G" cmt ISIP 2165 psi. 05-07-08 5080-5091' Frac A.5 sands as follows: Frac with 84098 #'s of 20/40 sand in 666 bbls of Lightning 17 fluid. Treat at an ave pressure of 2065 psi @ 23.2 BPM, ISIP 2582 psi. 05-07-08 4968-4974' Frac B2 sand as follows: PRODUCTION CASING Frac with 24764 #'s of 20/40 sand in 354 bbls of Lightning 17 fluid, Treat at an CSG SIZE: 5-1/2" ave pressure of 3365 psi @ 23.3 BPM. GRADE: I-55 ISIP 2959 psi WEIGHT: 15.5# 05-07-08 4778-4785 Frac D2 sands as follows: Frac with 24664 #'s of 20/40 sand in 341 LENGTH: 139jts. (5807.48') bbls Lightning of 17 fluid, Treat at an ave pressure of 1975 psi @ 23,3 BPM. HOLE SIZE: 7-7/8" ISIP 2279 psi. DEPTH LANDED: 5825' 05-07-08 4170-4182' Frac GB4 sands as follows: CEMENT DATA: 300 sk Prem. Lite II mixed & 400 sxs 50/50 POZ. Frac with 59402 #'s of 20/40 sand in 511 CEMENT TOP AT: 70' bbls of Lightning 17 fluid. Treat at an ave pressure of 1805 psi @ 23.3 BPM. ISIP 1929 psi. 12-18-09 Pump Change. Update rod and tubing **TUBING** SIZE/GRADE/WT .: 2-7/8" / J-55 / 6 5# NO. OF JOINTS: 168 its (5268.1') TUBING ANCHOR: 5268.11 NO. OF JOINTS: 2 jts (62,6') SEATING NIPPLE: 2-7/8" (1.10') SN LANDED AT: 5345,51' KB NO. OF JOINTS: 5 jts (155,2') TOTAL STRING LENGTH: EOT @ 5496' SUCKER RODS 4170-4182 POLISHED ROD: 1-1/2" x 26" SUCKER RODS: 2- 4' x ¼" pony rods, 94- ¾" guided rods, 93- ¾" guided rods, 20- ¾" guided rods, 6- 1 ½" weight bars 4778-4785' PUMP SIZE: 2-1/2" x 1-1/2" x 14' x 18' RHAC STROKE LENGTH: 102' 4968-4974 PUMP SPEED, SPM: 5 5080-5091 PERFORATION RECORD 4170-4182' 4 JSPF 48 holes 4778-4785 4 JSPF 28 holes Anchor @ 5268' 4968-4974 4 JSPF 24 holes 5334-5342 5080-5091' 4 JSPF 44 holes SN @ 5346' 5334-5342' 4 JSPF 32 holes EOT @ 5496' 5698-5706' 4 JSPF 32 holes 5698-5706 **NEWFIELD** PBTD @ 5799 TD@ 5825'

State 3-16-9-16

Spud Date: 02-28-08 Put on Production: 05-13-08 GL: 5841' KB: 5853'

API #43-013-33847; Lease #Utah State ML-16532

Wellbore Diagram

FRAC JOB SURFACE CASING Frac CP1 sds as follows: 04-22-08 5571-5592' CSG SIZE: 8-5/8" Frac w/144.428# 20/40 sand in 1022 bbls GRADE: J-55 of Lightning 17 fluid. Treated w/ ave Cement Top @ 278' pressure of 1764 psi w/ ave rate of 25,2 WEIGHT: 24# BPM, ISIP 2006 psi, Actual Flush: 5065 LENGTH: 10 its gals. HOLE SIZE: 12-1/4" 04-22-08 5203-5211 Frac LODC sds as follows: Frac w/24,817# 20/40 sand in 356 bbls of CEMENT DATA: To surface with 209 sx Class "G" cmt Lightning 17 fluid, Treated w/ ave pressure of 2477 psi w/ ave rate of 23.3 BPM. ISIP 2543, Actual Flush: 4696 gals 04-22-08 5094-5109* Frac A1 sds as follows: Frac w/38,375# 20/40 sand in 420 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2034 psi w/ ave rate of 23,3 BPM. ISIP 2543 psi. Actual Flush: 4586 PRODUCTION CASING gals. CSG SIZE: 5-1/2" 04-22-08 4944-4954' Frac B2 sds as follows: GRADE: J-55 Frac w/30,349# 20/40 sand in 383 bbls of Lightning 17 fluid, Treated w/ ave pressure of 1804 psi w/ ave rate of 23,3 WEIGHT: 15.5# LENGTH: 147 jts BPM, ISIP 1842 psi Actual Flush: 4439 gals. HOLE SIZE: 7-7/8" 04-22-08 4824-4839 Frac C sds as follows: TOTAL DEPTH: 5826' Frac w/48,027# 20/40 sand in 446 bbls of CEMENT DATA: 300 sk Prem, Lite II mixed & 400 sxs 50/50 POZ, Lightning 17 fluid, Treated w/ ave pressure of 2057 psi w/ ave rate of 23,3 CEMENT TOP AT: 278' BPM, ISIP 2063 psi, Actual Flush: 4318 04-22-08 4710-4724 Frac D2 sds as follows: Frac w/37,944# 20/40 sand in 423 bbls of Lightning 17 fluid. Treated w/ ave TUBING pressure of 2539 psi w/ ave rate of 23.4 4710-47241 BPM. ISIP 2646 psi. Actual Flush: 4624 SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5# gals. NO. OF JOINTS: 176 jts (5533.42') 4824-4839 TUBING ANCHOR: 5545.423 NO. OF JOINTS: 2 jts (62.86') 4944-4954 SEATING NIPPLE: 2-7/8" (1,10') SN LANDED AT: 5611,08' KB NO. OF JOINTS: 2 its (62.80') 5094-5109' TOTAL STRING LENGTH: EOT @ 5508,31' w/12' KB SUCKER RODS 5203-5211* POLISHED ROD: 1-1/2" x 26' polished rod SUCKER RODS:1-2', 3-4', 1-6' x 3" pony sub, 99-3" guided rods,78-3/4" plain rods, 40- 3/" guided rods, 6- 1 1/2" weight rods PUMP SIZE: 2-1/2" x 1-1/2" x 16' x 18' RHAC pump STROKE LENGTH: 102" EOT @ 5508' PUMP SPEED, SPM: 5 Anchor @5545' PERFORATION RECORD 5571-5592' 4710-4724' 4 JSPF 56 holes 5606-5620' SN @5611' 4824-48391 4 ISPE 60 holes 4944-4954' 4 JSPF 40 holes 5094-5109 4 JSPF 60 holes 5203-5211' 4 JSPF 32 holes 5571-5592' 4 JSPF 84 holes 5606-5620' 4 JSPF 56 holes PBTD @ 5812' NEWFIELD TD @ 5855 State 3-16-9-16 660' FNL & 1990' FWL NE/NW Section 16-T9S-R16E Duchesne Co, Utah



State 4-16-9-16

Spud Date: 4/1/08 Put on Production: 6/3/08 GL: 5881' KB: 5893'

Wellbore Diagram

Cement Top @48

SURFACE CASING_

CSG SIZE 8-5/8"

GRADE: J-55

Ce
WEIGHT: 24#

LENGTH: 7jts (300 96')

DEPTH LANDED: 312.81' KB

HOLE SIZE: 12-1/4"

CEMENT DATA:1- 160, sxs Class "G" cmt, est 6 bbls cmt to surf.

PRODUCTION CASING

GRADE: J-55
WEIGHT: 15.5#
LENGTH: 158jts 5819 28
HOLE SIZE: 7-7/8"
DEPTH LANDED: 5832.53"

CSG SIZE 5-1/2"

CEMENT DATA: 300 sx Premlite II and 400 sx 50/50 Poz

CEMENT TOP AT: 48'

TUBING

SIZE/GRADE/WT... 2 7/8" /J-55 /6 5#
NO OF JOINTS 175 jis 5182.02
TUBING ANCHOR: 5194.02'
NO OF JOINTS 1ji (31.52')
SEATING NIPPLE: 2 7/8"
SN LANDED AT 5228.29'
NO OF JOINTS 2jis 62.47
TOTAL STRING LENGTH: EOT@ 5292.31'

SUCKER RODS

POLISHED ROD 1 1/2" x 26' polished rod

SUCKER RODS: 1-2', 8' x $\frac{1}{2}$ " pony subs, 99-3/4" guided rods, 83-3/4" plain rods, 20-3/4" guided rods, 6-1 $\frac{1}{2}$ " weight bars

PUMP SIZE 2 1/2" x 1 1/2" x 12' x 15 1/2' RHAC rod pump CDI

STROKE LENGTH: 58
PUMP SPEED, SPM: 5

NEWFIELD

State 4-16-9-16

660' FNL & 815' FWL

NW/NW Section 16-T9S-R16E

Duchesne Co, Utah

API #43-013-33848; Lease #Utah State ML-16532

FRAC JOB

4778-4791'

4842-4856

4916-4925

5108-5114

5126-5132

Anchor @ 5194

5198-5203"

5209-52281

EOT @5292'

PBTD @ 5788

TD @ 5853'

SN @ 5228

05-28-08 5209-5228' Frac LODC sds as follows: 200,061# 20/40 sand in 1373 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1997 psi w/ ave rate of 27 3 BPM ISIP 2322 psi Actual Flush 4683 gals

05-28-08 4916-4925' Frac B1 sds as follows:

54,952# 20/40 sand in 495 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1767 psi w/ ave rate of 23 4 BPM. ISIP 1705 psi. Actual Flush: 4406 gals.

05-28-08 4842-4856' Frac C sds as follows:

115,003# 20/40 sand in 846 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1920 psi w/ ave rate of 23.5 BPM. ISIP 1926 psi. Actual Flush: 4330 gals.

05-28-08 4778-4791' Frac D3 sds as follows:

15,003# 20/40 sand in 846 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1920 psi w/ ave rate of 23.5 BPM. ISIP 1926 psi. Actual Flush: 4679 gals.

3/28/09 Pump Change. Updated r & t details.
6/5/09 Pump Change Updated rod & tubing

details

PERFORATION RECORD

4778-4791' 4 JSPF 52 holes 4842-4856' 4 JSPF 56 holes 4916-4925 4 JSPF 36 holes 5108-51141 24 holes 4 JSPF 5126-5132 4 JSPF 24 holes 5198-52031 4 JSPF 20 holes 5209-52281 4 JSPF 76 holes



State 6-16-9-16

Spud Date: 03-03-08 Put on Production: 05-12-08 GL: 5876' KB: 5888'

Duchesne Co, Utah API #43-013-33850; Lease # Utah State ML-16532


Wellbore Diagram

FRAC JOB SURFACE CASING CSG SIZE: 8-5/8" Cement Top@ 38' 4-29-08 5548-5574' Frac CP1 sands as follows: Frac with 125681 #'s of 20/40 sand in GRADE: J-55 903 bbls of Lightning 17 fluid. Treat at an ave pressure of 1713 psi @ 23 9 BPM WEIGHT: 24# ISIP 2198 psi LENGTH: 10 jts (321 48') Casing Shoe @ 431' 4-29-08 5086-5094' Frac A1 sands as follows: DEPTH LANDED: 431' Frac with 60763 #'s of 20/40 sand in 507 bbls of Lightning 17 fluid. Treat at an HOLE SIZE: 12-1/4" ave pressure of 2229 psi @ 23.2 BPM CEMENT DATA: 205 sxs Class "G" cmt ISIP 2405psi 4-29-08 4692-4748' Frac D3 & D2 sands as follows: Frac with 133141 #'s of 20/40 sand in 962 bbls of Lightning 17 fluid, Treat at an ave pressure of 2005 psi @ 24 6 BPM ISIP 2005 psi. 4-29-08 4093-4171' Frac GB4 & GB6 sand as follows: PRODUCTION CASING Frac with 43849 #'s 20/40 sand in 426 bbls of Lightning 17 fluid, Treat at an ave pressure of 1908 psi @ 23.2 BPM. CSG SIZE 5-1/2" GRADE: I-55 ISIP 1900 psi. WEIGHT: 15.5# LENGTH: 137 jts. (5809.35') pump change. Updated tubing and rod 7/14/08 HOLE SIZE: 7-7/8" detail DEPTH LANDED: 5822,6' Pump Change, Updated rod &tubing 9/9/08 details CEMENT DATA: 300 sk Prem, Lite II mixed & 400 sxs 50/50 POZ 3/23/10 Pump change. Updated rod and tubing CEMENT TOP AT: 38' **TUBING** SIZE/GRADE/WT .: 2-7/8" / J-55 NO OF JOINTS: 175 its (5514.2') TUBING ANCHOR: 5526.2' NO OF JOINTS: 1 jts (31.6') SEATING NIPPLE: 2-7/8" (1_10') SN LANDED AT: 5560,5' KB NO OF JOINTS: 2 jts (63 0') TOTAL STRING LENGTH: EOT @ 5625' w/12' KB 4093-4099 4125-41301 SUCKER RODS 4166-4171' POLISHED ROD: 1-1/2" x 26 SUCKER RODS: 1-2' x ½" pony rod, 3-12' x ½" pony rods, 1-8' x ½" pony rods, 98-½" guided rods (4per), 77-½" sucker rods, 40-½" guided rods (4per), 77-½" sucker rods, 40-½" guided rods (4per), 4692-47081 6- 1 1/2" weight bars 4732-4748 PUMP SIZE 2-1/2" x 1-1/2" x 14' x 16' RHAC pump STROKE LENGTH: 86' 5086-5094 PUMP SPEED, SPM: 4 PERFORATION RECORD 4093-4099' 4 JSPF 24 holes 4125-4130' 4 JSPF Anchor @ 5526' 20 holes 4166-4171' 4 JSPF 20 holes 5548-5574 SN @ 5561* 4692-4708' 4 JSPF 64holes 4732-4748' 4 JSPF 64 holes EOT @ 5625' 5086-5094 4 JSPF 32 holes 5548-5574' 4 JSPF 104 holes PBTD @ 5801' NEWFIELD TD @ 5820' 1 State 6-16-9-16 1849' FNL & 1974' FEL SENW Section 16-T9S-R16E

State 11-16-9-16

Spud Date: 07-16-08 Put on Production: 08-27-08 GL: 5907' KB: 5919'

Wellbore Diagram



State 12-16-9-16

Spud Date: 04-17-08 Put on Production: 06-10-08 GL: 5950' KB: 5962'

Wellbore Diagram

Cement Top@ 180'

Casing Shoe @ 323'

SURFACE CASING

CSG SIZE 8-5/8' GRADE J-55 WEIGHT 24# LENGTH 7jts (313 7') DEPTH LANDED: 3233 HOLE SIZE 12-1/4" CEMENT DATA To surface with 160 sx Class 'G' cmt

PRODUCTION CASING

CSG SIZE: 5-1/2" GRADE: J-55 WEIGHT: 15,5# LENGTH: 141jts HOLE SIZE 7-7/8

DEPTH LANDED 5787 23' CEMENT DATA: 300 sx Premlite II and 400 sx 50/50 Poz

CEMENT TOP AT: 180'

TUBING

SIZE/GRADE/WT 2-7/8" / J-55 / 6.5#

NO. OF JOINTS 180its

TUBING ANCHOR: 2 80 @5543 59'kb

NO OF JOINTS ljt SEATING NIPPLE: 1,10'

SN LANDED AT. 5578.11'

NO OF JOINTS: 2jts (61.90')

TOTAL STRING LENGTH: EOT @ 5640.46'

SUCKER RODS


POLISHED ROD 1-1/2" x 26

SUCKER RODS 1- 2' x ¼" pony sub, 100- ¼" guided rods, 97- ¼" plain rods, 20- ½" guided rods, 6- 1 ½" weight rods

PUMP SIZE 1-1/2" x 2-1/2" x 16' x 18' RHAC pump rod pump

STROKE LENGTH 86

PUMP SPEED, SPM 5



EOT @ 5640'

PBTD @ 5766 TD @ 5790'

NEWFIELD

State 12-16-9-16

2034' FSL & 504' FWL NW/SW Section 16-T9S-R16E Duchesne Co, Utah API #43-013-33852; Lease #Utah State ML-16532

FRAC JOB

06-02-08 5544-5574 Frac CP1 sds as follows: 129,858# 20/40 sand in 990 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1557 psi w/ ave rate of 25.7 BPM. ISIP 1756 psi. Actual Flush: 4956 gals

06-02-08 5194-5202' Frac LODC sds as follows 40,109# 20/40 sand in 426 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2182 psi w/ ave rate of 26 5 BPM ISIP 2297 psi. Actual Flush 4687 gals

06-02-08 5046-5067 Frac A1 sds as follows:

140,344 20/40 sand in 1049 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1990 psi w/ ave rate of 28 3 BPM. ISIP 2225 psi. Actual Flush: 4540 gals.

06-02-08 4902-4910' Frac B2 sds as follows: 48,476# 20/40 sand in 464 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1990 psi w/ ave rate of 26.2 BPM. ISIP 2071 psi. Actual Flush: 4456 gals.

06-02-08 4698-4706 Frac D2 sds as follows: 55,518# 20/40 sand in 489 bbls of Lightning 17 fluid Treated w/ ave pressure of 2128 psi w/ ave rate of 26.2 BPM 1SIP 2145 psi. Actual Flush: 4183 gals

06-02-08 4116-4124' Frac GB4 sds as follows. 22,357# 20/40 sand in 326 bbls of Lightning 17 fluid. Treated w/ ave pressure of 2230 psi w/ ave rate of 24.0 BPM ISIP 1880 psi. Actual Flush: 3675 gals.

06-02-08 4008-4015' Frac GB2 sds as follows: 17,193# 20/40 sand in 264 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1778 psi w/ ave rate of 24.3 BPM. ISIP 1632 psi. Actual Flush: 3931 gals

PERFORATION RECORD

	-	
4008-4015	4 JSPF	28 holes
4116-4124'	4 JSPF	32 holes
4698-4706'	4 JSPF	32 holes
4902-4910'	4 JSPF	32 holes
5046-5067'	4 JSPF	84 holes
5194-5202'	4 JSPF	32 holes
5544-5574'	4 JSPF	120 holes

CP State 32-16

Spud Date: 3-25-82 Put on Production: 8-26-82

CP State 32-16
2009' FNL & 1838' FEL
SW/NE Section 16-T9S-R16E
Duchesne County, Utah
API #43-013-30650; Lease #ML-16532

Wellbore Diagram

FRAC JOB SURFACE CASING 5504-5512' and 5526-5554' - Acidized with 2000 gal. 15% HCl with 1000 gal. terasperse, CENERALIZE PROOFE CASING SIZE WEIGHT, 13/77. DEPTH SET (NO) EGLE SHE 20 gal. FE-1A & 4 gal. HAI-75 inhibitor. Fraced with 42,000 200 sx Class 'G' 8-5/8" 255 gal. VER-1400 gelled water with 62,500# 20/40 sand & 10,000# 5-1/2" 15.5 56501 5000-5010' and 4732-4738' - Fraced with 25,000 gal. VER-1400 gelled water with 28,000! of 20/40 sand & 10,000f of 10/20 sand. Casing Shoe @ 255' 4732'-5512' **TUBING** Size: 2 7/8" Total String Length: EOT 5584' PERFORATION RECORD 5504-5512' - 2 SPF, 23 gram, 4" gun 5526-5554' - 2 SPF, 23 gram, 4" gun 5000-5010' - 2 SPF, 23 gram, 4" gun 4732-4738' - 2 SPF, 23 gram, 4" gun EOT @ 5584' PBTD @ 5620* NEWFIELD TD @ 5650°

Attachment E-7

Federal 1-17-9-16

Initial Production: BOPD, Spud Date: 9-13-06 Put on Production: 11-15-06 MCFD, BWPD Wellbore Diagram GL: 5878' KB. 5890' FRAC JOB SURFACE CASING 11-07-06 5572-5592 Frac CP1 sands as follows: CSG SIZE: 8-5/8' 25276# 20/40 sand in 354 bbls Lightning 17 GRADE LSS frac fluid Treated @ avg press of 2000 psi w/avg rate of 25 5 BPM ISIP 2000 psi Calc WEIGHT 24# flush 5107 gal Actual flush 5570 gal LENGTH 7 its (311.97') Frac LODC sands as follows: 11-07-06 5316-5362 DEPTH LANDED: 323 82' KB 140563# 20/40 sand in 964 bbls Lightning 17 frac fluid Treated @ avg press of 2425 psi w/avg rate of 25 BPM ISIP 2450 psi Calc flush 4809 gal Actual flush 5314 gal HOLE SIZE 12-1/4" CEMENT DATA 160 sxs Class "G" cmt, est 6 bbls cmt to surf Frac A 1 sands as follows: 11-08-06 5086-5111' 90538# 20/40 sand in 724 bbls Lightning 17 frac fluid Treated @ avg press of psi w/avg rate of BPM ISIP 2190 psi Calc flush 4578 gal Actual flush 5084 gal PRODUCTION CASING Frac C sands as follows: 11-08-06 4835-4845 CSG SIZE 5-1/2' 30222# 20/40 sand in 404 bbls Lightning 17 frac fluid Treated @ avg press of 2105 w/ GRADE J-55 avg rate of 25 5 BPM ISIP 2060 psi Calc WEIGHT 15 5# flush 4368 gal Actual flush 4833 gal LENGTH 137 jts (6007 66') Frac D1, & D2 sands as follows: 11-08-06 4668-4737 DEPTH LANDED 6020 91' KB 80170# 20/40 sand in 587 bbls Lightning 17 frac fluid Treated@ avg press of 1932 w/ avg rate of 25 5 BPM ISIP 2090 psi Calc HOLE SIZE 7-7/8" CEMENT DATA 350 sxs Prem Lite II mixed & 450 sxs 50/50 POZ flush 4162 gal Actual flush 4666 gal CEMENT TOP AT 6' 11-08-06 4174-4183 Frac GB4 sands as follows: 27661# 20/40 sand in 296 bbls Lightning 17 frac fluid Treated @ avg press of 1800 w/ avg rate of 25 3 BPM ISIP 1818 psi Calc TUBING flush 4032 gal Actual flush 4172 gal SIZE/GRADE/WT 2-7/8" / J-55 / 6 5# 4/13/11 Tubing leak Updated rod & tubing detail 4174-4183 NO OF JOINTS 183 jts (5544 7') TUBING ANCHOR 5556 7' KB NO OF JOINTS 2 jts (63 1') SEATING NIPPLE: 2-7/8" (1 10') 4668-4682 SN LANDED AT 5622.6' KB 4725-4737 NO OF JOINTS 2 jts (596') TOTAL STRING LENGTH EOT @ 5684' KB 4835-4845 5086-5094 ≥ 5101-5111° PERFORATION RECORD SUCKER RODS 11-01-06 5587-5592' 4 JSPF 20 holes 5572-5578' 4 JSPF POLISHED ROD 1-1/2" x 26' 11-01-06 24 holes 5347-5362' 4 JSPF 11-07-06 60 holes SUCKER RODS 99 x 3/4" = 2475 guided rods, 107 x 3/4" = 2675' sucker rods, $10 \times \frac{1}{4}$ " = 250' guided rods, $6 \times 1 \frac{1}{2}$ " = 150' weighted bars, $6 \times 1 \frac{1}{2}$ " = 24 11-07-06 5316-5326' 4 JSPF 40 holes 5316-5326 stabilizer rod 11-07-06 5101-5111' 4 JSPF 40 holes 5347-5362 PUMP SIZE 2-1/2" x 1-1/4" x 12' x 16 RHAC 11-07-06 5086-5094' 4 JSPF 32 holes 11-08-06 4835-4845' 4 JSPF 40 holes STROKE LENGTH 86' 11-08-06 4725-4737' 4 JSPF 48 holes PUMP SPEED, SPM 5 SPM 11-08-06 4668-4682' 4 JSPF 56 holes Anchor @ 5557 11-08-06 4174-4183' 4 JSPF 36 holes 5572-5578 5587-5592 EOT @ 5684' NEWFIELD PBTD @ 5999

SHOE @ 6020

TD @ 6075



Federal 1-17-9-16

660' FNL & 660' FEL

NE/NE Section 17-T9S-R16E

Duchesne Co, Utah

API # 43-013-33028; Lease # UTU-64379

Federal 8-17-9-16

Spud Date: 09/12/06 Put on Production: 11/09/06

K.B.: 5918, G.L.: 5906 SURFACE CASING

Wellbore Diagram

Casing Shoe @ 323'

SN 5308

Initial Production: BOPD. MCFD. BWPD

FRAC JOB

11/06/06 5295-5304'

11/06/06 4105-4114'

11/06/06 3940-4014

7/23/08

3940-3949

4005-4014

4105-4114'

4710-4721

5078-5091

EOT 53753

PBTD @ 6025

SHOE @ 6046'

TD @ 6050'

Anchor @ 5272' 5295-5304'

Frac LODC sands as follows: 30252# 20/40 sand in 392 bbls Lightning 17 frac fluid Treated @ avg press of 3045 psi w/avg rate of 24.9 BPM ISIP 2580 psi Calc

flush 5302 gal. Actual flush: 4767 gal.

11/06/06 4710-4721 Frac C sands as follows:

Hara C. sands as follows: 41525# 20/40 sand in 417bbls Lightning 17 frac fluid Treated @ avg press of 1996 psi w/avg rate of 25.1BPM ISIP 1960 psi Calc flush 4719 gal. Actual flush 4204 gal.

Frac GB4 sands as follows: 21385# 20/40 sand in 280 bbls Lightning 17

frac fluid Treated @ avg press of 1809 psi w/avg rate of 25 8 BPM ISIP 1610 psi Calc flush: 4112 gal. Actual flush: 3637 gal. Frac GB2 sands as follows:

68288# 20/40 sand in 591 bbls Lightning 17

frac fluid Treated @ avg press of 1782 psi w/avg rate of 25.3 BPM. ISIP 1505 psi. Calc flush: 4012 gal. Actual flush:3822 gal.

HIT Rod & tubing updated

Cement Top@ 10'

CSG SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24#

LENGTH: 7 jts. (311 03') DEPTH LANDED: 323 45' KB

HOLE SIZE 12-1/4"

CEMENT DATA: 160 sxs Class "G" cmt, est 7 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2" GRADE: J-55 WEIGHT: 15,5#

LENGTH: 137 jts. (6032.95') DEPTH LANDED: 6046.20' KB

HOLE SIZE: 7-7/8"

CEMENT DATA 325 sxs Prem Lite II mixed & 450 sxs 50/50 POZ

CEMENT TOP: 10'

TUBING

SIZE/GRADE/WT :: 2-7/8" / J-55 / 6.5# NO. OF JOINTS: 164 jts (5260,26') TUBING ANCHOR 5272.26' KB NO OF JOINTS: 1 jts (32.50') SEATING NIPPLE 2-7/8" (1.10') SN LANDED AT: 5307.56' KB NO OF JOINTS: 2 its (66.03') TOTAL STRING LENGTH: EOT @ 5375.14' KB

PERFORATION RECORD

10/25/06 5295-5304' 4 JSPF 36 holes 11/06/06 5078-5091' 4 JSPF 52 holes 11/06/06 4710-4721 4 JSPF 44 holes 11/06/06 4105-4114' 4 JSPF 36 holes 11/06/06 3940-3949' 4 JSPF 36 holes

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM

SUCKER RODS: 1-8', 2-4' x 3/4" pony rod, 92-3/4" guided rods,81-3/4" plain rods, 30-3/4" scrapered rods, 6-1 1/2" weight rods

PUMP SIZE 2-1/2" x 1-1/2" x 14' RHAC w/SM plunger

STROKE LENGTH: 84"

PUMP SPEED, 5 SPM



Federal 8-17-9-16

1944' FNL & 675' FEL

SE/NE Section 17-T9S-R16E

Duchesne Co, Utah

API #43-013-33031; Lease #UTU-64379

ATTACHNENT E9

Federal 9-17-9-16

Spud Date: 9-11-06 Put on Production: 11-01-06

> 2108' FSL & 636' FEL NE/SE Section 17-T9S-R16E Duchesne Co, Utah API # 43-013-33032; Lease # UTU-52018

Wellbore Diagram

Initial Production: BOPD. MCFD, BWPD

GL: 5953' KB: 5965' FRAC JOB SURFACE CASING 10-27-06 5540-5572 Frac CP1 sands as follows: CSG SIZE: 8-5/8" Cement top @ 30 89695# 20/40 sand in 672 bbls Lightning 17 frac fluid. Treated @ avg press of 1635 psi w/avg rate of 24.9 BPM_ISIP 2000_psi_Calc GRADE J-55 WEIGHT: 24# flush: 5040 gal, Actual flush; 5538 gal, LENGTH 7 jts (310 22') Casing Shoe @ 322' Frac LODC sands as follows: 10-27-06 5236-5256 DEPTH LANDED: 322.07' KB Frac LODG. Santa as follows 80345# 20/40 sand in 604 bbls Lightning 17 frac fluid. Treated @ avg press of 2685 psi w/avg rate of 27.3 BPM. ISIP 2560 psi. Calc flush: 4746 gal. Actual flush: 5234 gal. HOLE SIZE 12-1/4" CEMENT DATA: 160 sxs Class "G" cmt, est 6 bbls cmt to surf. 10-27-06 5129-5148 Frac A 3 sands as follows: 80324# 20/40 sand in 597 bbls Lightning 17 frac fluid. Treated @ avg press of 2175 psi w/avg rate of 24 7 BPM. ISIP 2240 psi. Calc flush: 4923 gal. Actual flush: 4410 gal. PRODUCTION CASING 10-27-06 4092-4114 Frac GB4 sands as follows: CSG SIZE: 5-1/2 38251# 20/40 sand in 358 bbls Lightning 17 frac fluid. Treated @ avg press of 1410 w/ avg rate of 14.3 BPM. ISIP 1490 psi. Calc GRADE: J-55 WEIGHT: 15.5# flush: 4485 gal. Actual flush: 4410 gal. LENGTH 139 jts. (6032.96') 2/23/07 Pump Change. Rod & Tubing detail updated DEPTH LANDED: 6044-21' KB 05/27/08 updated rod and tubing detail HOLE SIZE: 7-7/8" CEMENT DATA 325 sxs Prem, Lite II mixed & 450 sxs 50/50 POZ 11/23/09 Pump change. Updated rod and tubing detail. CEMENT TOP AT: 30' **TUBING** SIZE/GRADE/WT: 2-7/8" / J-55 / 6_5# NO_OF JOINTS: 175 jts (5485.5') TUBING ANCHOR: 5485.5' KB NO OF JOINTS 2 jts (63.0') SEATING NIPPLE: 2-7/8" (1,10') SN LANDED AT 5551 2' KB NO OF JOINTS 2 jts (63.1') TOTAL STRING LENGTH: EOT @ 5616' KB PERFORATION RECORD SUCKER RODS 10-17-06 5540-5572' 4 JSPF 128 holes 10-27-06 5236-5256' 4 JSPF 80 holes POLISHED ROD: 1-1/2" x 22' SM 10-27-06 5129-5148' 4 JSPF 76 holes SUCKER RODS: 1-2'x 1/4" pony rod, 1-6'x 1/4" pony rod, 1-8'x 1/4" pony rod, 10-27-06 4092-4114' 4 JSPF 88 holes 99- 1/4" guided rods, 86- 1/4" guided rods, 30- 1/4" guided rods, 6- 1 1/2" weight 4092-4114 PUMP SIZE: 2-1/2" x 1-1/2" x 12' x 16' RHAC pump STROKE LENGTH: 86° 5129-5148 PUMP SPEED, SPM: 5 SPM 5236-52561 Anchor @ 5486' 5540-5572' SN 5551' EOT @ 5616' NEWFIELD PBTD @ 5998' SHOE @ 6044* Federal 9-17-9-16

TD @ 6050'

State 13-16-9-16

Wellbore Diagram

Spud Date: 4/9/08

Put on Production: 6/18/08 GL: 5959' KB: 5971'

SURFACE CASING

CSG SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24#

LENGTH: 7jts (313,38') HOLE SIZE: 12-1/4"

CEMENT DATA: To Surface with 160 sx Class 'G' cmt

PRODUCTION CASING

CSG SIZE: 5-1/2" GRADE: J-55 WEIGHT: 15.5# LENGTH: 132jts HOLE SIZE: 7-7/8" DEPTH LANDED: 5763.29

CEMENT DATA: 275 sx Premlite II and 400 sx 50/50 Poz

CEMENT TOP AT: 46'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO, OF JOINTS: 177 jts (5460.9')
TUBING ANCHOR: 5472.9'
NO, OF JOINTS: 1jt (31,70')
SEATING NIPPLE: 2-7/8" (1,10')
SN LANDED AT: 5507.1 'kb
NO, OF JOINTS: 1 jts (31,10')
TOTAL STRING LENGTH: EOT @ 5540

SUCKER RODS

POLISHED ROD: 1-1/2" x 26' polished rod

SUCKER RODS: $1 \times \frac{1}{4}$ " = 2' pony rods, 113-3/4" = 2825' guided rods, 55-3/4" = 1375' sucker rods, 41-3/4" = 1025' guided rods, 6-1 1 $\frac{1}{2}$ " = 150'sinker bars

PUMP SIZE: CDI 2-1/2" x 1-1/4" x 12' x 16' RHAC pump

STROKE LENGTH: 100" PUMP SPEED, SPM: 4

NEWFIELD

State 13-16-9-16
652' FSL & 524' FWL
SW/SW Section 16-T9S-R16E
Duchesne Co, Utah
API #43-013-33853; Lease #Utah State ML-16532

FRAC JOB

3978-3986"

4156-4164

4670-4680

4694-4701*

Anchor @ 5473'

5506-5516

5520-5528

EOT @5540'

PBTD @ 5742'

TD@ 5770*

06-06-08 5506-5616' Frac CP1 sds as follows: 40,770# 20/40 sand in 426 bbls of Lightning 17 fluid, Treated w/ ave pressure of 1994 psi w/ ave rate of 23,8 BPM. ISIP 2188 psi, Actual Flush: 4914 gals.

06-06-08 4670-4680' Frac D2 sds as follows: 40,545# 20/40 sand in 410 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1811 psi w/ ave rate of 23.8 BPM. ISIP 1920 psi. Actual Flush: 4120 gals.

06-06-08 4156-4164' Frac GB6 sds as follows: 50,204# 20/40 sand in 438 bbls of Lightning 17 fluid. Treated w/ ave pressure of 1855 psi w/ ave rate of 24.0 BPM, ISIP 1810 psi, Actual Flush: 3692 gals.

 $06-06-08\quad 3978-3986' \qquad \textbf{Frac GB2 sds as follows:} \\ 30,226\#\ 20/40\ \text{sand in }\ 366\ \text{ bbls of Lightning }\ 17\ \text{fluid. Treated w/ ave pressure of }\ 1552\ \text{psi}\ \text{w/ ave rate of }\ 15,6\ \text{BPM}_{\circ}\ \text{ISIP }\ 1587\ \text{psi}. Actual Flush: }\ 3893\ \text{gals}_{\circ}$

1/6/09 Tubing Leak, Updated rod & tubing details.

9/30/09 Tubing Leak, Updated rod & tubing

07/24/10 Pump Change, Updated rod & tubing

4/19/2011 Tubing Leak, Updated rods & tubing

PERFORATION RECORD

 3978-3986'
 4 JSPF
 32 holes

 4156-4164'
 4 JSPF
 32 holes

 4670-4680'
 4 JSPF
 40 holes

 4694-4701'
 4 JSPF
 28 holes

 5506-5516'
 4 JSPF
 40 holes

 5520-5528'
 4 JSPF
 32 holes

Packer Plus 8-5/8" x 5-1/2" RockSeal II 10K Hydraulic Set Open Hole Packer (Actuated at 2,046psi)

8

7

6

Wellhead

Rockstal II Packer

12

5.5 x4.5X XO 5,993

5,372

Lat Length Total Stim. Lateral

Avg. Stage Length

11

5,377

3,804

3.804

10

317 *between packers

9

GMB 3-16-9-16H

NEWFIELD

(bbl)

335,921

244.388

153

MD TD 10.259 TVD TD 6.011

Wellbore Diagram

Sand Total

3

4

5

100 mesh sand

30/50 mesh sand

sand per foot of lateral

ATTACHMENT

Multi-Chem Group, LLC

Multi-Chem Analytical Laboratory 1553 East Highway 40 Vernal, UT 84078



Sample ID: WA-53132

Water Analysis Report

Production Company: NEWFIELD PRODUCTION (158)

Well Name: south wells draw IF

Sample Point: tank Sample Date: 1 /7 /2011 Sales Rep: Monty Frost Lab Tech: Peter Poulsen

Sample Specifics					
Test Date:	1/24/2011				
Temperature (°F):	100				
Sample Pressure (psig):					
Specific Gravity (g/cm³):	1.0006				
pH:	7.25				
Turbidity (NTU):					
Calculated T.D.S. (mg/L)	5345				
Molar Conductivity (µS/cm):	8099				
Resitivity (Mohm):	1.2347				

	Analysis @ Proper
Cations	mg/L
Calcium (Ca):	31.62
Magnesium (Mg):	15.12
Barium (Ba):	8.18
Strontium (Sr):	*
Sodium (Na):	1897.00
Potassium (K):	
Iron (Fe):	0.12
Manganese (Mn):	0.02
Lithium (Li):	
Aluminum (AI):	
Ammonia NH₃ :	

Anions	mg/L
Chloride (CI):	2500.00
Sulfate (SO ₄):	88.00
Dissolved CO ₂ :	
Bicarbonate (HCO ₃):	805.00
Carbonate (CO ₃):	
H ₂ S:	
Phosphate (PO ₄):	
Silica (SiO ₂):	•
Fluoride (F):	
Nitrate (NO ₃):	
Lead (Pb):	
Zinc (Zn):	
Bromine (Br):	
Boron (B):	

		RIGHT	Sca	le Values @	Test Co	onditions - Potential Amount of Scale in lb/1000bbl						
Test Conditions		Calcium Carbonate			Gypsum CaSO ₄ : 2H ₂ O		Calcium Sulfate CaSO 4		Strontium Sulfate SrSO ₄		Barium Sulfate BaSO ₄	
Temp °F	Gauge Press.	Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	psi
100		0.76	-0.74	0.00	-1872.00	0.00	-1990.00			28.50	13.37	1.25
80	0	0.55	-1.54	0.00	-5.19	0.00	-2126.70	-	-	43.03	13.55	0.57
100	0	0.76	-0.74	0.00	-3.25	0.00	-1990.00	-	-	28.50	13.37	0.70
120	0	0.98	-0.06	0.00	-1.85	0.00	-1792.60			19.32	13.12	0.79
140	0	1.22	0.57	0.00	-0.80	0.00	-1562.50			13.37	12.78	0.89
160	0	1.47	1.15	0.00	0.01	0.00	-1323.40	-	-	9.43	12.32	1.01
180	0	1.72	1.70	0.00	0.63	0.01	-1092.60		*	6.77	11.71	1.11
200	0	1.96	2.21	0.01	1.12	0.01	-881.65		*	4.94	10.90	1.13
220	2.51	2.16	2.69	0.01	1.48	0.01	+703.26			3.59	9.80	1.14
240	10.3	2.34	3.11	0.01	1.72	0.02	-544.83	-	Ţ	2.67	8.45	1.17
260	20.76	2.48	3.47	0.01	1.84	0.02	-413.16	-		2.01	6.73	1.19
280	34.54	2.59	3.76	0.01	1.86	0.04	-306.03	-		1.53	4.58	1.22
300	52.34	2.65	3.95	0.01	1.79	0.06	-220.34			1.17	1.91	1.25

Conclusions:

Notes:

Calcium Carbonate scale is indicated. See graph for appropriate temperature ranges.

Gypsum Scaling Index is negative from 80°F to 300°F

Calcium Sulfate Scaling Index is negative from 80°F to 300°F

Strontium Sulfate scaling was not evaluated

Barium Sulfate scale is indicated at all temps from 80°F to 300°F

Monday, January 24, 2011 **Multi-Chem Production Chemicals**

ATTACHMENT (

Multi-Chem Group, LLC


Multi-Chem Analytical Laboratory 1553 East Highway 40 Vernal, UT 84078





Scale Prediction Graphs

Well Name: south wells draw IF










Commitment



ATTACHMENT F

Multi-Chem Group, LLC

Multi-Chem Analytical Laboratory 1553 East Highway 40 Vernal, UT 84078



Water Analysis Report

Production Company: NEWFIELD PRODUCTION (158)

Well Name: 5-16-9-16
Sample Point: Treater
Sample Date: 5 /16/2011
Sales Rep: Darren Betts
Lab Tech: John Keel

Sample	ID:	WA-58625	

Sample Specific	cs
Test Date:	6/3/2011
Temperature (°F):	70
Sample Pressure (psig):	
Specific Gravity (g/cm³):	1.0160
pH:	8.5
Turbidity (NTU):	
Calculated T.D.S. (mg/L):	22593
Molar Conductivity (µS/cm):	34232
Resitivity (Mohm):	0.2921

Cations	mg/L	Anions	mg/L
Calcium (Ca):	11.60	Chloride (CI):	13000.00
Magnesium (Mg):	6.60	Sulfate (SO 4):	17.00
Barium (Ba):	10.00	Dissolved CO ₂ :	
Strontium (Sr):		Bicarbonate (HCO 3):	927.20
Sodium (Na):	8620.00	Carbonate (CO 3):	•
Potassium (K):		H ₂ S:	0.50
Iron (Fe):	0.30	Phosphate (PO ₄):	
Manganese (Mn):	0.04	Silica (SiO ₂):	-
Lithium (Li):		Fluoride (F):	
Aluminum (AI):		Nitrate (NO ₃):	
Ammonia NH ₃ :		Lead (Pb):	
·		Zinc (Zn):	
		Bromine (Br):	
		Boron (B):	

		Scale Values @ Test Conditions - Potential Amount of Scale in lb/1000bbl										
Test Conditions		Calcium Carbonate		Gypsum CaSO ₄ - 2H ₂ O		Calcium Sulfate CaSO 4		Strontium Sulfate SrSO ₄		Barium Sulfate BaSO ₄		Calculated
Temp	Gauge Press.	CaC	O ₃	Caso.	2H 2U		00011		Sh.I-			
°F	psi	Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	psi 0.09 0.03 0.04 0.05 0.06 0.07 0.08 0.08 0.08 0.09
70		1.74	7.85	0.00	-3119.00	0.00	-3567.50		-	6.78	13.06	0.09
80	0	2.04	9.96	0.00	-3152.50	0.00	-3520.40	-		5.36	12.19	0.03
100	0	2.60	12.72	0.00	-3185.70	0.00	-3325.00			3.58	10.30	0.04
120	0	3.00	13.98	0.00	-2969.60	0.00	-3030.40	-	-	2.54	8.23	0.05
140	0	3.22	14.33	0.00	-2751.10	0.00	-2679.00			1.83	5.81	0.06
160	0	3.22	13.97	0.00	-2571.90	0.00	-2307.50	-	•	1.33	3.01	0.07
180	0	3.04	12.98	0.00	-2425.30	0.00	-1944.10	-	-	0.98	-0.19	0.08
200	0	2.73	11.42	0.00	-2306.30	0.00	-1607.60	-	17	0.73	-3.82	0.08
220	2.51	2.34	9.36	0.00	-2239.80	0.00	-1325.40	-		0.54	-8.30	0.08
240	10.3	1.98	7.10	0.00	-2167.20	0.00	-1065.60	-	7	0.40	-13.06	0.08
260	20.76	1.65	4.84	0.00	-2112.30	0.00	-846.48	(-		0.31	-18.43	0.09
280	34.54	1.36	2.74	0.00	-2073.70	0.00	-665.41	(T.	7	0.23	-24.50	0.09
300	52.34	1.11	0.89	0.00	-2050.30	0.00	-518.29	-	-	0.18	-31.38	0.09

Conclusions:

Calcium Carbonate scale is indicated at all temps from 80°F to 300°F

Gypsum Scaling Index is negative from 80°F to 300°F

Calcium Sulfate Scaling Index Is negative from 80°F to 300°F

Strontium Sulfate scaling was not evaluated

Barium Sulfate NO CONCLUSION

Notes:

P=0.9

ATTACHMENT P


Multi-Chem Group, LLC Multi-Chem Analytical Laboratory


1553 East Highway 40 Vernal, UT 84078



Scale Prediction Graphs

Well Name: 5-16-9-16






140 140 160 160 220 220 240 260 300

Temperature in degrees fahrenheit

Barium Sulfate BaSO₄ 14.0 12.0 Potential Amount of Scale (lbs/1000bbl) 10.0 Saturation Index 8.0 2.0 0 280 200 120 age 00, Temperature in degrees fahrenheit



Attachment "G"

State #5-16-9-16 Proposed Maximum Injection Pressure

				Calculated	
Frac Interval				Frac	
(fe	eet)	Avg. Depth	ISIP	Gradient	
Top	Bottom	(feet)	(psi)	(psi/ft)	Pmax
5698	5706	5702	2046	0.79	2009
5334	5342	5338	2165	0.84	2130
5080	5091	5086	2582	0.94	2549
4968	4974	4971	2959	1.03	2927
4778	4785	4782	2279	0.91	2248
4170	4182	4176	1929	0.90	1902 ◀──
				Minimum	1902

Calculation of Maximum Surface Injection Pressure

Pmax = (Frac Grad -(0.433*1.015)) x Depth of Top Perf where pressure gradient for the fresh water is .433 psi/ft and specific gravity of the injected water is 1.015.

Frac Gradient = (ISIP +(0.433*Top Perf.))/Top Perf.

Please note: These are existing perforations; additional perforations may be added during the actual conversion procedure.



NEWFIELD ATTACHMENT G-/

1 of 11

DAILY COMPLETION REPORT

WELL NAME:	State 5-16-9-1	<u> </u>	Report Date:	5/6/	2008		Day:1_
Operation:	Completion				Rig:	Rigless	
		WEL	L STATUS_				
Surf Csg: 8-5/8		Prod Cs	g: <u>5-1/2"</u>	@	5820'	Csg PBTD:	
Tbg: Size:	Wt:	Grd:	Pkr/EC	OT @:	E	3P/Sand PBTD:	
		PERFOR/	ATION RECORE	2			
<u>Zone</u>	<u>Perfs</u>	SPF/#shots	Zo	<u>ne</u>	<u>Pe</u>	<u>rfs</u>	SPF/#shots
	-						
			***************************************				***************************************
CP3 sds	 5698-5706'	4/32					
			GICAL OPERAT	IONS	<u></u>		
Date Work Perfor	med: 5/2/200		DIOAL OF LIVAT	10110	SITP:	SICP:	0
	ead. NU 6" 5K Camer					· · · · · · · · · · · · · · · · · · ·	
Starting fluid load Fluid <u>lost/</u> recovere Ending fluid to be	d today: 0	Sta Oil	COVERY (BBLs arting oil rec to d lost/recovered t m oil recovered:	late: coday:			
IFL:		Chol	ke:	Final F	luid Rate:	Final	oil cut:
	STIMULATION D	ETAIL				COSTS	
Base Fluid used: _	Job	Туре:			Weather		\$540
Company:				3000000		NU crew	\$300
Procedure or Equi	pment detail:					trucking	\$800
						itors LLC	\$6,113
						lling cost	\$370,183
						M Hot Oil	\$360
<u> </u>	<u></u>				Location pre		\$300
and the second second					NPC	wellhead	\$1,500
					Benco -	anchors	\$1,200
						<u>Overhead</u>	\$4,000
					NPC Su	pervision	\$300
Max TP:			od:	_			
Avg TP: ISIP:		_. Total Prop pmլ 0 min:	pd: FG:	<u></u>	DAILY CO		\$385,596
Completion S		Dulen		- Т	OTAL WEL		\$385,596
Completion 3	aher Aigory	Duitii		•	V : // !! !!		\$555,550



									,	2011
				Y COMPL						
WELL I		State 5-			Report Da	ite:5	3/8/2008			Day: <u>2a</u>
Ope	ration:	Completion	1				Rig:	Rigl	ess	
				WELL	STATUS					
Surf Csg:	<u>8-5/8'</u> @	324'			: <u>5-1/2'</u>		5820'	_		5757' WL
Tbg:	Size:	Wt:		Grd:	P	r/EOT @:		BP/Sand P	BID:	
			P	ERFORAT	TION REC	ORD				
Zone		<u>Perfs</u>	<u>SPF/#</u>	shots		Zone		<u>Perfs</u>		SPF/#shots
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,								-		
										
	·····			***************************************						
							***************************************	-		
CP3 sds		3-5706'	4/32							
			· · · · · · · · · · · · · · · · · · ·	ONOLOGIC	CAL OPER	RATIONS		_		
Date Wor	k Performe	d: <u>5</u>	/7/2008				SITP:		SICP:	0 psi
				LUID REC	OVERY (F	IRI S)				
Starting fl	uid load to b	e recovered:	136		ting oil rec					
_	recovered to		434							
_	id to be reco	vered:	570		oil recove					
IFL:	FFL	•••	FTP:	Choke): 	Fina	al Fluid Rate:		Final	oil cut:
		STIMULAT	ION DETAIL	L				COST	<u>s</u>	_
Base Fluid	l used: <u>Li</u>		Job Type:	Sar	nd frac			ervices-CP3	•	\$22,316
Company:		ervices						r & trucking		\$896
***************************************	or Equipme			CP3 sand	<u>ls</u>			NPC fuel gas	•	\$140
<u>780</u>	gals of pre-	pad of 4% Te	chni-Hib 76	7W		······································		d tools/serv		\$1,250
904	gals of flush	n spacer						PC trucking	•	\$300
330	0 gals of pa	<u>d</u>		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			NPC	supervision		\$50
243	1 gals W/ 1-	4 ppg of 20/4	0 sand							
<u>489</u>	0 gals W/ 4-	6.5 ppg of 20	/40 sand							
<u>211</u>	gals W/ 6.5	ppg of 20/40	sand							
Flus	sh W/ 504 ga	als of 15% H	CL acid							
Flus	sh W/ 5191	gals of slick v	vater.							

434 bbls

FG: <u>.79</u>

DAILY COST:

TOTAL WELL COST:

\$24,952

\$410,548

Flush called @ blender--includes 2 bbls pump/line volume

Avg TP: 1941 Avg Rate: 23.2 BPM Total Prop pmpd: 34,586#'s

10 min:

Max TP: 2188 Max Rate: 23.3 BPM Total fluid pmpd:

5 min: Completion Supervisor: Orson Barney

ISIP: 2046



3011

DAILY COMPLETION REPORT

WELL N	IAME:		State 5-16-	9-16	Re	port Date:	5/8	8/2008			Day:	2b
Ope	ration:		Completion					Rig:	Rig	gless		
			<u></u>	<u>_</u>	VELL S	TATUS						
Surf Csg:	8-5/8	@	324'	Pro	d Csg: _	5-1/2"	@ _	5820'	_	PBTD:		
Tbg:	Size:		Wt:	Grd:		Pkr/E	от @: _	· · · · · · · · · · · · · · · · · · ·	BP/Sand	PBTD:	54	<u>40'</u>
				PERF	ORATIO	ON RECOR	<u>D</u>					
<u>Zone</u>			<u>Perfs</u>	SPF/#shots	<u> </u>	<u>Zo</u>	<u>ne</u>		<u>Perfs</u>	_	<u>SPF/#</u>	<u>shots</u>
										_		
LODC	_	5334-	5342'	4/32	-	<u></u>						
CP3 sds			5706'	4/32	_					_		
				CHRONO	LOGICA	L OPERAT	IONS					
Date Worl	(Perfo	rmed	5/7/2	8008				SITP:		SICP:	1674	l psi
@ ave rate 918 BWTF Starting flu Fluid lost/r	e of 23. R See	2 BPN Day 2 to be	recovered:	4 gals of 15% FLUID 570	RECO Startin	flush for State /ERY (BBL g oil rec to coordinate)	age #3 S) late: today:	. ISIP 216	d w/ ave p 5 psi. Leav	ressure re pres	e of 24 sure o	i25 ps n well
Ending flui						il recovered	-	Fluid Rate:		_ Final	oil cut	
IFL:							_ ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' '					
			STIMULATION		Sand	fron		BISan	<u>cos</u> ices-LOD0		Φ.	7,157
Base Fluid Company:			rvices	ob Type:	Sand	ii a c			r & trucking		Ψ	\$640
Procedure				LOD	C sands	;	-		NPC fuel ga			\$100
			ad of 4% Techr					Weatherfor	d tools/ser	 v	\$	2,450
	<u> </u>	<u> </u>	spacer					Lo	ne Wolf W	L	\$	3,137
	gals o				,			NPC	supervisio	<u>n</u>		\$50
			ppg of 20/40 s	and						_		
			.5 ppg of 20/40									
Flus	h W/ 5	04 gal	s of 15% HCL	acid								
Flus	h W/ 4	330 ga	als of slick wate	er.						*********		
			olenderinclude			lume**	<u> </u>					
		•	Rate: 23.6 BP		_	348 bbls		DAILY C	·OST·		<u></u>	3,534
_		•	Rate: 23.2 BP	'M Total Prop 10 min:	pmpa:	FG: .84	-		ELL COST	•	_	24,082
Compl	: 2165		i min:Orse	nn Barnev		FG. 104		IOIAL W	JOJ1	•	Ψ¬∠	1,002



tof11

DAILY COMPLETION REPORT

WELL N	AME:		State 5	-16-9-16	R	eport Date:	5,	/8/2008	_		Day: <u>2c</u>
Oper	ration:	•	Completio	n				Rig:	Riç	gless	
					WELL S	TATUS					
Surf Csg:	8-5/8	@	324'	_	Prod Csg:_		@	5820'			5757' WL
Tbg:	Size:	····	Wt:		Grd:	Pkr/EC	от @:	<u>-</u>	<u>BP</u> /Sand	PBTD: BP: 544	5180'
				Р	ERFORATION	ON RECORE)			DI . 044	
<u>Zone</u>			<u>Perfs</u>	SPF/#s		Zoi	_		<u>Perfs</u>		SPF/#shots
***************************************	<u></u>			-		_					
	-					<u></u>					
A.5 sds	.	5080-	-5091'	4/44							
LODC	- -		-5342'	4/32		_					
CP3 sds	_	5698-	-5706'	4/32							
	-				NOLOGICA	AL OPERAT	<u>IONS</u>	OITE		OLOD-	4700 :
Date Work	Perfo	rmed	: 5	5/7/2008				SITP:	-	SICP:	1708 psi
Services. psi. Pump rate of 23.2 BWTR Se	1708 ped 7802 BPMee Day	osi on gals Pun 2d.	well. Frac of fresh wtr nped 504 g recovered:	ee A.5 sds @ A.5 sds w/ 8- mixed with 3 als of 15% He 918 666	4,098#'s of 2 0 gals of Te CL in flush f LUID RECO Startin	20/40 sand i chni-Hib 767	n 666 W. T ISIP S)	bbls of Lig reated w/ a 2582 psi.	htning 17 fli ve pressure	uid. Br ∍ of 206	oke @ 395€ 65 psi @ av€
Ending flui	d to be	recov		1584		il recovered:					
IFL:		. FFL:	<u></u>	_ FTP:	Choke: _		Fina	I Fluid Rate		_Final	oil cut:
			STIMULA	TION DETAIL					<u>cos</u>		
			htning 17	_ Job Type:	Sand	l frac			Services-A.		\$17,980
Company:			ervices	_				CD W	rtr & trucking	<u>~</u>	\$2,112
Procedure					A.5 sands	,	•	\\\\b_o_f_	NPC fuel ga		\$330
	H			echni-Hib 767	'VV	y 	•	***************************************	rd tools/ser		\$2,450
		***************************************	spacer	······································			•		one Wolf W		\$4,313
	gals (-	NPC	supervisio	<u>rı</u>	\$50
***********			ppg of 20/				-				
8622	2 gals \	N/ 5-8	3 ppg of 20/-	40 sand			-				
<u>1957</u>	gals \	/V/ 8pp	pg of 20/40	sand			-				
Flus	h W/ 5	04 ga	ls of 15% H	CL acid			-				
			als of slick v		<u></u>		-				
				ludes 2 bbls			-				***************************************
		_		BPM Total		666 bbls	-	DAILY	COST		\$27,235
_		-		BPM Total	-toh bwba;	FG: .94	-		/ELL COST		\$451,317
	: 2582	-	5 min:	_ 10 min: Orson Barne		ru. <u>.54</u>	-	IOIAL W	LLL GOO!		Ψ-01,011



ATTACHMENT G-1 5 of 11

Day: 2d

DAILY COMPLETION REPORT

State 5-16-9-16

Report Date: 5/8/2008

WELL N	AME:	State 5-	16-9-16	Re	port Date: _	5/8/20	800			Day: <u>2d</u>
Oper	ration:	Completion	1				Rig:	Rig	less	
				WELL S	TATUS					
Surf Csg:	8-5/8	@ 324'		Prod Csg:		@ 5	820'	Csg	PBTD:	5757' WL
Tbg:	Size:	Wt:	G	rd:	Pkr/EO	т @:		BP/Sand		
	ŕ		 D.F.	DEODATIO	W DECODD			BP:	5180',	5440'
Zono		Perf <u>s</u>	<u>PE</u> SPF/#sI		N RECORD Zone			<u>Perfs</u>		SPF/#shots
<u>Zone</u>		<u> </u>	<u>51 1 /#31</u>	<u> </u>		<u>~</u>			_	
B2 sds		4968-4974'	4/24						-	
A.5 sds		5080-5091'	4/44			······································				
LODC	- ,	5334-5342'	4/32							
CP3 sds	- ,	5698-5706'	4/32						_	
			CHRO	NOLOGICA	L OPERATION	ONS	_			
Date Work	Perfo	rmed: <u>5</u>	/7/2008				SITP:	, , , , , , , , , , , , , , , , , , , ,	SICP:	1921 psi
Set plug @ 1921 psi of Pumped 78	5040 on well 30 gals M. Pu	VLT, crane & lubric Perforate B2 so Frac B2 sds w of fresh wtr mixed Imped 504 gals of 2e.	ds @ 4968- 7 v/ 24,764#'s o d with 30 gals	4' w/ 3-1/8" of 20/40 sa s of Techni-	Slick Guns v nd in 354 bk Hib 767W. T	w/ 4 spf folsoft of Lighten Teated With the English Properties	or total htning / ave pr	of 24 shots 17 fluid. E essure of 3	s. RU Broke 365 ps	BJ Services @ 3710 psi si @ ave rate
			<u>FL</u>	UID RECOV	/ERY (BBLS)			_	
Starting flu	id load	to be recovered:	1584		g oil rec to da				•••	
Fluid lost/r		-	354		t/recovered to	day:	······································			
Ending flui		recovered:	1938 FTP:		il recovered:	Final Flu	id Rate:		– Final	oil cut:
			ION DETAIL					COST	<u>-</u>	
Race Fluid	neeq.	Lightning 17	Job Type:	Sand	frac		BJ :	Services-B2		\$7,084
Company:		BJ Services						tr & trucking		\$640
		ipment detail:	,	B2 sands				NPC fuel gas	 S	\$100
		pre-pad of 4% Te				We	atherfo	d tools/serv	<u></u>	\$2,450
·		of flush spacer				2000000	Lo	ne Wolf Wl	_ _	\$2,353
	gals o						NPC	supervision	<u> </u>	\$50
		N/ 1-4 ppg of 20/4	0 sand							
		N/ 4-6.5 ppg of 20								
Flus	h W/ 5	04 gals of 15% H0	CL acid							***************************************
Flusi	h W/ 4	465 gals of slick w	/ater.				······································			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
									******	···
***************************************		ed @ blenderincl								
		Max Rate: 23.7		_	354 bbls		AU V	· OST	_	¢10 677
_		Avg Rate: _23.3		rop pmpd:			DAILY (·.	\$12,677 \$463,004
	: <u>2959</u> etion S		_ 10 min: _ Drson Barney		FG: <u>1.03</u>	10	IAL W	ELL COST	•	\$463,994



6 of 11

DAILY COMPLETION REPORT

WELL N	AME:	State 5-1	6-9-16	Re	port Date:	5/	8/2008			Day: _	<u> 2e</u>
Oper	ation:	Completion					Rig:	Rig	less		
	<u> </u>		WE	LL ST	ATUS_						
Surf Csg:	8-5/8' @	324'	Prod (Csg:		@ .	5820'	_		5757'	
Tbg:	Size:	Wt:	Grd: _		Pkr/EC	OT @: .		BP/Sand			
			DEDEO	DATIO	N RECORD	`		BP: 504	U', 518	0', 544(].
Zone		<u>Perfs</u>	SPF/#shots	ILATIO	Zor	_		<u>Perfs</u>		SPF/#s	<u>shots</u>
D2 sds	477	'8-4785 '	4/28				<u></u>		-		
B2 sds		8-4974'	4/24						_		
A.5 sds	508	0-5091'	4/44						-		
LODC		4-5342'	4/32				**************************************		-		
CP3 sds		8-5706'	4/32								
			CHRONOLO	OGICA	<u>OPERAT</u>	<u>ONS</u>					
Date Work	Performe	ed: <u>5/7</u>	/2008				SITP:		SICP:	1452	<u>psi</u>
Pumped 78 of 23.3 BP BWTR Se	30 gals of M. Pumpee Day 2f.	fresh wtr mixed		echni-H sh for S	lib 767W. ~	Treate ISIP 1	ed w/ ave pr 906 psi. L	essure of 1 eave press	975 ps ure or	i @ av	∕e rat∈
Fluid lost/re				_	recovered t				-		
Ending fluid					recovered:	_			_		
IFL:			TP: Ch	oke:		Fina	Fluid Rate:		Final	oil cut:	
		STIMULATIO	ON DETAIL					COST	<u>s</u>		
Base Fluid	used: L	ightning 17	Job Type:	Sand	frac		BJ	Services-D2	<u>)</u>	\$7	7,120
Company:	BJ	Services					CD w	tr & trucking	<u> </u>		\$640
Procedure	or Equipm	ent detail:	<u>D2 sa</u>	ands_			***************************************	NPC fuel gas	<u>3</u>		\$100
780 g	gals of pre	-pad of 4% Tec	hni-Hib 767W				Weatherfor	d tools/serv	<u>/</u>	\$2	2,450
987 g	gals of flus	sh spacer					Lo	ne Wolf WL	-	\$2	2,745
2500	gals of pa	ad					NPC	supervisior	<u>1</u>		\$50
1915	gals W/ 1	-4 ppg of 20/40	sand						_		
3369	gals W/ 4	-6.5 ppg of 20/4	0 sand								
Flush	n W/ 504 g	als of 15% HCl									
Flush	1 W/ 4271	gals of slick wa	ter.								
Flu	sh called (g blenderinclu	des 2 bbls pump/l	ine volu	ıme	•			_		
			PM Total fluid pr		341 bbls	•					0.40=
_			PM Total Prop p	mpd: _		-	DAILY				3,105
	: <u>1906</u> etion Sup	5 min:Or ervisor: Or	10 min:		FG: <u>.83</u>		TOTAL W	ELL COST	:	\$47	7,099



ATTACHMENT G-1 7 of 11

Day: 2f

DAILY COMPLETION REPORT

State 5-16-9-16

WELL NAME:

Report Date: 5/8/2008

Ope	ration:	Complet	ion				Rig:	KIĆ	jiess	
			<u> </u>	WELL ST	TATUS					
Surf Csg:	8-5/8	@ 324'	Р	rod Csg:		@	5820'	Csg	PBTD:	5757' WL
Tbg:	Size:	~	Vt: Gr			от <u>@</u> :		BP/Sand		4280'
J	_					·		BP: 4880',	5040',	5180', 5440'
		_		RFORATIO				D		ODE#-1-4-
Zone		Perfs	<u>SPF/#sh</u>	<u>ots</u>	<u>Zc</u>	<u>one</u>		<u>Perfs</u>		SPF/#shots
GB4 sds D2 sds		170-4182' 778-4785'								
B2 sds		968-4974'	4/24					<u></u>		
A.5 sds		080-5091'	4/44							
LODC		334-5342'	4/32				 			
CP3 sds	<u>5</u>	698-5706'	4/32				WHITE COMMENTS OF THE PARTY OF			
· .			CHRON	IOLOGICA	L OPERA	<u> </u>				
Date Worl	k Perfor	med:	5/7/2008				SITP:		SICP:	<u>1466 psi</u>
gun. Set Services. psi. Pump rate of 23.	plug @ 4 1466 ps ped 780 g 3 BPM.	4280'. Perfor i on well. Fra aals of fresh w	ubricator. RIH wate GB4 sds @ oc GB4 sds w/ 59, wtr mixed with 30 si. Begin immedia BWTR.	4170- 82' \ ,402#'s of 2 gals of Tec	w/ 3-1/8" S 20/40 sand chni-Hib 76	lick Gu in 511 7W. T	ins w/ 4 spf bbls of Ligh reated w/ av	for total on thing 17 flore for the formal for the	of 48 sh uid. Br e of 180	ots. RUB. oke @ 3066)5 psi @ ave
				UD DECOV	(FDV (DDI					
Starting flu	iid load t	o be recovere		IID RECOV	g oil rec to					
Fluid lost/			81		/recovered				_	
		ecovered:	2360		I recovered					
IFL:		FFL:	FTP:	Choke: _		_ Fina	l Fluid Rate:		_Final	oil cut:
		STIMUL	ATION DETAIL					cos	<u>rs</u>	
Base Fluid	l used:	Lightning 1	7 Job Type:	Sand	frac		BJ Se	rvices-GB	<u>4</u>	\$22,572
Company:	В	J Services					CD wt	r & trucking	<u>g</u>	\$1,472
Procedure	or Equip	ment detail:	G	B4 sands			1	NPC fuel ga	<u>s</u>	\$230
780	gals of p	re-pad of 4%	Techni-Hib 767W	V		_	Weatherfor	d tools/ser	<u>v</u>	\$2,450
3		ush spacer					Loi	ne Wolf W	L	\$4,705
	0 gals of					-	NPC	supervisio	n	\$50
***************************************		/ 1-5 ppg of 2	0/40 sand				NPC flov	wback han	- d	\$400
		/ 5-8 ppg of 2					TPS- n	ew J-55 tb	— g	\$26,478
		/ 8 ppg of 20/					Unichen	n chemical	s	\$300
		16 gals of slic				*****	Monks	s pit reclair	 n	\$5,000
1100		. o gano <u>o cono</u>						equipmer		\$150,000
FI:	ısh calle	d @ blenderi	ncludes 2 bbls pu	mp/line vol	 ume	_		elding/labo	-	\$19,500
***************************************			B.5 BPM Total flu	***************************************				wtr disposa		\$8,500
			3.3 BPM Total Pr	_			DAILY C			\$241,657
_	P: 1929	5 min:	10 min:		FG: .90		TOTAL W	ELL COST	:	\$718,756
		·	Orson Barney							



8 of 11

DAILY COMPLETION REPORT

WELL NAM	ИЕ:	Sta	ate 5-16	6-9-16		Rep	ort Date:	5/9	9/2008	_		Day:	3
Operati	ion: Completion Rig: Leed 712 WELL STATUS												
					W	ELL STA	TUS						
Surf Csg: 8-	-5/8' @	32	4'				5-1/2"	@ _	5820'	Csg	PBTD:	5757'	WL_
Tbg: S	ize: 2	7/8"	Wt:	6.5#	_Grd: _	J-55	Pkr/E	OT @: _	4870'	BP/Sand			
				ı	DEDEC	DATION	RECOR	n		_BP: 4880',	5040',	5180', 5	<u> 440'</u>
Zone		Perfs		-	#shots	ZNATION		ne ne		<u>Perfs</u>		SPF/#s	shots
GB4 sds	4170)-4182'		4/48	7311013			110		<u> </u>		<u> </u>	
D2 sds		3-4785'	-	4/28			***************************************				-		
B2 sds	4968	3-4974'		4/24									
A.5 sds)-5091'		4/44					***************************************				
LODC		1-5342'		4/32			***************************************				_		
CP3 sds	5698	3-5706'		4/32									
					ONOL	OGICAL	OPERAT	<u>IONS</u>				_	_
Date Work P	erforme	d: _	5/8/	2008	_				SITP:		SICP:	100	<u>psi</u>
Circulate sand clean down to							o, urilled	up in 4	o miiis, Tā	iggeu sand	<i>₩</i> 402	o, ur	ouialt
				<u> </u>	LUID F	RECOVE	RY (BBL	<u>S)</u>					
Starting fluid	load to be	e recove		2360	•••	Starting of	oil rec to d	date:					
Fluid lost/reco	overed to	day:		2360 25		Starting of Oil lost/re	oil rec to decovered	 late: today:					
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to d	date: today: _ :	Fluid Rate:			oil cut:	
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	Fluid Rate:			oil cut:	
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :		COS	<u>-</u> Г <u>S</u>		5.332
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :		COS Leed rig 71	<u>rs</u> 2	\$	5,332 \$180
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	l Weath	COS	<u>ΓS</u>	\$8	5,332 \$180 \$400
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	Weath NPC v	COS Leed rig 712 Leed rig P12 Leed rig R	<u>TS</u> 2 5 - g	\$5	\$180 \$400
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	l Weath NPC n	COST Leed rig 712 nerford BOF wtr & trucking power swive	TS 2 2 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	\$8	\$180
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	NPC Nabors p	COS Leed rig 712 Leed rig P12 Leed rig R	TS 2 2 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	\$5	\$180 \$400 \$750
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	NPC Nabors p	COS- eed rig 712 nerford BOF wtr & trucking power swive DSI trucking	TS 2 2 5 9 8 8 9	\$8	\$180 \$400 \$750 \$600
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	NPC NPC NPC NPC loca	COS Leed rig 712 nerford BOF wtr & trucking bower swive DSI trucking supervision	TS 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	\$8	\$180 \$400 \$750 \$600 \$300
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	NPC NPC NPC NPC loca	COS- Leed rig 712	TS 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	\$8	\$180 \$400 \$750 \$600 \$300 \$300
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	NPC NPC NPC NPC loca	COS- Leed rig 712	TS 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	\$8	\$180 \$400 \$750 \$600 \$300 \$300
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	Neath NPC Nabors p Ni NPC NPC loca Mt we	COS- Leed rig 712	TS 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	\$8	\$180 \$400 \$750 \$600 \$300 \$300
Fluid lost/reco	overed to o be reco	day: vered:	2	2360 25 335		Starting of Oil lost/re	oil rec to decovered	date: today: _ :	NPC Nabors p NPC NPC loca Mt we	COS- Leed rig 712	TS 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	\$8	\$180 \$400 \$750 \$600 \$300 \$300



90f11

				DAI	LY CO	MPLETIC	N REI	PORT				101 11
WELL N	NAME:	Sta	te 5-16				rt Date:		3/2008			Day: 4
	ration:	Comp	letion						Rig:	Lee	d 712	
<u> </u>					WF	ELL STAT	ับร					
Surf Csg:	8-5/8	@ 324	! '				-1/2"	@	5820'	Csg	PBTD:	5799'
Tbg:	Size:	2 7/8"	Wt:	6.5#	_Grd: _		Pkr/E	от @: _	5680'	BP/ <u>Sand</u>	PBTD:	5799'
					DEDEO	DATION		. D				
Zono		<u>Perfs</u>			<u>PERFUI</u> #shots	RATION		one		<u>Perfs</u>		SPF/#shots
<u>Zone</u> GB4 sds	4	170-4182'		4/48			===	<u> </u>		10.10		
D2 sds		778-4785'		4/28								
B2 sds	_ 4	968-4974'		4/24								
A.5 sds		080-5091'		4/44								
LODC		334-5342'		4/32			***************************************					
CP3 sds		698-5706'		4/32								
					RONOLO	OGICAL (PERA	<u> TIONS</u>		.=	0100	
Date Wor	k Perfor	med:	5/12	2/2008					SITP:		SICP:	25 psi
Starting flu	uid load t	to be recove	ered:	2335		RECOVER Starting o						
Fluid lost/	recovere	<u>d</u> today:		55		Oil lost/re						
		ecovered: _		280		Cum oil re		-	Fluid Data		— Einal	oil cut:
IFL:		FFL:	F	TP:	<u>C</u> r	noke:		_ Finai	Fluid Rate:			on cut.
									_	cos		
	_									_eed rig 71		\$5,983
										erford BO		\$180
										vtr & truckir		\$400
				,					Nabors p	ower swiv	-	\$750
				, <u>.</u>		······				CDI T		\$525
								 .	NPC	supervision		\$300
										CDI S	<u>N</u>	\$80
												
				·							~~~~	
<u></u>												
											_	
		•										
	<u></u>	-		um mumm					DAILY			\$8,218
									TOTAL W	ELL COS	1:	\$735,136

Completion Supervisor: Orson Barney



10 of 11

DAILY COMPLETION REPORT

<u>WELL N</u>	<u>NAME:</u>		Sta	ate 5-1	6-9-16		Rej	port Date	e: <u>5/1</u>	4/2008	-		Day:5_
Ope	ration:		Comp	letion						Rig:		Leed 712	
		-				W	ELL ST	ATUS_					
Surf Csg:	8-5/8	@	32	4'		Prod	Csg:	5-1/2"	@	5820'	C	Csg PBTD:	5799'
Tbg:	Size:	2 7	/8"	Wt:	6.5#	Grd: _	J-55	Pkr/	EOT @:	5508'	BP/ <u>Sa</u>	and PBT <u>D</u> :	5799'
						PERFO	RATIO	N RECO	RD			<u></u>	
Zone		j	Perfs		SPF	/#shots			Zone		<u>Perfs</u>		SPF/#shots
GB4 sds		4170-4	4182'		4/4	8							
D2 sds		4778-	4785'		4/2	В							
B2 sds		4968-	4974'		4/2	4							
A.5 sds	-	5080-	5091'		4/4	4		***************************************		***************************************			
LODC	-	5334-	5342'		4/3	2		-	······································	-			
CP3 sds		5698-	5706'		4/3	2							
					СН	RONOLO	OGICAL	OPER/	ATIONS				•
Date Worl	k Perfo	rmed:	_	5/1:	3/2008					SITP:	25	SICP:	25 psi
25 psi o	n well.	Bleed	l off pr	essure	TOH V	w/ tbg. L	D bit &	bit sub.	PU & RI	H w/ produ	ction tb	g as follow	/s: BP, 4- jts

25 psi on well. Bleed off pressure. TOH w/ tbg. LD bit & bit sub. PU & RIH w/ production tbg as follows: BP, 4- jts 2 7/8" nipple, PBGA, 1- jt, SN, 2-jts, TA, 168 jts of 2 7/8" J-55 tbg. ND BOP, Set TA w/ 15,000#'s of tension @ 5280' Land tbg on flange. NU WH. Prime up rod pump. PU & RIH w/ follow: CDI: 2 1/2" X 1 1/2" X 18' RHAC, 6- 1 1/2" wtl bars, 20- 3/4" guided rods, 93- 3/4" plain rods, 94- 3/4" guided rods, 1-2' X 3/4" sub, 1 1/2" X 26' Polish rod. Space our rods. 2280 BWTR. Left well down due to surface equipment, Final report will follow.

		_	FLUID RECOVERY (BBL	<u>S)</u>		
Starti	ng fluid load to be recovered:	22	80 Starting oil rec to d			
Fluid	lost/ <u>recovered</u> today:				<u></u>	
Endir	g fluid to be recovered:		Cum oil recovered:			
IFL:	FFL:	FTP:	Choke:	Final	Fluid Rate:	Final oil cut:
					COSTS	 <u>3</u>
	PRODUCTION TBG DETAIL		PRODUCTION ROD DETAIL		Leed rig 712	\$5,947
KB	12.00'		1 1/2" x 26' polished rod		CDI rods pump	\$1,450
168	2 7/8" tbg J-55 (5268.08')		1- 2' x 3/4" pony sub		Circ head rubber	\$500
	TA 2.80' @ 5280.08' KB		94- 3/4" guided rods		NPC frc tnks(8X5dys)	\$1,600
2	2 7/8" tbg (62.63')		93- 3/4" plain rods	_	NPC swb tnk(1X5dys)	\$200
	SN 1.10' @ 5345.51'		20- 3/4" guided rods	_	NPC supervision	\$300
1	2 7/8" tbg (30.42')		6- 1 1/2" weight bars	-	NPC frac head	\$500
	PBGA 5.22' @ 5377.03'		2 1/2" X 1 1/2" x 16' x 18'	-	"A" grade rod string	\$13,428
	2 7/8" Nipple 0.50'		RHAC pump	•		
4	2 7/8" tbg (124.81')			•		
	2 7/8" BP & collar 0.75'			_		
	EOT @ 5508.31' w/ 12' KB			-		
				**	DAILY COST:	\$23,925
		-		-	TOTAL WELL COST:	\$759,061
<u></u>	ompletion Supervisor: C)reon	Rarney	-	•	



DAILY COMPLETION REPORT

WELL I	NAME:	S	tate 5-1	6-9-16		Repor	t Date:	5/14/2			Day: <u>6</u>	
Ope	eration:	Com	pletion						Rig:			
					WELL	STAT	<u>us</u>					
Surf Csg:	8-5/8	@ 32	24'		Prod Csg	: 5-	1/2"	@ 5	820'	Csg	PBTD:	5799'
Tbg:	Size:	2 7/8"		6.5#	Grd:	J-55	Pkr/EOT	@:5	508'	BP/ <u>Sand</u>	PBTD:	5799'
					PERFORA	TION R	ECORD					
Zone		<u>Perfs</u>		SPF	/#shots		<u>Zone</u>	2		<u>Perfs</u>		SPF/#shots
GB4 sds		4170-4182	•	4/48	3							
D2 sds	••••	4778-4785		4/28	3							<u></u>
B2 sds		4968-4974		4/24	1							
A.5 sds		5080-5091		4/44	1							£
LODC		5334-5342		4/32	2							
CP3 sds		5698-5706	1	4/32	2							
				СН	RONOLOGI	CAL O	PERATIO	NS				
Date Wor	k Perfo	rmed:	5/1	4/2008					SITP:		_SICP:	
Complete	flow lin	ne ty in. Ad	just tag.	PWOP	@ 1:00 pm	w/ 74" :	SL & 5 SF	PM. Fina	al repor	t.		

			FLUID RECOVERY (BBLS	<u>S)</u>		
Starti	ng fluid load to be recovered:	22	80 Starting oil rec to do			
	lost/recovered_today:		Oil lost/recovered to	oday:		•
Endir	ng fluid to be recovered:	2280				
IFL:	FFL:	FTP:	Choke:	Final	Fluid Rate:	Final oil cut:
					COST	<u>s</u>
	PRODUCTION TBG DETAIL	_	PRODUCTION ROD DETAIL			
KB	12.00'	_	1 1/2" x 26' polished rod			
168	2 7/8" tbg J-55 (5268.08')	_	1- 2' x 3/4" pony sub			
	TA 2.80' @ 5280.08' KB	_	94- 3/4" guided rods	. ,		
2	2 7/8" tbg (62.63')		93- 3/4" plain rods			
	SN 1.10' @ 5345.51'	_	20- 3/4" guided rods		NPC supervision	\$300
1	2 7/8" tbg (30.42')	_	6- 1 1/2" weight bars			
	PBGA 5.22' @ 5377.03'	_	2 1/2" X 1 1/2" x 16' x 18'	. ,		
	2 7/8" Nipple 0.50'		RHAC pump			
4	2 7/8" tbg (124.81')			. ,		
	2 7/8" BP & collar 0.75'					
	EOT @ 5508.31' w/ 12' KB					
			Marine and the Control of the Contro		DAILY COST:	\$300
		-		-	TOTAL WELL COST:	
C	ompletion Supervisor:	Drson	Barney	-		

ATTACHMENT H

WORK PROCEDURE FOR PLUGGING AND ABANDONMENT

1.		Set CIBP @ 4120'
2.	Plug #1	Set 100' plug on top of CIBP using 12 sx Class "G" cement
3.	Plug #2	180' balance plug using 21 sx Class "G" cement 50' above Trona-Bird's Nest extending 50' below base of Mahogany Oil Shale
4.	Plug #3	120' balance plug using 14sx Class "G" cement 60' above Uinta/Green River and extending 60' below
5.	Plug #4	Pump 43 sx Class "G" cement down 5 1/2" casing to 374'

The approximate cost to plug and abandon this well is \$42,000.

State 5-16-9-16

Propose P&A

Spud Date: 04-07-08 Put on Production: 05-14-08 GL: 5922' KB: 5934'

SURFACE CASING

CSG SIZE: 8-7/8" GRADE: J-55 WEIGHT: 24#

LENGTH: 7 jts, (312,48') DEPTH LANDED: 324' HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2" GRADE: J-55 WEIGHT: 15,5#

LENGTH: 139jts. (5807.48') HOLE SIZE: 7-7/8" DEPTH LANDED: 5825'

CEMENT DATA: 300 sk Prem, Lite II mixed & 400 sxs 50/50 POZ.

CEMENT TOP AT: 70'

Wellbore Diagram Cement Top@ 70' Casing Shoe @ 324' Casing Shoe @ 324'

120' balance plug using 14 sx Class "G" cement 60' above Uinta/Green River and extending 60' below (1527'-1647')

180' balance plug using 21 sx Class "G" cement 50' above Trona-Bird's Nest extending 50' below base of Mahogany Oil Shale (2851'-3031')

100' (12 sx) Class G Cement plug on top of CIBP CIBP @ 4120'

4778-4785' 4968-4974' 5080-5091'

4170-41821

5698-5706'

PBTD @ 5799'

TD @ 5825'

NEWFIELD

State 5-16-9-16
2043' FNL & 758' FWL
SWNW Section 16-T9S-R16E
Duchesne Co, Utah
API #43-013-33849; Lease #Utah State ML-16532

FORM 3160-5

UNITED STATES

August 2007) D SUNDR Do not use t abandoned w	Expires: July 31,2010 5. Lease Serial No. UTAH STATE ML-16532 6. If Indian, Allottee or Tribe Name.				
	TRIPLICATE - Other	r Instructions on page 2		7. If Unit or CA/A	greement, Name and/or
Type of Well Gas Well Other Name of Operator				8. Well Name and No. STATE 5-16-9-16	
a. Address Route 3 Box 3630 3b. Phone (include are code) Myton, UT 84052 435.646.3721				9. API Well No. 4301333849 10. Field and Pool, or Exploratory Area	
Location of Well (Footage, Sec., T., R., M., or Survey Description) 2043 FNL 758 FWL SWNW Section 16 T9S R16E				GREATER MB UNIT 11. County or Parish, State DUCHESNE, UT	
12. CHECH	APPROPRIATE BOX	(ES) TO INIDICATE NA	ATURE OF N		
TYPE OF SUBMISSION TYPE OF ACTION					
Notice of Intent Subsequent Report Final Abandonment	ce of Intent Alter Casing Fracture Treat Received Report Casing Repair Change Plans Plug & Abandon Ten		Reclamati Recomple Temporar Water Dis	ete ily Abandon sposal	Water Shut-Off Well Integrity Other
3. Describe Proposed or Completed O	peration: (Clearly state all pertinen	t details, including estimated starting	g date of any propos I true vertical depths	ed work and approxing of all pertinent marks	nate duration thereof. If the ers and zones. Attach the

Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final

Newfield Production proposes to convert the above mentioned well from producing oil well to an injection well.

RECEIVED SEP 07 2011

FORM APPROVED

DIV. OF OIL, GAS & MINING

I hereby certify that the foregoing is true and correct (Printed/ Typed)	Title Regulatory Technician			
Jill Lovle Signature	Date 09/01/2011			
THIS SPACE	FOR FEDERAL OR STATE OFFIC	RAL OR STATE OFFICE USE		
Approved by	Title	Date		
Conditions of approval, if any, are attached. Approval of this notice does certify that the applicant holds legal or equitable title to those rights in the which would entitle the applicant to conduct operations thereon.	subject lease Office	Office		
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a		to any department or agency of the United		

The Salt Lake Tribune



ACCOUNT NUMBER



· PROOF OF PUBLICATION

CUSTOMER NAME AND ADDRESS CEVED

CUSTOMER'S COPY

DATE

001 10 7011)/2011
1594 W NORTH TEMP #1210 P.O. BOX 145801 SALT LAKE CITY, UT 84114 22 72	116
ACCOUNT NAME	
DIV OF OIL-GAS & MINING,	
TELEPHONE ADORDER# / INVOICE NUMBER	
8015385340 0000732138 / BEFORE THE DIVISION OF CIL. DEPARTMENT OF PAUL STATE OF UTIL	GAS AND MINING . RESOURCES
SCHEDULE SCHEDULE SCHEDULE SCHEDULE NUTIE OF THE APPLICATION ON THE MATTER OF THE APPLICATION	
Start 10/08/2011 End 10/08/2011 in the MATTER OF THE APPLICATION TION COMPANY FOR ADMINISTRATIVE WELLS LOCATED IN SECTION 15, EAST, DUCHESNE COUNTY, UTAH	APPROVAL OF CERTAIN VNSHIP 9 SOUTH, RANGE AS CLASS II INJECTION
CUST, REF. NO. THE STATE OF UTAH TO ALL PERS ABOVE ENTITLED MATTER.	ONS INTERESTED IN THE
Legal Ad Legal Ad CAPTION Notice is hereby given that the Division is commencing proceeding to consider the application to company for administrative agreement to constitute the control of	on of Oil, Gas and Min- in informal adjudicative ion of Newfield Produc-
CAPTION Wells focated in Duchesne County, Class II Injection wells:	Utoh, for conversion to
BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RISIDER 5-16-9-16-9-16 well located in State 6-16-9-16 well located in State 1-16-9-16 well l	W/4 NW/4, Section 16, 43-013-33849 E/4 NW/4, Section 16,
SIZE SIZE South Range 1 South	43-013-33850 NE/4 SW/4, Section 16, 43-013-33851 NW/4 SW/4, Section 16.
The proceeding will be conducted	
RATE Solveted worse to the Green Plust R	uniotion will be pred for
water injection. The most man required on a representation of the most man required on a reason of the state	on fracture gradient in- duction Company.
MISC CHARGES AD CHARGES AD CHARGES Indistress in the proceeding, most fill to the proceeding of intervention of intervention to the proceeding of the pro	d written protest or no- within fifteen days fol- Division's Presiding Offi- Parmitting Manager, at
Any person desiring to object to the intervente in the proceeding, must fill tice of intervente with the business with the proceeding, must fill tice of intervention with the business. The car for the proceeding is breat fill. P.O. Sox 145801, 3ult lote CIII, number (801) 538-5340. If such a vention is received, a hearing with the deprendiction of the control of the proceeding is a first or vention is received, a hearing with the deprendiction of the control of the proceeding is the proceeding to breat fill.	IT 84114-5801, phone protest or notice of inter- be scheduled in accord-
TOTAL COST professional and/or interest and/or	s should be prepared to matter affects their in-
Dated this 5th day of October, 201 STATE OF UTAH DIVISION OF OIL, GAS & MINING	•
2250 RSC GGUICATION GF REFIDAVIT OF PUBLICATION Promitting Manager 732138	UPAXŁP
AS NEWSPAPER AGENCY COMPANY, LLC dba MEDIAONE OF UTAH LEGAL BOOKER, I CERTIFY THAT THE ATTACHED ADVERTISEMEN BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH NOTICE OF AGENC	T OF
CAUSE NO. UIC-380 IN THE MATTER OF THE APPLICA FOR DIV OF OIL-GAS & MINING, WAS PUBLISHED BY THE NEWSPAPER ACCOMPANY, LLC dba MEDIAONE OF UTAH, AGENT FOR THE SALT LAKE TRIBUNE AND DESERET NEWS, DAILY NEWSPAPERS PRINTED	BENCY
ENGLISH LANGUAGE WITH GENERAL CIRCULATION IN UTAH, AND PUBLISHED IN SALT LAKE CITY, SALT LAKE COUNTY IN THE STAT NOTICE IS ALSO POSTED ON UTAHLEGALS.COM ON THE SAME DAY AS THE FIRST NEWSPAPER PUBLICATION DATE AND REMAINS OF	E OF UTAH.
UTAHLEGALS.COM INDEFINATELY. Start 10/08/2011 End 10/08/2011	^~~
PUBLISHED ON VIGINIA CRAE Notary Public, State	of Utah 🕽
SIGNATURE Commission # 58 SIGNATURE SIGNATURE Commission # 58 My Commission # 58	culres }
10/10/2011 January 12, 20	
THIS IS NOT A STATEMENT BUT A "PROOF OF PUBLICATION"	

PLEASE PAY FROM BILLING STATEMENT

AFFIDAVIT OF PUBLICATION


County of Duchesne, STATE OF UTAH

I, Kevin Ashby on oath, say that I am the PUBLISHER of the Uintah Basin Standard, a weekly newspaper of general circulation, published at Roosevelt, State and County aforesaid, and that a certain notice, a true copy of which is hereto attached, was published in the full issue such newspaper for ______/ consecutive issues, and that the first publication was on the ____// day of ______, 20 //__, and that the last publication of such notice was in the issue of such newspaper dated the ___// day of ______, 20 _//__, and that said notice was published on Utahlegals. com on the same day as the first newspaper publication and the notice remained on Utahlegals.com until the end of the scheduled run.

Subscribed and sworn to before me this

17 day of October, 20 11

Notary Public



BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES THE OF UTAH NOTICE OF AGENCY ACTION CAUSE NO. UIC-380

IN THE MATTER OF THE APPLICATION OF NEWFIELD PRODUCTION COMPANY FOR ADMINISTRATIVEAP-PROVAL OF CERTAIN WELLS LOCATED IN SECTION 16, TOWN-SHIP9 SOUTH, RANGE 16 EAST, DUCHESNE COUNTY, UTAH, AS CLASS II INJECTION WELLS.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER;

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Production Company for administrative approval of the following wells located in Duchesne County, Utah, for conversion to Class II injection wells:

Greater Monument Butte Unit:

State 5-16-9-16 well located in SW/4 NW/4, Section 16, Township 9 South, Range 16 East API 43-013-33849

State 6-16-9-16 well located in SE/4 NW/4, Section 16, Township 9 South, Range 16 East API 43-013-33850

State 11-16-9-16 well located in NE/4 SW/4, Section 16, Township 9 South, Range 16 East API 43-013-33851

State 12-16-9-16 well located in NW/4 SW/4, Section 16, Township 9 South Range 16 East API

this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Permitting Manager, at P.O. Box 145801, Salt Lake City, UT 84114-5801, phone number (801) 538-5340. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedural rules. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 5th day of October, 2011.

STATE OF UTAH DIVISION OF. OIL, GAS & MINING

Published in the Uintah Basin Standard October 11, 2011.

BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH NOTICE OF AGENCY ACTION CAUSE NO. UIC-380

IN THE MATTER OF THE APPLICATION OF NEWFIELD PRODUCTION COMPANY FOR ADMINISTRATIVE APPROVAL OF CERTAIN WELLS LOCATED IN SECTION 16, TOWNSHIP 9 SOUTH, RANGE 16 EAST, DUCHESNE COUNTY, UTAH, AS CLASS II INJECTION WELLS.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Production Company for administrative approval of the following wells located in Duchesne County, Utah, for conversion to Class II injection wells:

Greater Monument Butte Unit:

State 5-16-9-16 well located in SW/4 NW/4, Section 16, Township 9 South, Range 16 East API 43-013-33849 State 6-16-9-16 well located in SE/4 NW/4, Section 16, Township 9 South, Range 16 East API 43-013-33850 State 11-16-9-16 well located in NE/4 SW/4, Section 16, Township 9 South, Range 16 East API 43-013-33851 State 12-16-9-16 well located in NW/4 SW/4, Section 16, Township 9 South, Range 16 East API 43-013-33852

The proceeding will be conducted in accordance with Utah Admin. R649-10, Administrative Procedures.

Selected zones in the Green River Formation will be used for water injection. The maximum requested injection pressures and rates will be determined based on fracture gradient information submitted by Newfield Production Company.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Permitting Manager, at P.O. Box 145801, Salt Lake City, UT 84114-5801, phone number (801) 538-5340. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedural rules. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 5th day of October, 2011.

STATE OF UTAH

DIVISION OF OIL, GAS & MINING

Brad Hill

Permitting Manager

Newfield Production Company

STATE 5-16-9-16, STATE 6-16-9-16, STATE 11-16-9-16, STATE 12-16-9-16

Cause No. UIC-380

Publication Notices were sent to the following:

Newfield Production Company 1001 17th Street, Suite 2000 Denver, CO 80202

Uintah Basin Standard 268 South 200 East Roosevelt, UT 84066 via e-mail legals@ubstandard.com

Salt Lake Tribune P O Box 45838 Salt Lake City, UT 84145 via e-mail naclegal@mediaoneutah.com

Vernal Office Bureau of Land Management 170 South 500 East Vernal, UT 84078 Duchesne County Planning P O Box 317 Duchesne, UT 84021-0317

Bruce Suchomel US EPA Region 8 MS 8P-W-GW 1595 Wynkoop Street Denver, CO 80202-1129

SITLA 675 East 500 South Salt Lake City, UT 84102-2818

Newfield Production Company Rt 3 Box 3630 Myton, UT 84052

Jan Sulet



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

October 5, 2011

Via e-mail: legals@ubstandard.com

Uintah Basin Standard 268 South 200 East Roosevelt, UT 84066

Subject: Notice of Agency Action - Newfield Production Company Cause No. UIC-380

To whom it may concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please <u>notify me via e-mail of the date it will be published</u>. My e-mail address is: <u>jsweet@utah.gov</u>.

Please send proof of publication and billing to:

Division of Oil, Gas and Mining PO Box 145801 Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet

Executive Secretary

Enclosure





State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

October 5, 2011

VIA E-MAIL naclegal@mediaoneutah.com

Salt Lake Tribune P. O. Box 45838 Salt Lake City, UT 84145

Subject: Notice of Agency Action - Newfield Production Company Cause No. UIC-380

To whom it may concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please <u>notify me via e-mail of the date it will be published</u>. My e-mail address is: <u>jsweet@utah.gov</u>.

Please send proof of publication and billing for account #9001402352 to:

Division of Oil, Gas and Mining PO Box 145801 Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet

Executive Secretary

Enclosure



Jean Sweet - Re: Notice of Agency Action - Newfield Production Company Cause No. UIC-380

From:

Cindy Kleinfelter <classifieds@ubstandard.com>

To:

Jean Sweet <jsweet@utah.gov>

Date:

10/5/2011 1:26 PM

Subject: Re: Notice of Agency Action – Newfield Production Company Cause No. UIC-380

On 10/5/2011 12:00 PM, Jean Sweet wrote:

To whom it may concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please <u>notify me via e-mail of the date it will be published</u>. My e-mail address is: jsweet@utah.gov.

Please send proof of publication and billing to:

Division of Oil, Gas and Mining PO Box 145801 Salt Lake City, UT 84114-5801


Sincerely,

Jean Sweet, Executive Secretary Utah Div. of Oil, Gas & Mining 1594 West Temple, Suite 1210 Salt Lake City, UT 801-538-5329 jsweet@utah.gov

Received. Thank you. It will be published Oct. 11, 2011. Cindy







Remit to: P.O. Box 704005 West Valley City, UT 84170

Order Confirmation for Ad #0000732138-01

Client

DIV OF OIL-GAS & MINING

Payor Customer

DIV OF OIL-GAS & MINING

Client Phone

801-538-5340

Payor Phone

801-538-5340

Account#

9001402352

Payor Account

9001402352

Address

1594 W NORTH TEMP #1210.P.O. BOX 145801 Payor Address SALT LAKE CITY, UT 84114 USA

1594 W NORTH TEMP #1210.P.O. BOX

SALT LAKE CITY, UT 84114

Fax

801-359-3940

Ordered By

Acct. Exec

EMail

earlenerussell@utah.gov

Jean

mfultz

Total Amount

Amount Due

\$157.50

Payment Amt \$0.00

Tear Sheets

Proofs

Affidavits

\$157.50 O O

PO Number Legal Ad

1

Payment Method Confirmation Notes:

Text:

Jean Ad Type

Ad Size

Color

2.0 X 61 Li

<NONE>

Product

Legal Liner

Placement Salt Lake Tribune::

Legal Liner Notice - 0998

10/08/2011 Scheduled Date(s):

Product

Placement

sltrib.com::

Legal Liner Notice - 0998

10/08/2011 Scheduled Date(s):

Product

Placement

10/08/2011

utahlegals.com:: utahlegals.com

Scheduled Date(s):

Position

Public Meeting/Hear-ing Notices

Position

Public Meeting/Hear-ing Notices

Position

utahlegals.com

Ad Content Proof Actual Size

BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH NOTICE OF AGENCY ACTION CAUSE NO. UIC-380

IN THE MATTER OF THE APPLICATION OF NEWFIELD PRODUC-TION COMPANY FOR ADMINISTRATIVE APPROVAL OF CERTAIN WELLS LOCATED IN SECTION 16, TOWNSHIP 9 SOUTH, RANCE 16 EAST, DUCHESNE COUNTY, UTAH, AS CLASS II INJECTION WELLS.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Min-ing (the "Division") is commercing an informal adjudicative proceeding to consider the application of NewHeild Pradic-tion Company for administrative approval of the following wells located in Duckeste County, Utah, for conversion to Class II injection wells:

Greater Morumert Butte Unit:
Store 5-16-9-16 well locared in SW/4 NW/4, Section 16,
Township 9 South, Range 16 East API 43-013-33849
Store 6-16-9-16 well locared in SE/4 NW/4, Section 16,
Township 9 South, Range 16 East API 43-013-33850
Store 11-16-9-16 well locared in NE/4 SW/4, Section 16,
Township 9 South, Range 16 East API 43-013-33851
Store 12-16-9-16 well located in NW/4 SW/4, Section 16,
Township 9 South, Range 16 East API 43-013-33852

The proceeding will be conducted in accordance with Utah Admin. R649-10, Administrative Procedures.

Selected zores in the Green River Formation will be used for water injection. The maximum requested injection pressures and rares will be determined based on fracture gradient information submitted by Newfield Production Company.

Any person destring to object to the application or otherwise intervene in the proceeding, must file a written protest or rotice of intervention with the Division within fifteen days following publication of this rotice. The Division's Presiding Officer for the proceeding is Brod Hill, Permitting Manager, or P.O. Box 145801, Solt Loke City, UT 84114-5801, point concernible (801) 538-5340. If such a protest or rotice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedural rules. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 5th day of October, 2011.

STATE OF UTAH DIVISION OF OIL, GAS & MINING

/s/ Brod Hill

Permitting Manager 732138

UPAXLP



Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

April 19, 2012

Newfield Production Company 1001 Seventeenth Street, Suite 2000 Denver, CO 80202

Subject: Greater Monument Butte Unit Well: State 5-16-9-16, Section 16, Township 9 South, Range 16 East,

SLBM, Duchesne County, Utah, API Well #43-013-33849

Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

- 1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
- 2. Conformance with all conditions and requirements of the complete application submitted by Newfield Production Company.
- 3. A casing tubing pressure test shall be conducted prior to commencing injection.
- 4. Pressure shall be monitored between the surface casing and the production casing on a regular basis. Any pressure changes observed shall be reported to the Division immediately.
- 5. The top of the injection interval shall be limited to a depth no higher than 3,997 feet in the State 5-16-9-16 well.

A final approval to commence injection will be issued upon satisfactory completion of the listed stipulations. If you have any questions regarding this approval or the necessary requirements, please contact Mark Reinbold at 801-538-5333 or Brad Hill at 801-538-5315.

Sincerely

John Rogers

Associate Director

JR/MLR/js

cc: Bruce Suchomel, Environmental Protection Agency

Bureau of Land Management, Vernal

SITLA


Duchesne County


Newfield Production Company, Myton

Well File

N:\O&G Reviewed Docs\ChronFile\UIC







DIVISION OF OIL, GAS AND MINING UNDERGROUND INJECTION CONTROL PROGRAM PERMIT STATEMENT OF BASIS

Applicant: N	ewfield Production C	ompany Well:	State 5-16-9-16	
Location:	16/9S/16E	API:	43-013-33849	

Ownership Issues: The proposed well is located on State of Utah land. The well is located in the Greater Monument Butte Unit. Lands in the one-half mile radius of the well are administered by the State of Utah and the BLM. The State of Utah and the Federal Government are the mineral owners within the area of review (AOR). Newfield and other various individuals hold the leases in the unit. Newfield has provided a list of all surface, mineral and leaseholders in the half-mile radius. Newfield is the operator of the Greater Monument Butte Unit. Newfield has submitted an affidavit stating that all owners and interest owners have been notified of their intent.

Well Integrity: The proposed well has surface casing set at 324 feet and has a cement top at the surface. A 5½ inch production casing is set at 5,825 feet. A cement bond log demonstrates adequate bond in this well up to about 3,144 feet. A 2 7/8 inch tubing with a packer will be set at 4,120 feet. Higher perforations will be opened at a later date. A mechanical integrity test will be run on the well prior to injection. On the basis of surface location, there are 11 producing wells in the AOR. One of the producing wells is a horizontal well, with a surface location inside the AOR and a bottom hole location outside the AOR. All wells within the AOR have evidence of adequate casing and cement for the proposed injection interval.

Ground Water Protection: As interpreted from Technical Publication No. 92, the base of moderately saline water is at a depth of approximately 2300 feet. Injection shall be limited to the interval between 3,997 feet and 5,799 feet in the Green River Formation. Information submitted by Newfield indicates that the fracture gradient for the 5-16-9-16 well is 0.90 psi/ft., which was the lowest reported fracture gradient for the injection zone. The resulting minimum fracture pressure for the proposed injection interval is 1,902 psig. The requested maximum pressure is 1,902 psig. The anticipated average injection pressure is 1100 psig. Injection at this pressure should not initiate any new fractures or propagate existing fractures in the adjacent confining intervals. Any groundwater present should be adequately protected.

State 5-16-9-16 page 2

Oil/Gas& Other Mineral Resources Protection: The Board of Oil, Gas & Mining approved the Greater Monument Butte Unit on December 1, 2009. Correlative rights issues were addressed at this time. Previous reviews in this area indicate that other mineral resources in the area have been protected or are not at issue.

Bonding: Bonded with the State of Utah

Actions Taken and Further Approvals Needed: A notice of agency action has been sent to the Salt Lake Tribune and the Uinta Basin Standard. A casing/tubing pressure test will be required prior to injection. It is recommended that approval of this application be granted.

Note: Applicable technical publications concerning water resources in the general vicinity of this project have been reviewed and taken into consideration during the permit review process.

Reviewer(s)	Mark Reinbold	Date	10/26/2011
Keviewensi.	IVIAIR IXCIIIDUIU	Date	10/20/2011

Sundry Number: 32914 API Well Number: 43013338490000

			FORM 9
STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES			
DIVISION OF OIL, GAS, AND MINING			5.LEASE DESIGNATION AND SERIAL NUMBER: ML-16532
SUNDF	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.			7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)
1. TYPE OF WELL Oil Well			8. WELL NAME and NUMBER: STATE 5-16-9-16
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	OMPANY		9. API NUMBER: 43013338490000
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT	, 84052 435 646-48	PHONE NUMBER: 25 Ext	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2043 FNL 0758 FWL			COUNTY: DUCHESNE
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNW Section: 16 Township: 09.0S Range: 16.0E Meridian: S			STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICA	ATE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
The subject well he injection well on 1 State of Utah DOG above listed well. Opsig and charted for injecting during the	□ change to previous plans	producing oil well to an 2 Chris Jensen with the ng the initial MIT on the ras pressured up to 1270 are loss. The well was not was 250 psig during the	Accepted by the Utah Division of Oil, Gas and Mining Date: December 12, 2012 By:
NAME (PLEASE PRINT) Lucy Chavez-Naupoto SIGNATURE N/A	PHONE NUM 435 646-4874		

Sundry Number: 32914 API Well Number: 43013338490000

Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company Rt. 3 Box 3630 Myton, UT 84052 435-646-3721

ally Bag		Time / !so	am pi
		•	
-16	Field: Wone	ment Butte	
	API No: 43013	333 849	
Time	Casing Pressure		
		psia	
-		•	
-			
-			
-			

25 _ 30 min	17.70	psig	
	Time 0 min 5 10 15 20 25	Field: Wone API No: 4301 Time Casing Pressure 0 min 1270 10 1270 15 1270 20 1270 25 1270	Field: Wonument Butte API No: 4301333849 Time Casing Pressure O min

Tubing pressure: 250 psig

Result:

40

45

50

55

60 min

Pass

Fail

psig

psig

psig

psig


psig

Signature of Witness:

Signature of Person Conducting Test:

What I

Sundry Number: 32914 API Well Number: 43013338490000



Sundry Number: 32914 API Well Number: 43013338490000
Summary Rig Activity Page 1 of 3

Daily Activity Report

Format For Sundry STATE 5-16-9-16 9/1/2012 To 1/30/2013

11/19/2012 Day: 1

Conversion

Nabors #1450 on 11/19/2012 - MIRUSU, pull rods - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN - spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN - spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - bleed well, CSG 100 PSI, TBG 0 PSI, rig maintainance LD 114 3/4" 4 per, 93 3/4" slick, 6 wt bars, & pump, stopped twice & flushed w/ 20 bbl each time XO to TBG equip, ND WH flange, unset TAC, NU BOP's, RU floor, RU tongs POOH w/ 30 stands, breaking, cleaning, & doping colars SWI, clean up for the night - spot rig, post trips, prep to RU, RU, pull head. unseat pump, flush rods w/ 30 bbl, soft seat & test, had to beat on pump to unseat it. LD 30 3/4 4 per, PU polish rod. SDFN

Finalized
Daily Cost: \$0

Cumulative Cost: \$13,709

11/20/2012 Day: 3

Conversion

Nabors #1450 on 11/20/2012 - POOH w/ 36 stands, breaking, cleaning, & doping colars on the way out, LD 43 joints - Travel time, start rig, morning meeting. Other, bleed well, CSG 250 PSI TBG PSI, rig maintainance, derrick inspection. POOH w/ 36 stands, breaking, cleaning, & doping colars on the way out, LD 43 joints. Make up BHA, 2 3/8" XN, 2 3/8" x 4' sub, 2 3/8" x 2 7/8" XO, 5 1/2" x 2 7/8" PKR, on/off tool, 2 7/8" S/N, 131 joints. pump 10 bbl pad, drop valve, fill TBG w/ 25 bbl, pumped TBG upto 3000 PSI, RU sandline, TBG droped to 2600 PSI in 15 min, bumped back up to 3000 PSI, droped to 2600 PSI in 15 min, bumped back upto 3000 PSI, droped to 2800 PSI in 15 min, pulled test tee, redoped and retightened tee, pump TBG upto 3000 PSI, held for 30 min, good test. fish valve, RD sandline. SWI, clean

Sundry Number: 32914 API Well Number: 43013338490000 Page 2 of 3 Summary Rig Activity

up for the night. - Travel time, start rig, morning meeting. Other, bleed well, CSG 250 PSI TBG PSI, rig maintainance, derrick inspection. POOH w/ 36 stands, breaking, cleaning, & doping colars on the way out, LD 43 joints. Make up BHA, 2 3/8" XN, 2 3/8" x 4' sub, 2 3/8" x 2.7/8" XO, 5.1/2" x 2.7/8" PKR, on/off tool, 2.7/8" S/N, 131 joints. pump 10 bbl pad, drop valve, fill TBG w/ 25 bbl, pumped TBG upto 3000 PSI, RU sandline, TBG droped to 2600 PSI in 15 min, bumped back up to 3000 PSI, droped to 2600 PSI in 15 min, bumped back upto 3000 PSI, droped to 2800 PSI in 15 min, pulled test tee, redoped and retightened tee, pump TBG upto 3000 PSI, held for 30 min, good test. fish valve, RD sandline. SWI, clean up for the night. - Travel time, start rig, morning meeting. Other, bleed well, CSG 250 PSI TBG PSI, rig maintainance, derrick inspection. POOH w/ 36 stands, breaking, cleaning, & doping colars on the way out, LD 43 joints. Make up BHA, 2 3/8" XN, 2 3/8" x 4' sub, 2 3/8" x 2 7/8" XO, 5 1/2" x 2 7/8" PKR, on/off tool, 2 7/8" S/N, 131 joints. pump 10 bbl pad, drop valve, fill TBG w/ 25 bbl, pumped TBG upto 3000 PSI, RU sandline, TBG droped to 2600 PSI in 15 min, bumped back up to 3000 PSI, droped to 2600 PSI in 15 min, bumped back upto 3000 PSI, droped to 2800 PSI in 15 min, pulled test tee, redoped and retightened tee, pump TBG upto 3000 PSI, held for 30 min, good test. fish valve, RD sandline. SWI, clean up for the night.

Daily Cost: \$0

Cumulative Cost: \$27,910

11/21/2012 Day: 4

Conversion

Nabors #1450 on 11/21/2012 - Nu wellhead, pressure test - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - move different rig on to fish out tools move different rig on to fish out tools - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - move different rig on to fish out tools - move different rig on to fish out tools - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - RD tongs and floor, ND BOP's, Nu wellhead and flange, pump pkr fluid, set pkr w/15000# tension. Fill csg w/ 30 bbl, pressure up to 1400psi, held for 30 min, good test. - move different rig on to fish out tools - move different rig on to fish out tools Finalized

Daily Cost: \$0

Cumulative Cost: \$38,945

11/27/2012 Day: 6

Conversion

Nabors #1450 on 11/27/2012 - MIRU, TOOH W/131 JTS S&N on/off TOOL 70 - Crew Traval & safety Meeting . RD Rig road rig from 3-23-9-16 to 5-16-9-16, MIRU, SICP 1350 Bleed off casing bleed off tubing for 1 1/2 hours, tbg release off packer NU BOP RU tbg EQ TOOH W/131 its SN& on/off TOOL W/ 70 its Completely solid with oil did not find gyro tools TIH W/tbg string W/ bit & scraper on bottom flushing pluged jts did not find gyro - Crew Traval & safety Meeting, RD Rig road rig from 3-23-9-16 to 5-16-9-16, MIRU, SICP 1350 Bleed off casing bleed off tubing for 1 1/2 hours, tbg release off packer NU BOP RU tbg EQ TOOH W/131 jts SN& on/off TOOL W/ 70 jts Completely solid with oil did not find gyro tools TIH W/tbg string W/ bit & scraper on bottom flushing pluged jts did not find gyro - Crew Traval & safety Meeting . RD Rig road rig from 3-23-9-16 to 5-16-9-16, MIRU, SICP 1350 Bleed off casing bleed off tubing for 1 1/2 hours, tbg release off packer NU BOP RU tbg EQ TOOH W/131 jts SN& on/off TOOL W/70 its Completely solid with oil did not find gyro tools TIH W/tbg string W/ bit & scraper on bottom flushing pluged jts did not find gyro

Sundry Number: 32914 API Well Number: 43013338490000
Summary Rig Activity
Page 3 of 3

Daily Cost: \$0

Cumulative Cost: \$49,676

11/29/2012 Day: 7

Conversion

Nabors #1450 on 11/29/2012 - Pressure test TBG & CSG, Tested good - Crew training and safety meeting, TIH W/ 2 3/8 re-entry / Giude ,2 3/8 Xn nipple 2 3/8 TBG sub 2 3/8 x2 7/8 x over, 5 1/2 as-z1 packer ,on/off TOOL, 2 7/8 SN 60 JTS flush TBG W/ 30 BW TIH W/ 71 more JTS 2 7/8 J-55 TBG pump 30 BW Drop SV psi test tbg to 3000 psi W/40 more bbls hold for 45 minutes good test BET SV W/ sand line, RU VES & gyro well RD work floor ND BOP Set PKR @ 4,128' for 16000 tension SV @ 41723' Xn @ 4136 EOT @ 4138' land tbg W/injection tree mix 15 gal pkr fliud W/ 60 bbls fresh H20 psi CSG to 1500psi W/ 50 bbls lost 100 psi & held good @ 1400 psi 30 min took 1 1/2 hr to get good test Rd and ready to road. - Crew training and safety meeting, TIH W/ 2 3/8 re-entry / Giude ,2 3/8 Xn nipple 2 3/8 TBG sub 2 3/8 x2 7/8 x over, 5 1/2 as-z1 packer ,on/off TOOL, 2 7/8 SN 60 JTS flush TBG W/ 30 BW TIH W/ 71 more JTS 2 7/8 J-55 TBG pump 30 BW Drop SV psi test tbg to 3000 psi W/40 more bbls hold for 45 minutes good test BET SV W/ sand line , RU VES & gyro well RD work floor ND BOP Set PKR @ 4,128' for 16000 tension SV @ 41723' Xn @ 4136 EOT @ 4138' land tbg W/injection tree mix 15 gal pkr fliud W/ 60 bbls fresh H20 psi CSG to 1500psi W/ 50 bbls lost 100 psi & held good @ 1400 psi 30 min took 1 1/2 hr to get good test Rd and ready to road. - Crew training and safety meeting, TIH W/ 2 3/8 re-entry / Giude ,2 3/8 Xn nipple 2 3/8 TBG sub 2 3/8 x2 7/8 x over, 5 1/2 as-z1 packer ,on/off TOOL, 2 7/8 SN 60 JTS flush TBG W/ 30 BW TIH W/ 71 more JTS 2 7/8 J-55 TBG pump 30 BW Drop SV psi test tbg to 3000 psi W/40 more bbls hold for 45 minutes good test BET SV W/ sand line, RU VES & gyro well RD work floor ND BOP Set PKR @ 4,128' for 16000 tension SV @ 41723' Xn @ 4136 EOT @ 4138' land tbg W/injection tree mix 15 gal pkr fliud W/ 60 bbls fresh H20 psi CSG to 1500psi W/ 50 bbls lost 100 psi & held good @ 1400 psi 30 min took 1 1/2 hr to get good test Rd and ready to road. Finalized

Daily Cost: \$0

Cumulative Cost: \$56,304

12/3/2012 Day: 8

Conversion

Rigless on 12/3/2012 - Conduct initial MIT - On 11/20/2012 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 11/29/2012 the casing was pressured up to 1270 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 250 psig during the test. There was not a State representative available to witness the test. - On 11/20/2012 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 11/29/2012 the casing was pressured up to 1270 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 250 psig during the test. There was not a State representative available to witness the test. - On 11/20/2012 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 11/29/2012 the casing was pressured up to 1270 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 250 psig during the test. There was not a State representative available to witness the test. **Finalized**

Daily Cost: \$0

Cumulative Cost: \$138,638

Pertinent Files: Go to File List

Sundry Number: 36845 API Well Number: 43013338490000

STATE OF UTAH				FORM 9	
DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING				5.LEASE DESIGNATION AND SERIAL NUMBER: ML-16532	
SUNDRY NOTICES AND REPORTS ON WELLS			6. IF INDIAN, ALLOTTEE OR TRIBE NAME:		
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.				7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)	
1. TYPE OF WELL Water Injection Well				8. WELL NAME and NUMBER: STATE 5-16-9-16	
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	DMPANY			9. API NUMBER: 43013338490000	
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT	, 84052 435 646-48		NE NUMBER: t	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2043 FNL 0758 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNW Section: 16 Township: 09.0S Range: 16.0E Meridian: S				COUNTY: DUCHESNE	
			S	STATE: UTAH	
11. CHEC	K APPROPRIATE BOXES TO INDIC	ATE N	ATURE OF NOTICE, REPOR	T, OR OTHER DATA	
TYPE OF SUBMISSION			TYPE OF ACTION		
	ACIDIZE		ALTER CASING	CASING REPAIR	
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS		CHANGE TUBING	CHANGE WELL NAME	
Approximate date work will start.	✓ CHANGE WELL STATUS		COMMINGLE PRODUCING FORMATIONS	✓ CONVERT WELL TYPE	
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	☐ F	RACTURE TREAT	NEW CONSTRUCTION	
4/12/2013	OPERATOR CHANGE	F	PLUG AND ABANDON	PLUG BACK	
SPUD REPORT	PRODUCTION START OR RESUME	F	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION	
Date of Spud:	REPERFORATE CURRENT FORMATION		SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON	
_	TUBING REPAIR		ENT OR FLARE	WATER DISPOSAL	
DRILLING REPORT Report Date:	WATER SHUTOFF		SI TA STATUS EXTENSION	APD EXTENSION	
	WILDCAT WELL DETERMINATION		OTHER	OTHER:	
12. DESCRIBE PROPOSED OR	COMPLETED OPERATIONS. Clearly sho	w all pe	rtinent details including dates, d	epths, volumes, etc.	
The above ref	erence well was put on inje 04/12/2013.	ection	at 1:30 PM on	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 19, 2013	
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUM 435 646-4874		TITLE Water Services Technician		
SIGNATURE DATE			DATE 4/19/2013		
N/A			7/13/2013		

State 5-16-9-16 Spud Date: 04-07-08 Put on Production: 05-14-08 GL: 5922' KB: 5934' Injection Wellbore Diagram SURFACE CASING CSG SIZE: 8-7/8" GRADE: J-55 Cement Top@ 70 WEIGHT 24#

FRAC JOB 05-07-08 5698-5706 Frac CP3 sands as follows: Frac with 34586 #'s of 20/40 sand in 434 bbls of Lightning 17 fluid Treat at an ave pressure of 1941 psi @ 23 2 BPM. ISIP 2046 psi Casing Shoe @ 324' 05-07-08 5334-5342 Frac LODC sands as follows: Frac with 24721 #'s of 20/40 sand in 348 bbls of Lightning 17 fluid. Treat at an ave pressure of 2425 psi @ 23.2 BPM ISIP 2165 psi Frac A.5 sands as follows: 05-07-08 5080-50913 Frac with 84098 #'s of 20/40 sand in 666 bbls of Lightning 17 fluid. Treat at an ave pressure of 2065 psi @ 23.2 BPM ISIP 2582 psi 05-07-08 4968-4974 Frac B2 sand as follows: Frac with 24764 #'s of 20/40 sand in 354 bbls of Lightning 17 fluid. Treat at an ave pressure of 3365 psi @ 23.3 BPM ISIP 2959 psi 05-07-08 4778-4785' Frac D2 sands as follows: Frac with 24664 #'s of 20/40 sand in 341 bbls Lightning of 17 fluid Treat at an ave pressure of 1975 psi @ 23.3 BPM. CEMENT DATA: 300 sk Prem. Lite II mixed & 400 sxs 50/50 POZ. ISIP 2279 psi 05-07-08 4170-4182' Frac GB4 sands as follows: Frac with 59402 #'s of 20/40 sand in 511 bbls of Lightning 17 fluid Treat at an ave pressure of 1805 psi @ 23.3 BPM. ISIP 1929 psi 12-18-09 Pump Change. Update rod and tubing 11/28/12 Convert to Injection Well 11/29/12 Conversion MIT Finalized - update tbg

TUBING SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5# NO OF JOINTS: 131 jts (4110.1') SEATING NIPPLE: 2-7/8" (1_10') SN LANDED AT: 4122.1' KB ON/OFF TOOL AT: 4123.2' ARROW #1 PACKER CE AT: 4129 XO 2-3/8 x 2-7/8 J-55 AT: 4132' TBG PUP 2-3/8 J-55 AT: 4132.5* X/N NIPPLE AT: 4136.7' TOTAL STRING LENGTH: EOT @ 4138'

LENGTH: 7 jts. (312 48')

DEPTH LANDED: 324'

CEMENT DATA: 160 sxs Class "G" cmt

PRODUCTION CASING CSG SIZE: 5-1/2"

LENGTH: 139jts. (5807.48')

DEPTH LANDED: 5820 73'

HOLE SIZE: 12-1/4"

GRADE: J-55 WEIGHT: 15.5#

HOLE SIZE: 7-7/8"

CEMENT TOP AT: 70'

X/N Nipple @ 4137' EOT @ 4138' 4170-4182' 4778-4785 4968-4974 5080-5091 5334-5342 5698-5706 PBTD @ 5799' TD @ 5825'

SN @ 4122'

Packer @ 4129'

On Off Tool @ 41231

PERFORATION RECORD 4170-4182' 4 JSPF

4778-4785' 4 JSPF 4968-4974' 4 JSPF 28 holes 24 holes 5080-5091 4 JSPF 44 holes 5334-5342' 4 JSPF 32 holes 5698-5706 4 JSPF 32 holes



State 5-16-9-16 2043' FNL & 758' FWL SWNW Section 16-T9S-R16E Duchesne Co, Utah API #43-013-33849; Lease #ML-16532



Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA

Division Director

UNDERGROUND INJECTION CONTROL PERMIT

Cause No. UIC-380

Operator:

Newfield Production Company

Well:

State 5-16-9-16

Location:

Section 16, Township 9 South, Range 15/East

County:

Duchesne

API No.:

43-013-33849

Well Type:

Enhanced Recovery (waterflood)

Stipulations of Permit Approval

- Approval for conversion to Injection Well issued on April 19, 2012. 1.
- 2. Maximum Allowable Injection Pressure: 1,902 psig
- Maximum Allowable Injection Rate: (restricted by pressure limitation) 3.
- 4. Injection Interval: Green River Formation (3,997' – 5,799')
- Any subsequent wells drilled within a ½ mile radius of this well shall have 5. production casing cement brought up to or above the top of the unitized interval for the Greater Monument Butte Unit.

Approved by:

ssociate Director

cc: Bruce Suchomel, Environmental Protection Agency

Bureau of Land Management, Vernal

Eric Sundberg, Newfield Production Company, Denver

Newfield Production Company, Myton

Duchesne County

Well File

N:\O&G Reviewed Docs\ChronFile\UIC

1594 West North Temple, Suite 1210, PO Box 145801, Salt Lake City, UT 84114 -5801 telephone (801) 538-5340 • facsimile (801) 359-3940 • TTY (801) 538-7458 • www.ogm.utah.gov

